

Enquiries: Xavier Dubreuil
Direct 07 5433 2739
Our Ref: DA/2023/3491
Your Ref: 22-000082_1A-1B
Date: 24 October 2023

Foreverlen Pty Ltd PO Box 5233 BRISBANE QLD 4001

Dear Applicant,

Re: DEVELOPMENT APPROVAL

Planning Act 2016

Development Application No.: DA/2023/3491

Property Location: 409-423 Caboolture River Road LILYWOOD

403 Caboolture River Road UPPER CABOOLTURE

Property Description: Lot 1 RP 866105

Lot 12 RP 866105

Development Type: Operational Works - Development Permit for

Roadworks, Stormwater and Earthworks (Lilywood

Landings, Stage 1A & 1B)

Please be advised that on 23 October 2023 the above development application was approved by Council's Delegate as the Assessment Manager in accordance with section 63 of the *Planning Act 2016* subject to conditions.

The following type of approval has been issued:

• Development Permit - Operational Works for Roadworks, Stormwater & Earthworks

The development allowed by this approval must be carried out in accordance with the attached Decision package.

Attached is an extract from the *Planning Act 2016* which details your appeal rights and the appeal rights of any submitters, if applicable, regarding this decision.

Should you require any further information about this matter, please contact Xavier Dubreuil as referenced above.

Yours faithfully

Xavier Dubreuil
Senior Engineer
Development Services

Enclosures: Attachment 1 - Decision Notice

Attachment 2 - Assessment Manager Conditions
Attachment 3 - Approved Plans / Documents
Attachment 4 - Appeal Rights
Attachment 5 - Infrastructure Charges

Сс Unitywater

Development.Services@Unitywater.com

ATTACHMENT 1

Decision Notice

Decision Notice

Planning Act 2016, section 63

APPL	IC	TI		M I	רםר	$\Gamma \Lambda I$	II C
AFFL	.16/	۱ı	VI	N I	JE	М	LJ

Application No: DA/2023/3491

Applicant: Foreverlen Pty Ltd

Street Address: 409-423 Caboolture River Road LILYWOOD

403 Caboolture River Road UPPER CABOOLTURE

Real Property Description: Lot 1 RP 866105 Lot 12 RP 866105

Planning Scheme: Moreton Bay Regional Council Planning Scheme

APPROVAL DETAILS

Date of Decision: 23 October 2023

The development application was approved by Council's Delegate as the Assessment Manager subject to conditions (refer Attachment 2).

Application Type	Development Permit	Preliminary Approval
Operational Works for Roadworks, Stormwater and Earthworks	V	

OTHER NECESSARY PERMITS

Not applicable.

In addition to this approval, you may also be required to obtain a water approval from the Northern SEQ Distributor Retailer, trading as Unitywater. To engage a Registered Certifier to lodge your connection application, go to Unitywater's website www.unitywater.com/certifier

CURRENCY PERIOD OF APPROVAL

The currency period stated in section 85 of the *Planning Act 2016* applies to this approval as outlined below:

Operational Works - 2 years from the date of this approval starts to have effect.

DEEMED APPROVAL

Not applicable.

VARIATION APPROVAL

Not applicable.

INFRASTRUCTURE

Unless otherwise specified, all assessment manager conditions of this development approval relating to the provision of infrastructure are non-trunk infrastructure conditions under Chapter 4, section 145 of the *Planning Act 2016*.

ASSESSMENT MANAGER CONDITIONS

The Conditions relevant to this development approval are listed in Attachment 2 of the Decision package.

APPROVED PLANS / DOCUMENTS

The approved plans and/or documents as listed below for this development approval are included in Attachment 3 of the Decision package.

The approved plans/documents for this development approval are listed below.

Approved Plans and Documents				
Plan / Document Name	Reference Number	Prepared By	Dated	
Title Sheet & Locality Plan	22-000082_1A-1B Dwg. 1000 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Site Layout Plan	22-000082_1A-1B Dwg. 1100 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Retaining Wall Setout Plan Sheet 1 of 2	22-000082_1A-1B Dwg. 1200 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Retaining Wall Setout Plan Sheet 2 of 2	22-000082_1A-1B Dwg. 1201 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Retaining Wall Notes and Details	22-000082_1A-1B Dwg. 1202 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Control Line Setout Plan Sheet 1 of 2	22-000082_1A-1B Dwg. 1300 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Control Line Setout Plan Sheet 2 of 2	22-000082_1A-1B Dwg. 1301 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Roadworks Layout Plan Sheet 1 of 5	22-000082_1A-1B Dwg. 1310 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Roadworks Layout Plan Sheet 2 of 5	22-000082_1A-1B Dwg. 1311 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Roadworks Layout Plan Sheet 3 of 5	22-000082_1A-1B Dwg. 1312 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Roadworks Layout Plan Sheet 4 of 5	22-000082_1A-1B Dwg. 1313 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Roadworks Layout Plan Sheet 5 of 5	22-000082_1A-1B Dwg. 1314 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Intersection Details	22-000082_1A-1B Dwg. 1320 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Road 3 Longitudinal Section Sheet 1 of 2	22-000082_1A-1B Dwg. 1330 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Road 3 Longitudinal Section Sheet 2 of 2	22-000082_1A-1B Dwg. 1331 Rev. D	Egis Consulting Pty Ltd	06/10/2023	
Road 3 Cross Section Sheet 1 of 2	22-000082_1A-1B Dwg. 1332 Rev. D	Egis Consulting Pty Ltd	06/10/2023	

Approved Plans and Docum	nents		
Plan / Document Name	Reference Number	Prepared By	Dated
Road 3 Cross Section Sheet	22-000082 1A-1B	Egis Consulting Pty	06/40/2022
2 of 2	Dwg. 1333 Rev. D	Ltd	06/10/2023
D 1	22-000082 1A-1B	Egis Consulting Pty	00/40/0000
Road 4 Longitudinal Section	Dwg. 1334 Rev. D	Ltd	06/10/2023
D 110 0 "	22-000082 1A-1B	Egis Consulting Pty	00/40/0000
Road 4 Cross Sections	Dwg. 1335 Rev. D	Ltd	06/10/2023
Road 5 Longitudinal and	22-000082_1A-1B	Egis Consulting Pty	00/40/000
Cross Sections	Dwg. 1336 Rev. D	Ltd	06/10/2023
Southern Swale	22-000082 1A-1B	Egis Consulting Pty	00/40/000
Longitudinal Section	Dwg. 1340 Rev. D	Ltd	06/10/2023
Southern Swale Cross	22-000082 1A-1B	Egis Consulting Pty	00/40/000
Section Sheet 1 of 4	Dwg. 1341 Rev. D	Ltd	06/10/2023
Southern Swale Cross	22-000082 1A-1B	Egis Consulting Pty	00/40/000
Section Sheet 2 of 4	Dwg. 1342 Rev. D	Ltd	06/10/2023
Southern Swale Cross	22-000082 1A-1B	Egis Consulting Pty	00/10/000
Section Sheet 3 of 4	Dwg. 1343 Rev. D	Ltd	06/10/2023
Southern Swale Cross	22-000082 1A-1B	Egis Consulting Pty	
Section Sheet 4 of 4	Dwg. 1344 Rev. D	Ltd	06/10/2023
Stormwater Layout Plan	22-000082 1A-1B	Egis Consulting Pty	
Sheet 1 of 2	Dwg. 1400 Rev. D	Ltd	06/10/2023
Stormwater Layout Plan	22-000082_1A-1B	Egis Consulting Pty	
Sheet 2 of 2	Dwg. 1401 Rev. D	Ltd	06/10/2023
Stormwater Drainage Noes	22-000082 1A-1B	Egis Consulting Pty	
and Details	Dwg. 1402 Rev. D	Ltd	06/10/2023
	22-000082 1A-1B	Egis Consulting Pty	
Stormwater Catchment Plan	Dwg. 1410 Rev. D	Ltd	06/10/2023
Stormwater Longitudinal	22-000082 1A-1B	Egis Consulting Pty	00/40/000
Section Sheet 1 of 3	Dwg. 1420 Rev. D	Ltd	06/10/2023
Stormwater Longitudinal	22-000082 1A-1B	Egis Consulting Pty	00/40/000
Section Sheet 2 of 3	Dwg. 1421 Rev. D	Ltd	06/10/2023
Stormwater Longitudinal	22-000082_1A-1B	Egis Consulting Pty	00/40/000
Section Sheet 3 of 3	Dwg. 1422 Rev. D	Ltd	06/10/2023
Stormwater Calculation	22-000082 1A-1B	Egis Consulting Pty	00/10/000
Table Sheet 1 of 2	Dwg. 1430 Rev. D	Ltd	06/10/2023
Stormwater Calculation	22-000082 1A-1B	Egis Consulting Pty	00/40/000
Table Sheet 2 of 2	Dwg. 1431 Rev. D	Ltd	06/10/2023
Stormwater Structures	22-000082 1A-1B	Egis Consulting Pty	
Details Sheet 1 of 2	Dwg. 1440 Rev. D	Ltd	06/10/2023
Stormwater Structures	22-000082 1A-1B	Egis Consulting Pty	
Details Sheet 2 of 2	Dwg. 1441 Rev. D	Ltd	06/10/2023
	22-000082 1A-1B	Egis Consulting Pty	
Bio-Basin G1 Layout Plan	Dwg. 1700 Rev. D	Ltd	06/10/2023
	22-000082 1A-1B	Egis Consulting Pty	
Bio-Basin G1 Section Plan	Dwg. 1701 Rev. D	Ltd	06/10/2023
	22-000082 1A-1B	Egis Consulting Pty	
Bio-Basin G2 Layout Plan	Dwg. 1702 Rev. D	Ltd	06/10/2023
	22-000082 1A-1B	Egis Consulting Pty	
Bio-Basin G2 Section Plan	Dwg. 1703 Rev. D	Ltd	06/10/2023
	22-000082 1A-1B	Egis Consulting Pty	
Bio-Basin Notes and Details	Dwg. 1704 Rev. D	Ltd	06/10/2023

Note: Approved plans as indicated in **BOLD** above are annotated in **red** on the stamped plans by Council dated 23/10/2023

ASSESSMENT BENCHMARKS

The Assessment Benchmarks that applied to the development from the following Categorising Instruments include;

Categorising Instrument (Planning Regulation 2017)

State Planning Policy

State Planning Policy 2017, Part E.

Regional Plan

South East Queensland Regional Plan 2017 (ShapingSEQ).

Local Categorising Instrument (Moreton Bay Regional Planning Scheme)

 MBRC Planning Scheme - Works Code, Caboolture West Local Plan Code & Reconfiguring a lot Code (applicable precinct only)

Local Categorising Instrument (Variation Approval)

Not applicable.

Local Categorising Instrument (Temporary Local Planning Instrument)

Not applicable.

OTHER RELEVANT ASSESSMENT MATTERS

Not applicable.

REASONS FOR THE DECISION

Not Applicable.

REASONS FOR APPROVAL DESPITE NON-COMPLIANCE WITH ASSESSMENT BENCHMARKS

Not applicable.

REFERRAL AGENCY CONDITIONS

There were no Referral Agencies applicable to this development application.

SUBMISSIONS

Not applicable.

APPEAL RIGHTS

Attachment 4 of the Decision package is an extract from the *Planning Act 2016* which details your appeal rights, and the appeal rights of any submitters, if applicable, regarding this decision.

ATTACHMENT 2 Assessment Manager Conditions of Approval

	TIMING		
OPERATIONAL WORKS - AII			
ELOPMENT ENGINEERING			
Non-Conforming Designs			
Only non-conforming designs listed in this approval have been accepted. All other discrepancies with Council standards shall be redesigned and / or reconstructed as necessary to conform with Council standards at no cost to Council.	At all times during construction and prior to works being accepted Off Maintenance.		
Errors and Omissions			
Where errors or omissions occur in the design or works do not conform to or meet Council standards then these works shall be rectified to comply with Council standards at no cost to Council.	At all times during construction and prior to works being accepted Off Maintenance.		
Where drawings contain insufficient detail or do not contain details of works that are either necessary or associated with the development then these works shall be designed and constructed to Council standards.			
Only the approved plans shall be used for construction.			
Note: Council reserves the right to amend the approved drawings or request further information should this become necessary.			
Works – Applicant's Expense			
All works, services, facilities and/or public utility alterations required by or as a consequence of this approval or stated condition/s, whether carried out by the Council or otherwise, shall be at the developer's expense unless otherwise specified or agreed in writing.	At all times during construction and prior to works being accepted Off Maintenance.		
Replace existing Council infrastructure (including but not limited to street trees and footpaths) to Council's standards.			
Works – Connection to existing works			
Where existing works, including roads and drainage works, will not link up with and join smoothly to proposed works and are not more than twenty (20) metres from the nearest point of the proposed works the developer shall carry out such works as are necessary to ensure that the incomplete works, including roads and drainage, are constructed to link up with and join smoothly to the works proposed in accordance with Council's standards. These works are to be undertaken at the developer's expense unless otherwise specified or agreed in writing	Prior to works being accepted On Maintenance.		
	Non-Conforming Designs		

CON	DITION	TIMING
5	Notification of Finalisation of Works	
	Notify Council in writing that the development works on site have been finalised.	At the time of completion of construction.
6	As Constructed Drawings	
P	Provide, for review and approval, Council with a preliminary set of the surveyor and engineering As Constructed drawings for the approved works and a digital ADAC file. Note: The current design standard and relevant planning scheme policy is MBRC Planning Scheme Policy Operational Works inspection, maintenance and bonding procedures.	Prior to requesting an On Maintenance inspection.
E	Submit 'As Constructed' drawings and digital ADAC file in accordance with Council's Planning Scheme, relevant Planning Scheme Policies and design standards current at the time of development.	Prior to works being accepted On Maintenance.
7	Works Through Land not owned by the Developer	
	Where any works are proposed to be undertaken on or extend into any property not owned by the developer then the other property owner's written consent must be lodged with Council. The written consent from the land owner must identify the correct drawing title and number (including revision number) for the works within or through their land.	Prior to any works commencing within those properties.
8	Works in Existing Roads	
P	Works carried out in or affecting existing Roads must be undertaken so that these roads are maintained in a safe and useable condition.	At all times.
E	Provide to Council's delegated officer and receive acknowledgement of a Traffic Management Plan, with site specific Guidance Scheme, prepared and signed by an appropriately qualified person and in accordance with the Manual of Uniform Traffic Control Devices (MUTCD) for any works that will affect traffic movements or traffic safety in existing roads.	At least five (5) days prior to undertaking the works in or affecting existing roads.
	 Note: A 'Part Road Closure Application' for Development Works form is to accompany the Traffic Management Plan submission. This submission is required to be made in addition to any Traffic Management Plan which has been submitted and/or approved as part of a Construction Management Plan for the site during the development application process for Material Change of Use or Reconfiguring a Lot or subsequent non-IDAS applications. 	

COND	ITION	TIMING
9	Information Sign – Works in Existing Roads	
	A construction advisory road sign must be erected and regularly updated and maintained displaying the developer and contractors details and the expected completion date for works on existing roads. The sign shall be located so as be clearly legible to the public from of minimum 15m distance from the existing road on which the works are to be carried out on.	For the duration of the works from commencement to acceptance of On Maintenance.
10	Notification to Affected Premises	
В	Provide Council with a copy of an information kit for 'Notification to Affected Premises' which includes the following: A layout plan of the proposed development showing adjoining lot boundaries, new and existing roads, park and open space, drainage reserves and community purposes lots as applicable; Details of any external works with any changes to existing works highlighted for easy identification; Scheduled start and completion dates; Contact names and phone numbers for the Developer, Supervising Engineer, Consulting Engineer, the Contractor, Wildlife Spotter and who to contact in an emergency; and The site working hours authorised for the site works. Provide all occupiers of premises adjoining the site, directly opposite the frontage of the site, adjacent to and directly	Not less than 14 days prior to commencing
	opposite external works and residents/occupiers likely to be directly affected by the works with a copy of the 'Notification to Affected Premises' information kit. Provide Council's delegated officer with a list of premises which the information kit has been delivered to.	any construction works.
11	Information Sign – Development Works	
	An information sign containing the following details and after hours contact details must be provided at each entrance to the development site: • Developer • Supervising Consultant/ Engineers / Project Manager • Principal Contractor The sign must be at least 0.9m (W) by 0.6m (H). The sign must be erected and maintained for the duration of the development works.	For the duration of the development works from commencement to acceptance On Maintenance by Council.

COND	ITION	TIMING
12	Prestart Meeting	
	Arrange a prestart meeting with Council officers from Development Services section on 3205 0555 or (Email - council@moretonbay.qld.gov.au - Attention - Development Services - Engineering Waraba Construction Team - Referencing DA/2023/3491.	Not less than 7 days prior to commencing any construction works.
	The following people will be required to attend the prestart meeting:	
	 Developer's Supervising Engineer Contractor's Engineer / Project Manager Contractor's Site Supervisor 	
13	Fauna Manager (where required). Mandatory Inspections with Council Officers	
	Submit required documentation for each mandatory inspection in accordance with MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to requesting inspection.
	Undertake the following inspections with Council's delegated officer (where applicable to approved works) in accordance with MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures:	As prescribed below.
Α	Stormwater drainage.	Prior to backfilling stormwater trenches.
В	Subgrade / box inspection.	Prior to placement of structural pavements.
С	Preseal inspection.	Prior to priming and sealing of structural pavements.
D	For concrete slabs and concrete pavements - foundations / subgrade and pre-pour inspections.	Prior to concrete pouring.
E	On maintenance inspection for Council's acceptance of all works.	Prior to works being accepted On Maintenance.
F	Off maintenance inspection of all works.	After maintenance period has elapsed.
	Note: Reinspections attract a fee in accordance with Council's Fee Schedule. The fee must be paid prior to the reinspection.	politica nac diapoca.
G	Provide Council's delegated officer with a copy of an Engineers' Certificate Soil tester's reports demonstrating that required compaction standards, finished levels and textures of finish have been obtained in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to proceeding to construction of next layer or surfacing.

COND	ITION	TIMING
14	Testing Frequency – General	
A	All testing of the works shall be carried to comply with the minimum testing frequencies given in MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	At all times during construction.
	Note: Council's delegated officer may vary the frequency of testing to suit site conditions but must provide written advice to the supervising engineer prior to commencement of the relevant works.	
В	Provide a plan identifying locations where testing has occurred.	Prior to works being accepted On Maintenance.
15	Construction Hours Restrictions	
	Ensure hours of construction are limited to 0630 to 1830 Monday to Saturday and not at all on Sundays and public holidays.	At all times.
	Note: Council's engineer may approve (in writing) work outside the above hours where it can be demonstrated to the satisfaction of Council that the work will not cause unreasonable interference with the amenity of adjoining premise and any person.	
16	Construction Nuisance and Annoyance	
	Ensure construction works do not cause unreasonable interference with the amenity of adjoining premise and any person by reason of noise, vibration, electrical interference, smell, fumes, vapour, steam, soot, ash, dust, silt, wastewater, waste products, grit, oil or otherwise.	At all times.
17	Construction Site Management	
	Ensure the construction site is kept in a clean and tidy state.	At all times.
18	Temporary Sedimentation, Erosion and Runoff Control	
A	Implement an Erosion and Sediment Control Plan which is prepared by an experienced Certified Professional in Erosion and Sediment Control (CPESC) in accordance with International Erosion Control Association Australasia (IECA) Best Practice and Sediment Control document and MBRC Planning Scheme current at the time of development.	Prior to commencement of works and to be maintained current at all times during construction and until the development is accepted offmaintenance.
В	The temporary erosion and sediment control measures shall be maintained and be functional until the end of the Maintenance Period for the works or earlier if Council's delegated officer considers they are no longer required.	At all times during construction.
	Note: Council's delegated officer may order additional measures to control silt on site at no cost to Council.	

CON	DITION	TIMING
19	Haul Routes	
	Submit and have approved by Council's delegated officer all haul routes for the transport of imported or spoil material and gravel pavement material along Council roads below subarterial standard. Note: Refer to MBRC Planning Scheme Values and Constraints Mapping - Road Hierarchy for details on sub-	Prior to a prestart meeting being held.
	arterial and arterial roads.	
20	Spillage onto Existing Roads	
	Clean those parts of the access route to the site that are affected by any material dropped, deposited or spilled on the roads as a result of construction processes associated with the site.	At all times during construction.
	 Note: All materials must be swept up and removed from the roads and not directed into Council's stormwater drainage system. All care must be taken to prevent sediments being deposited on roads. 	
21	Dust Control – Nuisance and Annoyance	
	Implement suitable dust control measures. If airborne particles are observed leaving the site, any work is to cease immediately and satisfactory dust suppression is to be implemented.	At all times prior to works being accepted Off Maintenance.
	Note: Dust suppression measures must be in place at all times including weekends and public holidays.	
22	Earthworks Batters	
	Where approved drawings do not include specifications for scour and erosion protection apply the following treatments to batter slopes: • Slopes of 1:6 or flatter – topsoil and seed • Slopes between 1:6 and 1:4 – topsoil and turf • Slopes of 1:4 or greater – provide treatment recommendation from a qualified geotechnical engineer (R.P.E.Q.) for Council approval prior to undertaking batter works • Or as directed by Council.	At all times during construction.
	Note: Batters within Open and Civic Spaces are to be treated in accordance with MBRC Planning Scheme Policy Integrated Design - Open and Civil Space Design.	
23	Road Crossings in Existing Roads	
	All services crossings under Existing Council Roads are to be tunnel bored unless approved otherwise by Council's delegated officer.	At all times during construction.

COND	ITION	TIMING
	 Where approval is given for open trenching, the following is to apply: Minor Roads - backfill shall be compacted in layers to 95% standard maximum dry density and topped with 300mm of pavement material and a 50mm AC wearing course. Sub-arterial or Arterial roads - refer to I.P.W.E.A. Standard Drawing RS-170. Verge - Backfill shall be compacted to 90% standard maximum dry density and topped with 75mm of sandy loam. Restoration of any vegetation shall be undertaken to a standard as near as practicable to the pre-construction standard. 	
24	Site works – Stormwater Runoff Quality	
	Carry out earthworks in accordance with the State Planning Policy - Water Quality and IECA Best Practice Erosion and Sediment Control document. Note:	At all time during construction and until the site is suitably stabilised.
	 Soil disturbances of greater than 1.0 hectares will require a site specific Erosion & Sediment Control Plan. Earthworks are to be undertaken to ensure that soil disturbances are staged into manageable areas of not greater than 3.5 hectares. 	
25	Earth Retaining Structures	
A	Earth retaining structures within the subject land around areas of cut that are on or near the boundaries of the site must be designed to allow for the existing live and dead loads associated with the adjoining land/premises current occupancy and use of the adjoining land including allowance for a 2m high boundary fence. The minimum design life (the period assumed in design for which a structure or structural element is required to perform its intended purpose without replacement or major structural repairs) for the earth retaining structure that is specified in Table 2.1 of Australian Standard AS4678.	At all times.
В	Submit for Council records copies of Forms 15 & 16 as detailed under section 254 of the Building Act 2006. The forms are to be signed by an RPEQ for all structural retaining walls.	Prior to works being accepted On Maintenance.
	Additionally, submit certification from an R.P.E.Q. that the design and construction of retaining walls comply with the requirements of this condition.	

COND	ITION	TIMING
26	Unsuitable Fill Materials	
	Ensure that all fill material used on the development site is free of unsuitable materials, identified in AS3798 and the following:	At all times.
	 actual acid sulfate soils and potential acid sulfate soils; organic or putrescible matter; material imported from land which is, or has been, listed on the "Environmental Management Register" 	
	 under the Environmental Protection Act 1994; and building demolition material. 	
27	Compaction Requirements	
	All fill material which is intended to be load bearing, or the finished surface level of which is required to remain approximately constant, is selected, placed and compacted to the standard prescribed in Australian Standard AS3798 Guidelines on Earthworks for Commercial and Residential developments.	At all times during construction.
28	Advisory Sign – Future Road Extension	
	At the end of each road that is intended to extend with future development an advisory sign shall be supplied and erected to inform residents and the public of the future road extension. The sign shall be worded as follows:	Prior to works being accepted On Maintenance.
	"This road may be extended with future development of the adjoining land. For further information refer to Council's Planning Scheme."	
	This sign must be easily read at a distance of 5 metres. The sign shall not be attached to the road end hazard sign above the sign board.	
29	Pavement Design	
А	All road pavements must be designed, constructed and tested in accordance with MBRC Planning Scheme Policy - Integrated Design - Street, Roads and Utilities and standard drawings current at the time of construction.	At all times during construction.
	Council requires a primer seal placed under all asphalt surfaces. Increased asphalt surface thicknesses for road thresholds are to be identified in the pavement design.	
В	Submit, for review and approval by Council's delegated officer, a pavement design for all roads. Pavement designs are to include Soil tester's reports.	Prior to subgrade inspection.

COND	ITION	TIMING				
30	Pavement Jointing Detail					
	Undertake pavement jointing in accordance with I.P.W.E.A.Q. Standard Drawings RS-170.	Prior to works being accepted On Maintenance.				
31	Concrete Footpaths					
	Construct concrete footpaths and kerb ramps in accordance with I.P.W.E.A. Standard Drawings RS-065 and RS-090.	Prior to works being accepted On Maintenance.				
32	Street Signs					
	Street signs must be provided in accordance with Council's Standard Drawings and I.P.W.E.A. Standard Drawings. Note: House numbers required for these signs shall be	Prior to works being accepted On Maintenance.				
	obtained from Council's house numbering officer by contacting Council's Customer Service. The MBRC Logo is not to be put on the sign.					
33	Road Safety Barrier System Certification and Quality Assurance Documentation					
	 Where road safety barriers are required provide the following: certification from a Registered Professional Engineer Queensland (R.P.E.Q.) for the design and installation of the road safety barrier systems (including terminals) identified in the Approved Drawings and designs. full documentation, in accordance with AS3845:1999, relating to all road safety barrier systems and terminals designed and installed. Documentation required includes: Site Information Road Safety Barrier System Information Crash attenuator Information 	Prior to works being accepted On Maintenance.				
34	Hazard Management					
A	Undertake the hazard identification and treatment process for any additional, existing or introduced hazards identified onsite by the Consultant or by Council's delegated officer during the construction process. Undertake a review of the identified hazards and provide a same of the completed Hazard Mitigation Workshoot found in					
	copy of the completed Hazard Mitigation Worksheet found in AUSTROADS Guide to Road Design Part 6: Roadside Design, Safety and Barriers Appendix B along with any supporting information.					
В	Provide, for review and approval by Council's delegated officer, adequate design documentation for the recommended hazard management treatment in accordance with AS3845:1999 and AUSTROADS Guide to Road Design Part 6: Roadside Design, Safety and Barriers.	Prior to construction of any hazard management treatment.				

COND	ITION	TIMING
С	Construct approved hazard management treatments in accordance with Council's Planning Scheme, Planning Scheme Policies, standard drawings and any other relevant standards current at the time of development.	Prior to works being accepted On Maintenance.
35	Stormwater Runoff Control – Batters and Retaining Walls	
	Provide cut-off drains at the top of the batter with turf or rock lined batter drains for all batters and/or retaining walls generally higher than 600mm in height and with a catchment greater than 1000m2.	Prior to works being accepted On Maintenance.
	Note: Where these are not detailed on the approved drawings then these works shall be in accordance with Council's current standards.	
36	Stormwater Runoff Control – Open Drains	
	Provide lining with appropriate scour protection to all open drains and bunds in accordance with Council's Planning Scheme, Planning Scheme Policies and standard drawings current at the time of development.	Prior to works being accepted On Maintenance.
	Note: Dumped rock is generally not considered as an appropriate solution.	
37	Stormwater Pipe Outlets and Culvert Inlets and Outlets	
	Stabilise all culvert inlets and outlets or stormwater drainage outlets in accordance with industry best practice and the following requirements: • Rock gabion baskets/rock mattresses • Grouted rock/stone pitching with a properly designed and prepared base and constructed to the following requirements: • Mortar to be 1 part cement to 3 parts sand (by volume). • Open face stone pitching is to be used where the concrete is recessed 50mm behind the stone facing. • Select spalls to avoid sharp edges. • Other solutions as approved by Council's delegated officer. Note: Dumped rock is generally not considered as an appropriate solution.	At all times.
38	Stormwater Overland Flow – Site Earthworks	
	Earthworks must be undertaken on the site so as not to cause nuisance and annoyance to any person or premises. The development must: • Allow stormwater overland flow which entered the land prior to the commencement of the earthworks to continue to enter the land; and • Ensure stormwater overland flow from the development site is not discharged or diverted onto	At all times during construction.

COND	ITION	TIMING
	land (other than a road) adjacent to the site in a manner which: o concentrates the rate of flow at any point along the property boundary; or o increases the peak flow rates of stormwater discharged at any point along the property boundary; beyond that which existed prior to commencement of these earthworks.	
39	CCTV – Stormwater Pipes	
A	Undertake and provide, to the satisfaction of the Council, a high definition Closed Circuit Television (CCTV) recording of all stormwater pipes, including inter allotment roof water drainage. Recording to be undertaken within one month immediately preceding making a request for On Maintenance inspection and post road pavement construction works. CCTV to clearly display all joints (full surrounds) and any form of damage or defects, including date and time of the recording.	Prior to a request for On Maintenance Inspection
	The recording is to include a report signed by a suitably qualified Registered Professional Engineer Queensland (RPEQ) stating that the recording has been reviewed and all works are satisfactory.	
	Where defects have been identified, consultant is to provide method of rectification to Council for approval, prior to carrying out any rectification works.	
В	Undertake and provide, to the satisfaction of the Council, a high definition Closed Circuit Television (CCTV) recording of all stormwater pipes, including inter allotment roof water drainage. Recording to be undertaken within one month immediately preceding making a request for Off Maintenance inspection. CCTV to clearly display all joints (full surrounds) and any form of damage or defects, including date and time of the recording.	Prior to a request for Off Maintenance inspection.
	The recording is to include a report signed by a suitably qualified Registered Professional Engineer Queensland (RPEQ) stating that the recording has been reviewed and all works are satisfactory.	
	Where defects have been identified, consultant is to provide method of rectification to Council for approval, prior to carrying out any rectification works.	
40	Drainage Behind Retaining Walls	
	Design and install agricultural pipes or strip drains behind retaining walls in accordance with Q.U.D.M. to connect to: • The proposed inter-allotment drainage systems; or • To drainage inlet structures via a stub connection in roadways; or	Prior to works being accepted On Maintenance.

COND	ITION	TIMING
	 Directly to kerb and channel if there are no drainage structures within 10m of the frontage of the land; or As approved in writing by Council's delegated officer. 	
	Notes: Corrugated pipes are not to be used to connect the stormwater drainage to Council's infrastructure. The drainage system behind retaining walls must not connect to Council's subsurface drainage system in the Council road.	
41	Provision of Kerb Adapters	
	Provide a minimum of two (2) metal kerb adaptors per lot for lots that drain to the road. Where a lot has side crossfall of up to 1.5%, one (1) kerb adaptor shall be located at each side of the lot. Where a lot has side crossfall of greater than 1.5%, both kerb adaptors shall be located at the low side of the lot.	Prior to works being accepted On Maintenance.
	For lots with a concrete footpath at the frontage, the kerb adaptors shall be connected to the front boundary of the lot with Class SN8 uPVC stormwater pipe.	
42	Fertilisers for Grassing and Landscape Works	
	Odorous chemicals, fertilisers, soil conditioners or mulches shall not be used on land development projects. Only a non-odorous, commercially bagged and labelled fertiliser shall be used when seeding grass areas or laying turf.	At all times during construction.
	Without limiting the above, Council's delegated officer may approve the use of suitably composed and aged organic material, such as soil conditioners, at the following locations: • in isolated locations where existing and proposed houses are considerable distances from the work site; and • where, in the officer's opinion, their use would not adversely affect the occupiers of any nearby properties with strong odours or loose material blown from the work site.	
	Council's delegated officer will provide the approval in writing with conditions where odorous fertilisers are approved.	
43	Stabilisation of Disturbed Areas	
	Ensure that a grass strike rate of at least 80% cover has been attained on all disturbed areas or other approved means of stabilisation of grassed areas have been provided.	Prior to works being accepted On Maintenance.
	Note: For residential and rural residential subdivisions, the road reserve between kerb and property line shall be turfed as a condition of completion.	
		I

COND	TION	TIMING				
44	Certification – Public Stormwater Management Infrastructure					
	Provide documentation to Council from a Registered Professional Engineer (RPEQ) specialising in stormwater design certifying that the stormwater management treatment train as approved in the stormwater management plan and design drawings has been constructed in accordance with engineering best practise and is functioning as designed. The certification shall include the completed sign-off forms for	Prior to works being accepted On Maintenance.				
	bioretention systems prepared by Water by Design in Partnership with Healthy Waterways shall be completed. The sign-off forms are accessible from www.waterbydesign.com.au .					
45	Public Bioretention Inspections					
	Provide Council with notice of the subsoil drains being laid and the filter media being installed. Note: Council's delegated officer may attend the inspection.	Not less than 48 hours prior to subsoil drains being laid and the filter				
46	Maintenance Process for Public Bioretention Basin	media being installed.				
A	The entire bioretention basin shall act as a sediment basin. Note: Council will consider alternative solutions to achieve the desired outcome.	During the build-out phase (80%) or up to a maximum of two (2) years.				
В	Submit, for review and approval by Council's delegated officer, a deferred works schedule to cover the cost of basin conversion plus twenty-five percent (25%) and in accordance with the requirements of Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to the bioretention basin area being accepted On Maintenance as a sediment basin.				
	The following works are to be included as a minimum in the deferred works bond schedule: • removal of sacrificial turf and geofabric; and • In-situ hydraulic conductivity testing of filter material in accordance with the "Guidelines for Soil Filter Media in Bioretention Systems: (produced by the Faculty for Advanced Water Biofiltration) requirements. • Planting out of the basin in accordance with the approved landscaping drawings.					
С	Construct deferred works and any other works necessary to convert to the basin from sediment basin to a functioning bioretention basin in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Once the contributing catchment achieves eighty percent (80%) build-out or a maximum of 2 years.				
	In-situ hydraulic conductivity testing of filter material is to be provided to Council's delegated officer to demonstrate that area can be planted out. Where in-situ hydraulic conductivity					

COND	ITION	TIMING
	testing shows that the filter material is not acceptable then replacement of the filter material is required in addition to planting out of basin area.	
	Note: Deferred Works for bioretention basin conversion are subject to a separate on maintenance process to the other civil works for the development. The On Maintenance process is to be in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures including on and off maintenance inspections and maintenance period.	
OPERA	ATIONAL WORKS - Stage 1A	
47	Road Classifications for Pavement Design	
	Design pavement in accordance with the following road classifications:	Prior to subgrade inspections.
	Road 3 (fronting Lot 19) - Modified Living Residential (15.0m) - 1.2 x 10 ⁵ ESA Road 3 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA Road 4 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA	
	Road 5 - Driveway (3.0m) - 2.5 x 10 ³ ESA	
OPERA	ATIONAL WORKS - Stage 1B	
48	Road Classifications for Pavement Design	
	Design pavement in accordance with the following road classifications:	Prior to subgrade inspections.
	Road 3 (fronting Lot 18) - Modified Living Residential (15.0m) - 1.2 x 10 ⁵ ESA Road 3 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA	

ADVICES Development Permit This approval shall comply with all the conditions of related approval as stipulated in Council's Decision Notice – Development Permit dated 24 August 2023 referenced as DA/2021/4669. The Applicant needs to be aware that the Currency Period of that Decision Notice may determine the validity period of this Decision Notice. 2 **Extent of Checking by Council** This approval shall not be taken to mean that the drawings have been checked in detail and Council accepts no responsibility whatsoever for the survey information, the design, or for the accuracy of any information or detail contained in the approved drawings and specifications. Aboriginal Cultural Heritage Act 3 The Aboriginal Cultural Heritage Act 2003 commenced in Queensland on April 16, 2004. Under the Act, indigenous parties are key in assessing cultural heritage significance. The Aboriginal Cultural Heritage Act 2003 establishes a Duty of Care for indigenous cultural heritage. This applies on all land and water, including freehold land. The Cultural Heritage Duty of Care lies with the person or entity conducting the activity. Penalty provisions apply for failing to fulfil the Cultural Heritage Duty of Care. Those proposing an activity that involves additional surface disturbance beyond that which has already occurred on the proposed site need to be mindful of the Duty of Care requirement. Details of how to fulfil the Duty of Care are outlined in the Duty of Care Guidelines gazetted with the Act. Council strongly advises that you contact the relevant state agency to obtain a copy of the Duty of Care Guidelines and further information on the responsibilities of developer under the terms of the Aboriginal Cultural Heritage Act 2003. **Environmental Protection Act** It remains the duty of care of the site owner not to cause Environmental Harm as defined under the Environmental Protection Act 1994. 5 Road and Stormwater infrastructure In respect to Road and Stormwater infrastructure, the works shall be designed and constructed in accordance with the relevant Planning scheme codes and policies; The current relevant planning scheme codes and policies are: Works code: Reconfiguring a lot codes; **PSP- Integrated Design** PSP- Operational Works Inspection, Maintenance and Bonding Procedures. All of which may be downloaded free of charge from Council's website at

ADVICES

www.moretonbay.qld.gov.au.

The PSP- Operational Works Inspection, Maintenance and Bonding Procedures also contains details of other requirements such as:

- 1. arrangements for works going On or Off Maintenance;
- 2. inspection and testing;
- 3. checklists and certification proforma;
- 4. bonding procedures.

Should further information be required regarding the road and stormwater component of the Operational Works Application, please contact Council's Officer, Xavier Dubreuil on phone (07) 5433 2739.

6 Acceptance Based on Applicant's Certification

Council's acceptance of the above submission is based solely on the applicant's certification that the proposal conforms totally to Council's Planning Scheme, Planning Scheme Policies and standard drawings.

7 Biosecurity Act 2014 - Fire Ant Control

Significant portions of the Moreton Bay are within Fire Ant Biosecurity Zone 2 and must remain vigilant for the presence of fire ants. Under the Biosecurity Act 2014, individuals and businesses are responsible for ensuring that they follow the movement controls for specific organic materials to help prevent the spread of fire ants within South East Queensland's fire ant biosecurity zones. Movement of a fire ant carrier from within the fire ant biosecurity zone may need a biosecurity instrument permit.

More information is available on https://www.fireants.org.au/treat/business-and-industry/movement-controls

ATTACHMENT 3

Approved Plans / Documents

LILYWOOD LANDINGS







STAGES 1A & 1B - OPERATIONAL WORKS FOR FOREVERLEN PTY LTD



LOCALITY PLAN

MORETON BAY REGIONAL COUNCIL

Moreton Bay

AREA OF SITE: 5.499 ha

LOT INFORMATION

LOT 12 ON RP866105, LOT 35 ON SP115959. & LOT 1 ON RP866105

DRAWINGS INDEX

1000 TITLE SHEET & LOCALITY PLAN

KEY PLAN

1100 SITE LAYOUT PLAN

RETAINING WALL SETOUT PLAN SHEET 1 OF 2 RETAINING WALL SETOUT PLAN SHEET 2 OF 2

RETAINING WALL NOTES & DETAILS 1202

CONTROL LINE SETOUT PLAN SHEET 1 OF 2

CONTROL LINE SETOUT PLAN SHEET 2 OF 2

ROADWORKS LAYOUT PLAN

ROADWORKS LAYOUT PLAN SHEET 1 OF 5 ROADWORKS LAYOUT PLAN SHEET 2 OF 5

1312 ROADWORKS LAYOUT PLAN SHEET 3 OF 5 1313 ROADWORKS LAYOUT PLAN SHEET 4 OF 5

ROADWORKS LAYOUT PLAN SHEET 5 OF 5 1314

SECTIONS

1330 ROAD 3 LONGITUDINAL SECTION SHEET 1 OF 2 ROAD 3 LONGITUDINAL SECTION SHEET 2 OF 2 1331

ROAD 3 CROSS SECTIONS SHEET 1 OF 2

ROAD 3 CROSS SECTIONS SHEET 2 OF 2

1334 **ROAD 4 LONGITUDINAL SECTION**

ROAD 4 CROSS SECTIONS 1335

ROAD 5 LONGITUDINAL AND CROSS SECTIONS 1336

SOUTHERN SWALE LONGITUDINAL SECTION

SOUTHERN SWALE CROSS SECTIONS SHEET 1 OF 4 SOUTHERN SWALE CROSS SECTIONS SHEET 2 OF 4

SOUTHERN SWALE CROSS SECTIONS SHEET 3 OF 4

SOUTHERN SWALE CROSS SECTIONS SHEET 4 OF 4

STORMWATER LAYOUT PLANS

STORMWATER LAYOUT PLAN SHEET 1 OF 2 STORMWATER LAYOUT PLAN SHEET 2 OF 2

STORMWATER DRAINAGE NOTES AND DETAILS

STORMWATER CATCHMENT PLAN

STORMWATER LONGITUDINAL SECTIONS

STORMWATER LONGITUDINAL SECTIONS SHEET 1 OF 3

STORMWATER LONGITUDINAL SECTIONS SHEET 2 OF 3

STORMWATER LONGITUDINAL SECTIONS SHEET 3 OF 3

STORMWATER CALCULATION TABLES

STORMWATER CALCULATION TABLES SHEET 1 OF 2

STORMWATER CALCULATION TABLES SHEET 2 OF 2

STORMWATER STRUCTURES DETAILS SHEET 1 OF 2

SEWER RETICULATION COVER SHEET

SEWER RETICULATION LAYOUT PLAN

SEWER LONGITUDINAL SECTIONS SHEET 1 OF 4

SEWER LONGITUDINAL SECTIONS SHEET 2 OF 4

SEWER LONGITUDINAL SECTIONS SHEET 3 OF 4

SEWER LONGITUDINAL SECTIONS SHEET 4 OF 4

WATER RETICULATION COVER SHEET

WATER RETICULATION LAYOUT PLAN

BIO-BASIN PLANS

BIO-BASIN G1 LAYOUT PLAN

BIO-BASIN G1 SECTION PLAN

BIO-BASIN G2 LAYOUT PLAN

BIO-BASIN G2 SECTION PLAN

BIO-BASIN NOTES AND DETAILS

CONSTRUCTION NOTE

THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH:

- CRR INTERSECTION & IDC SET 22-000082 CRR BULK FARTHWORKS SET - 22-000082 FWKS
- STAGE 2 SET 22-000082 2
- STAGE 3 SET 22-000082 3
- STAGE 4 SET 22-000082 4
- STAGE 22 SET 22-000082_22
- GEOTECHNICAL REPORT
- BAF TRUNK WATER INFRASTRUCTURE SET 22-000082 TWI
- DOBSON LANE TRUNK GRAVITY SEWER SET 20-000027 SIGNALS PLANS (BY CV SERVICES)
- LANDSCAPE PLANS (BY AECOM)
- ELECTRICAL/ COMMS PLAN (BY CV SERVICES

CONSTRUCTION HOLD POINT

PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL VERIFY LEVELS OF ALL EXISTING CROSSINGS AND CONNECTION POINTS.


Approved Subject to Conditions of Decision Notice DA/2023/3491


LILYWOOD LANDINGS


STAGE 1A & 1B

22-000082 1A-1B 1A & 1B OPERATIONAL 06/10/23

1000







RETAINING WALL DESIGN AND CONSTRUCT NOTES:

- CONCRETE SLEEPER RETAINING WALL IS A DESIGN AND CONSTRUCT ITEM.
 CONTRACTOR SHALL ENGAGE A RPEQ STRUCTURAL ENGINEER WITH SUITABLE
- RETAINING WALL EXPERIENCE.
- 3. FOLLOWING DESIGN PARAMETERS SHALL BE ADOPTED.
- a) SURCHARGE LOAD 5kPa FOR INTERALLOTMENT WALLS.
- b) SURCHARGE LOAD 20kPa WHERE WALLS ARE SUPPORTING ROADS OR DRIVEWAYS.
 c) ALLOW FOR WIND AND DEAD LOADS FOR SOLID 1.8m HIGH FENCE, OR HIGHER IF SPECIFIED IN THE ACOUSTIC REPORT.
- d) ALLOW FOR MAX 1 IN 4 SLOPE AT TOP AND TOE OF WALLS.
- e) TORSIONALLY RIGID BEAMS SUCH AS UC SECTION SHALL BE SPECIFIED.
- f) DESIGN SHALL ACHIEVE 60 YEAR DESIGN LIFE. OR DESIGN LIFE SPECIFIED BY THE RELEVANT AUTHORITY.
- g) CONTRACTOR SHALL ARRANGE GEOTECHNICAL INVESTIGATION AND STRUCTURAL DESIGN SHALL ALLOW FOR CONDITIONS IDENTIFIED IN INVESTIGATION
- WALL DESIGN SHOULD INCLUDE FOUNDATION LEVELS WITH THEIR LINE OF INFLUENCE CLEAR OF ANY PROPOSED UTILITY SERVICES INSTALLATIONS.
- 4. CONTRACTOR SHALL PROVIDE RPEQ CERTIFIED STRUCTURAL DESIGN PRIOR TO CONSTRUCTION AND FORM 15 CERTIFICATION.
- CONTRACTOR SHALL ARRANGE FOR RPEQ INSPECTIONS DURING CONSTRUCTION AND PROVIDE RPEQ CERTIFIED FORM 16 PRIOR TO PRACTICAL COMPLETION BEING AWARDED
- 6. CONTRACTOR TO CONSIDER NEARBY EXISTING AND PROPOSED SERVICES WITHIN RPEQ DESIGN OF WALLS, AND TO OBTAIN BUILD OVER ASSET APPROVALS WITH THE RELEVANT AUTHORITIES AS REQUIRED BY THE AUTHORITIES' SPECIFICATIONS, PRIOR TO CONSTRUCTION. CONTRACTOR TO PROVIDE BUILD OVER ASSET APPROVALS TO THE SUPERINTENDENT, PRIOR TO CONSTRUCTION.
- 7. RETAINING WALLS TO BE CONSTRUCTED TO MANUFACTURERS SPECIFICATIONS.
- 8. PROVIDE APPROVED SAFETY FENCE TO ALL WALLS HIGHER THAN 1.0m.
- CONTRACTOR TO ENSURE ALL WORKS ADJACENT TO EXISTING RETAINING WALLS IS UNDERTAKEN SO AS NOT TO IMPACT ON THE STRUCTURAL INTEGRITY OF THE EXISTING WALLS. SUBSOIL OUTLETS FOR EXISTING RETAINING WALLS TO BE KEPT FREE DRAINING AT ALL TIMES.
- WALL ALIGNMENT IS TO BE PEGGED FOR INSPECTION BY SUPERINTENDENT PRIOR TO CONSTRUCTION.


11. WALLS TO BE VERTICAL FACE TYPE TO A MAXIMUM HEIGHT OF 2.5m. TYPE, FINISH AND COLOUR TO BE APPROVED BY SUPERINTENDENT, UNLESS NOTED OTHERWISE.

 CONTRACTOR IS RESPONSIBLE FOR PROVIDING STRUCTURAL DESIGN, CONSTRUCTION SUPERVISION AND STRUCTURAL CERTIFICATION BY A SUITABLY QUALIFIED AND EXPERIENCED, REGISTERED STRUCTURAL ENGINEER (RPEQ) FOR ALL WALLS 1.0m HIGH OR GREATER.


13. BE LODGED FOR EARTH RETAINING STRUCTURES > 1000mm HIGH


- 14. ALL WALLS TO BE DESIGNED BASED ON A GEOTECHNICAL ASSESSMENT OF INSITU SOILS BY A SUITABLY QUALIFIED ENGINEER. SHOULD WALLS REQUIRE ADDITIONAL FOOTINGS AND/OR FOUNDATION SUPPORT, THESE ARE TO BE FACTORED INTO THE DESIGN AND THE TENDERED COST OF THE WALLS.
- 15. PRIVATE WALLS INCLUDING FOOTING TO BE CONTAINED WHOLLY WITHIN PRIVATE PROPERTY AND ARE TO BE FULLY CONTAINED WITHIN THE LOWER LOT UNLESS WALL ABUTS ROAD RESERVE/PARK, IN WHICH CASE THE WALL SHALL BE CONTAINED WHOLLY WITHIN THE PRIVATE PROPERTY.
- 16. SUBSOIL DRAINAGE BEHIND ALL WALLS TO INCLUDE DISCHARGE PIPE INTO THE NEAREST STORMWATER STRUCTURE (OR DEDICATED KERB ADAPTOR) AND MUST BE FREE DRAINING. ALL WALL DRAINAGE LINES DISCHARGING THROUGH LOTS OR ROAD VERGE TO BE SOLID uPVC (NO SLOTS) AND MUST BE FREE DRAINING.
- verge to be solid upvo (no slots) and most be free draining.

 17. WALLS ARE TO BE CAPABLE OF SUPPORTING TWO STOREY "HEAVY CONSTRUCTION"
 BUILDINGS.
- 18. CONTRACTOR TO PROVIDE & MAINTAIN SAFETY FENCE TO ALL WALLS GREATER THAN 1.0m IN HEIGHT.
- A MINIMUM 600mm CLEARANCE IS TO BE MAINTAINED BETWEEN THE OUTSIDE OF THE BORED PIERS AND THE OUTSIDE OF ANY SEWER MAIN OR ROOFWATER PIPE IN THE VICINITY OF THE RETAINING WALL.
- 20. RETAINING WALL DESIGN AND CONSTRUCTION TO CONSIDER AND CATER FOR ALL SERVICES LOCATED UNDER, OR IN THE VICINITY OF, THE RETAINING WALL.
- 21. ALL WALLS TO BE DESIGNED TO ALLOW FOR 1.8m HIGH ENCLOSED FENCE.
- WHERE APPLICABLE, RETAINING WALL DESIGN AND CONSTRUCTION SHALL MAKE ANY NECESSARY ALLOWANCES TO FACILITATE AND ENABLE FUTURE RETAINING WALL JOINTS/CONNECTIONS/EXTENSIONS.
- EXTENT OF ALL WALLS TO BE CONFIRMED BY CONTRACTOR WITH SUPERINTENDENT PRIOR TO STARTING CONSTRUCTION.
- 24. ORANGE MESH SAFETY FENCING TO BE ERECTED ON TOP OF WALL 1.0m HIGH OR



Moreton Bay





EVISION DATE ISSUE DETAILS

SUBSEQUENT WALLS.

BOULDER RETAINING WALL NOTE

CLEARANCE BETWEEN THE FRONT AND BACK OF

STEPPED BOULDER RETAINING WALLS TO BE

CONSTRUCTED WITH 1.5m HORIZONTAL

ISSUED FOR APPROVAL

SIGN CHECK RYAN ASHWORTH RPEQ 19674

1:20 0.2 0 0.2 0.4 0.6 0.8 1m A1 1:40 A3 LENNIUM




LANDINGS
STAGES 1A & 1B


RETAINING WALL NOTES & DETAILS

1202

STAGES 1A & 1B
DISCLAIMER

22-000082_1A-1B





ROAD 5 CONTROL LINE SETOUT TABLE

PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
IP 1	0.000	90957.338	502008.533	233°56'50.25"			
TC	9.819	90949.400	502002.754	233°56'50.25"			
IP 2	14.217	90945.738	502000.089		R = 15.000	8.796	33°35'56.07"
СТ	18.615	90941.214	501999.895	267°32'46.31"			
IP 3	50.436	90909.422	501998.533	267°32'46.31"			

ROAD 4 CONTROL LINE SETOUT TABLE PT CHAINAGE **EASTING** NORTHING **BEARING**

91125.388

90954.499

90964.141

502019.895

502081.141

502090.633

502055.751

8°56'46.00"

8°56'46.00"

98°56'54.40"

98°56'54.40"

CT

IP8

IP 2

647.618

709,619

0.000

224.257

NOTE: REFER TO DRG 22-000082_1A-1B_1300 FOR DRG LEGEND.

TEMPORARY TURN HEAD 2 COAT SPRAY SEAL ON 150mm BASE. 1.0m GRAVEL SHOULDER PROVIDE 2m² OF GROUTED ROCK PITCHING TO END OF KERB AND CHANNEL (DOWN SLOPE ONLY)

ROAD 3 & 4 - TYPICAL TEMPORARY TURNAROUND AREA DETAIL

SCALE 1:250(A1) SCALE 1:500(A3)

VISION	DATE	ISSUE DETAILS	DRAWN	DESIGN	DRAWN CHECK	STATUS	SCALE 1:25	0.25	0 0.25	0.5	0.75 1.0	0 125m	Λ1
Α	14.12.22	ISSUED FOR APPROVAL	IB	AA	1 .	ISSUED FOR APPROVAL	1:50	0.20	0.20	-0.0	0.70 1.0		A3
В	01.03.23	AMENDED COUNCIL COMMENTS	IB	AA	1 KT	1000LD 1 OIX / II 1 IXO V / IL							
С	24.05.23	MINOR AMENDMENTS	IB	AA	1 1 1		1:250	5	0		5	10m	Α1
D	06.10.23	UPDATE TO EGIS COVER PAGE	RT	AA		APPROVED	1:500						A3
						RYAN ASHWORTH RPEQ 19674	1.000						ΛJ
					aa	0 1 1	1:500	10	5 0		10	20m	Δ1
		Mana	Manahan Day			l Kyan Ushworth	1:1000	Ě	خــــــــــــــــــــــــــــــــــــــ		<u> </u>		
		More	ton Bat			FOR & ON BEHALIF OF CALIBRE PROFESSIONAL SERVICES PTY LTD	1.1000						A3

FOREVERLEN PTY LTD LENNIUM





LANDINGS STAGES 1A & 1B ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.


CONTROL LINE SETOUT PLAN SHEET 2 OF 2


1301


22-000082_1A-1B














ROAD 3 BEND 1 SETOUT


POINT ID	EASTING	NORTHING	LEVEL
1	90950.812	502020.476	24.216
2	90966.401	501999.060	24.744
3	90967.561	502006.430	24.744
4	90958.181	502019.315	24.216

DRIVEWAY 1 SETOUT

POINT ID	EASTING	NORTHING	LEVEL
D 1	90956.277	502003.741	24.535
D 2	90952.381	502008.945	24.418
D 3	90947.548	502005.426	24.583
D 4	90940.999	502003.139	24.719
D 5	90938.603	502005.338	24.857
D 6	90914.625	502004.311	25.222
D 7	90912.426	502001.915	25.155
D 8	90909.283	502001.780	25.203
D 9	90909.561	501995.286	25.398
D10	90941.278	501996.645	24.914
D11	90951.373	502000.171	24.778

ROAD 4 & 3 INTERSECTION

POINT ID	EASTING	NORTHING	LEVEL
5	90958.279	502067.891	23.193
6	90949.731	502079.634	23.079
7	90977.390	502075.279	23.579
8	90965 648	502066 731	23 193




ROAD 4 AND ROAD 3 INTERSECTION

SCALE 1:200

LEGEND

RL.59.651 ×

10,




ROAD 3 & 4 INTERSECTION

POINT ID	EASTING	NORTHING	LEVEL
9	90917.117	502084.770	22.551
10	90906.451	502079.445	23.075
11	90898.418	502080.706	23.092
12	90899.131	502084.361	22.951
13	90900.832	502095.203	22.587
14	90912.925	502121.606	22.125
15	90918.592	502116.801	22.124
16	90911.934	502106.402	22.270
17	90919.648	502091.923	22.557

ROAD 3 BEND 2 SETOUT

POINT ID	EASTING	NORTHING	LEVEL
18	90942.603	502156.654	21.979
19	90959.802	502163.043	22.088
20	90958.641	502155.674	22.088
21	90948 292	502151 829	21 982



INDICATIVE DRIVEWAY LOCATIONS NOTE KERB SETOUT IS TO LIP OF KERB AND CHANNEL.

GULLY PIT

WORKS BOUNDARY CONTROL LINE

KERB INTERMEDIATE LEVEL

KERB SETOUT POINT

CONCRETE FOOTPATH

ASPHALT SURFACING

CONCRETE DRIVEWAY

OUTLET STRUCTURE

STORMWATER DRAINAGE MAINTENANCE HOLE

DESIGN SURFACE CONTOUR (0.1m INTERVALS)

LEVEL ARE SHOWN TO LIP OF KERB AND CHANNEL. KERB LEVELS SHOWN AT EQUAL INTERVALS, U.N.O.

REVISION DATE ISSUE DETAILS ISSUED FOR APPROVAL 01.03.23 AMENDED COUNCIL COMMENTS C 24.05.23 MINOR AMENDMENTS
D 06.10.23 REVISED AS PER COUNCIL RF RYAN ASHWORTH RPEQ 19674 Ryan Asliworth DR & ON BEHALF OF CALIBRE PROFESSIONA

Moreton Bay

FOREVERLEN PTY LTD LENNIUM



LANDINGS STAGES 1A & 1B ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION, USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE. INTERSECTION DETAILS

1320


22-000082_1A-1B

- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).


PRELIMINARY ROAD 3 PAVEMENT DESIGN


			1 1 (E E II VIII V II V I I V	O/ ID O I / IV LIVILII		1011			
ROAD	SUBGRADE	TRAFFIC	ROAD CLASS	AC SURFACING (mm)	BASE	SUB-BASE	LOWER SUB-BASE	TOTAL BOX	
RUAD	CBR	ESA'S	RUAD CLASS	AC SORI ACING (IIIII)	(mm)	(mm)	(mm)	(mm)	
ROAD 3	3 *	1.2 X 10 ⁵	LIVING RESIDENTIAL	25 BCC TYPE 2	100	100	300	525	

* ASSUMED SUBGRADE CBR



REFER INTERSECTION DETAILS FOR LEVELS HORIZ SCALE: 1:500 VERTICAL SCALE: 1:50 EVISION DATE ISSUE DETAILS **FOREVERLEN PTY LTD ROAD 3 LONGITUDINAL** ISSUED FOR APPROVAL LANDINGS 01.03.23 AMENDED COUNCIL COMMENTS SECTION SHEET 1 OF 2 C 24.05.23 MINOR AMENDMENTS
D 06.10.23 UPDATE TO EGIS COVER PAGE LENNIUM STAGES 1A & 1B RYAN ASHWORTH RPEQ 19674 aa Kyan Aslworth ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION, USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE. 22-000082_1A-1B 1330 D www.egis-group.com Moreton Bay Approved Subject to Conditions of Decision Notice DA/2023/3491 23/10/2023






NOTE:

- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).

PRELIMINARY ROAD 3 PAVEMENT DESIGN

				o o		. •		
040	SUBGRADE	TRAFFIC	DOAD OLAGO	AC SURFACING (mm)	BASE	SUB-BASE	LOWER SUB-BASE	TOTAL BOX
ROAD	CBR	ESA'S	ROAD CLASS	AC SURFACING (IIIII)	(mm)	(mm)	(mm)	(mm)
ROAD 4	3 *	1.2 X 10 ⁵	LIVING RESIDENTIAL	25 BCC TYPE 2	100	100	300	525


^{*} ASSUMED SUBGRADE CBR



HORIZ SCALE: 1:500
VERTICAL SCALE: 1:50

REFER INTERSECTION DETAILS FOR LEVELS

Moreton Bay







STAGES 1A & 1B


DISCLAIMER
ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO
CONSTRUCTION, USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.

ROAD 4 LONGITUDINAL
SECTION
PROJECT NO. IDRAWING NO. IT

D


1334

22-000082_1A-1B



PAVEMENT NOTE:

DRIVEWAY TO BE 175mm THICK N32 CONCRETE WITH SL92 MESH ON 150mm BASE TYPE 2.1. FINISH PER LANDSCAPE SPECIFICATION.





ROAD 5 (DRIVEWAY) - LONGITUDINAL SECTION
HORIZ SCALE: 1:500
VERTICAL SCALE: 1:50 REFER INTERSECTION DETAILS FOR LEVELS

ION	DATE	ISSUE DETAILS	DRAWN	DESIGN	DRAWN CHECK	STATUS	SCALE 1:100	1	0 1	2 3	4 5	5m A1
	14.12.22	ISSUED FOR APPROVAL	IB	AA	1 .	ISSUED FOR APPROVAL	1:200		_		_	■ A3
	01.03.23	AMENDED COUNCIL COMMENTS	IB	AA] RT	1000LD TOR ALT NOVAL	4.500	40	- 0			
	24.05.23	MINOR AMENDMENTS	IB	AA	1.1		1:500	10	5 0	1) 2	20m A1
	06.10.23	REVISED AS PER COUNCIL RFI	RT	AA		APPROVED	1:1000			ORIZONTAL		A 3
						RYAN ASHWORTH RPEQ 19674			п	URIZUNTAL		
					aa	0.1 11	1:50	1 0	J.5 0	1		2m A1
		Manahan	D			Kyan Ushworth	1:100					A3
		Moreton	Bal			FOR & ON BEHALIF OF CALIBRE PROFESSIONAL SERVICES PTY LTD			,	VERTICAL		
		Beginnal C	`nuncil 🐓	,				4	\sim	1000		



LOT 50

LOT 49

LOT 48

RL23.000 CH 50.436

RL23.000

RL23.000 CH 20.000

CH 40.000



2.2m

3.6m

3.6m

4.6m

LANDINGS STAGES 1A & 1B

ROAD 5 LONGITUDINAL AND **CROSS SECTIONS**

1336

Road 6 - CMB

PROPOSED CONCRETE


PROPOSED CONCRETE
SLEEPER RETAINING WALL

LOT 51

BARRIER KERB & CHANNEL TYPE B2 REFER TO IPWEA STD. DRG. RS-080 FOR DETAILS.

SLEEPER RETAINING WALL


FOR & ON BEHAL® OF CALIBRE PROFESSIONAL SERVICES PTY LTD Approved Subject to Conditions of Decision Notice DA/2023/3491 22-000082_1A-1B




SOUTHERN SWALE LONGITUDINAL SECTION


HORIZ SCALE: 1:500 VERTICAL SCALE: 1:50


REVISION DATE ISSUE DETAILS FOREVERLEN PTY LTD A 14.12.22 ISSUED FOR APPROVAL
B 01.03.23 AMENDED COUNCIL COMMENTS SOUTHERN SWALE ISSUED FOR APPROVAL LANDINGS LONGITUDINAL SECTION C 24.05.23 MINOR AMENDMENTS
D 06.10.23 UPDATE TO EGIS COVER PAGE LENNIUM RYAN ASHWORTH STAGES 1A & 1B RPEQ 19674 Ryan Ashworth
R & ON BEHALF OF CALIBRE PROFESSIONAL SERVICES PTY LTD 22-000082_1A-1B 1340 www.egis-group.com Moreton Bay














STORMWATER DRAINAGE NOTES

- 1. ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH CURRENT M.B.R.C STANDARD DRAWINGS AND METHODS.
- 2. ALL STORMWATER PIPES UNDER ROADWAYS AND FOOTPATHS SHALL BE RCP CLASS 3 U.N.O.
- 3. ALL STORMWATER PIPES UP TO AND INCLUDING 600Ø SHALL BE R.R.J. STORMWATER PIPES GREATER THAN 600Ø SHALL BE INTERNAL FLUSH JOINTED WITH PROPRIETARY EXTERNAL BAND.
- 4. STEPIRONS ARE TO BE PROVIDED IN STORMWATER MANHOLES AND GULLIES GREATER THAN 1.20m DEEP, IN ACCORDANCE WITH M.B.R.C STD. DRG. SD.10.
- 5. ALL DIMENSIONS ARE IN METRES UNLESS SHOWN OTHERWISE.
- 6. CONTRACTOR TO LIAISE WITH ALL RELEVANT SERVICE AUTHORITIES TO ASCERTAIN SERVICES PRESENT ON-SITE. ANY ALTERATION WORKS TO SERVICES WILL BE CARRIED OUT BY THAT SERVICE **AUTHORITY ONLY**
- 7. THE CONTRACTOR SHALL NOTIFY THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF DEMOLISHING ANY EXISTING STRUCTURES WITHIN THE SITE AREAS.
- 8. THE STORMWATER PIPE CLASSES HAVE BE DESIGNED FOR SERVICE LOADS ONLY, AND THE CONTRACTOR SHALL ASSESS ANTICIPATED CONSTRUCTION LOADS AND UPGRADE THE PIPE CLASSES IF NECESSARY, IN ACCORDANCE WITH AS3725-2007.
- 9. RETAINING WALL SUBSOIL DRAINS TO CONNECT TO KERB AND CHANNEL SUBSOIL OR STORMWATER DRAINAGE STRUCTURES.
- 10. WORKS SHALL BE PROGRAMMED SO AS NOT TO DISTURB NEARBY HOUSEHOLDERS EITHER BY DUST, NOISE, FLOODING OR DISCONNECTION OF SERVICES.
- 11. ALL CONSTRUCTION ACTIVITIES SHALL COMPLY WITH WORKPLACE HEALTH AND SAFETY
- 12. ANTI PONDING GULLIES ARE TO BE SIDE ENTRY TYPE. CHAMBER AND GRATE ONLY TYPE NOT TO BE USED.
- 13. GULLY PITS IN EXCESS OF 1.5 METRES DEEP ARE TO BE CONSTRUCTED AS A GULLY PIT/ACCESS CHAMBER STRUCTURE.
- 14. CRACKS IN STORMWATER PIPES WILL NOT BE ACCEPTED.
- 15. LEVELS AND GRADIENTS AT JUNCTIONS WITH EXISTING WORKS MAY BE VARIED AS REQUIRED TO ACHIEVE A SATISFACTORY CONNECTION AND THE CONTRACTOR SHALL INCLUDE THE COST OF THIS WORK IN THE TENDER PRICE. WHERE NEW WORK JOINS EXISTING, THE WORK SHALL TRANSITION NEATLY WITH THE PAVEMENT SO THAT DEVIATION FROM THE LINE OF A 3.0m STRAIGHT EDGE SHALL BE NO GREATER THAN 10mm
- 16. CONDUITS SHALL BE IN ACCORDANCE WITH I.P.W.E.A STD. DRG. RS-101.
- 17. ALL EXCAVATION AND FILLING SHALL BE COMPACTED TO THE REQUIREMENTS OF AS3798-2007 IN ACCORDANCE WITH THE LOCAL AUTHORITY REQUIREMENTS.
- 18. ALL LEVELS ARE IN METRES ABOVE AUSTRALIAN HEIGHTS DATUM (mAHD) UNLESS OTHERWISE SHOWN

KERB ADAPTORS NOTES

ADAPTORS . KERB ADAPTORS SHOWN ARE INDICATIVE ONLY AND ARE TO BE INSTALLED IN ACCORDANCE WITH IPWEA STD DRG RS-081.

NOTWITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THE JOB DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE SUPERINTENDENT OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ANY UNDERGROUND SERVICES IN THIS AREA AND SHALL BE RESPONSIBLE FOR MAKING GOOD ANY DAMAGE THERETO.

SCOUR PROTECTION NOTES:

- IF ROCK SIZE IS SPECIFIED ON THE PLAN AS D_{50} THIS CORRESPONDS TO A ROCK SIZE WITH A MEDIAN ROCK DIAMETER OF D_{50} . A VARIANCE OF $\pm30\%$ IS ACCEPTABLE. Eg. IF D_{50} = 600 IS SPECIFIED THEN THE EQUIVALENT ROCK DIAMETER RANGES FROM 420mm TO 780mm
- NEITHER BREADTH NOR THICKNESS OF A SINGLE ROCK SHALL BE LESS THAN ONE HALF ITS LENGTH (ie THE ROCK SHALL BE CHUNKY RATHER THAN FLAT).
- ROCK TYPE BASALT OR OTHER APPROVED MATERIAL. TO BE CONFIRMED WITH SUPERINTENDENT BEFORE COMMENCING ROCK WORK.
- ROCKS GREATER THAN $\rm D_{50}$ =450 TO BE PLACED AND INTERLOCKED INTO POSITION AND BUILT UP TO FINAL LEVELS SHOWN, ENSURING COVERAGE OF GEOFABRIC. GAPS BETWEEN THE BOULDERS ARE TO BE FILLED BY DROPPING STONES INTO GAPS AND LOCKING INTO POSITION WITH A CROWBAR.
- ROCKS LESS THAN & EQUAL TO D₅₀=450 TO BE DUMPED & MOVED INTO POSITION. BUILD UP TO FINAL LEVELS & ENSURING COVERAGE OF GEOFABRIC.


REFERENCE POINT LOCATION FOR DRAINAGE


STRUCTURES

	<u> </u>	ROCTORES	
STRUCTURE TYPE		TAL CONTROL POINT LOCATION)	VERTICAL CONTROL (REFERENCE LEVEL)
MANHOLE	REF	€ OF MAIN SHAFT	FINISHED SURFACE LEVEL
GULLY PIT	REF	GEOMETRIC CENTRE OF PIT STRUCTURE	KERB LIP LEVEL
HEADWALL	REF	INTERSECTION OF HEADWALL FACE AND PIPE &	INVERT OF HEADWALL

ROCK SCOUR PROTECTION

OUTLET	OUTLET PIPE SIZE	VELOCITY	D ₅₀	'L'
OUT/G2	Ø 450	2.0m/s	300 mm	4.3m
OUT/B19 & OUT/B20	Ø 2/ 450	2.2m/s	300 mm	4.3m






TYPICAL SCOUR PROTECTION SECTION

- STORMWATER PIPE - CONCRETE PIER 17.5MPa SEWER MAIN SEWER IL ~ 150 LENGTH = TRENCH WIDTH

STORMWATER / SEWER BRIDGING DETAIL - SECTION

SCALE 1:20 (A1) SCALE 1:40 (A3)




STORMWATER / SEWER BRIDGING DETAIL - ELEVATION

SCALE 1:20 (A1) SCALE 1:40 (A3)

	X = WIDTH OF CON	CRETE PIERS (mm)
PIPE SIZE	FIRM/STIFF CLAY SAFE	STIFF/VERY STIFF CLAY
FIFE SIZE	BEARING >150kPa	SAFE BEARING >200kPa
600Ø - 1050Ø	600	450
1200Ø - 2100Ø	450	350


GROUND CONDITIONS TO BE VERIFIED ON-SITE BY SUPERINTENDENT. IF LESSER GROUND CONDITIONS PREVAIL, SPECIALLY DESIGNED DRILLED PIERS ARE TO BE CONSIDERED.


CONTRACTOR TO ENSURE PIPE CONNECTORS TO GULLY PITS ARE NOT CONSTRUCTED INTO THE CORNER OF TWO WALLS.





TYPICAL GULLY PIT PIPE CONNECTION DETAIL

EVISION DATE ISSUE DETAILS DRAWN DESIGN **FOREVERLEN PTY LTD** STORMWATER DRAINAGE **ISSUED FOR APPROVAL** LANDINGS 1.03.23 AMENDED COUNCIL COMMENTS NOTES AND DETAILS 24.05.23 MINOR AMENDMENTS D 06.10.23 UPDATE TO EGIS COVER PAGE AS SHOWN LENNIUM RYAN ASHWORTH STAGES 1A & 1B RPEQ 19674 aa Ryan ashworth ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION, USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE. 22-000082_1A-1B 1402 www.egis-group.com Moreton Bay









}	LOCATIO		ATCHMEN ROPERTIE		FUL	L AREA RI	UNOFF		P	PART AREA	A RUNOFF	:					NLET DESIGN							DRAIN DE	ESIGN						HEADLO	OSSES				PART	FULL				ESIGN LEVI	LS		
}								Q		I A			Qa					Qg	Qb		tc	1		Qp			Vf	S/Do Q	Qg/Qo Du/Do			Ku hu	Kw	hw	Sf ht			\neg	$\overline{}$				T	\top
DESIGN ARI	STRUCTURE No.	FRACTION IMPERVIOUS	COEFFICIENT OF RUNOFF IMPERVIOUS AREA	COEFFICIENT OF RUNOFF PERVIOUS AREA	TIME OF CONCENTRATION RAINFALL INTENSITY	SUB-CATCHMENT AREA	EQUIVALENT IMPERVIOUS AREA	SUB-CATCHMENT DISCHARGE	TIME OF CONCENTRATION	RAINFALL INTENSITY PARTIAL CATCHMENT AREA	EQUIVALENT IMPERVIOUS AREA	SUB-CATCHIMENT DISCHARGE	FLOW IN K&C(INC. BYPASS)	FLOW WIDTH	FLOW DxV	ROAD GRADE AT	NLET TYPE	FLOW INTO INLET	BYPASS FLOW	BYPASS STRUCTURE No.	CRITICAL TIME OF CONC.	RAINFALL INTENSITY	TOTAL (C × A)	PIPE FLOW	REACH LENGTH PIPE GRADE	PIPE SIZE	FULL PIPE VELOCITY	RATIO	GRATE FLOW RATIO DIAMETER RATIO	CHART(S) USED	VELOCITY HEAD	U/S HEAD LOSS COEFFICIENT U/S HEAD LOSS	W.S.E COEFFICIENT	CHANGE IN W.S.E	PIPE FRICTION SLOPE	NORMAL DEPTH	NORMAL DEPTH VEL.	PIPE U/S I.L	PIPE D/S I.L	PIPE U/S H.G.L	PIPE D/S H.G.L	GRATE LEVEL	FREEBOARD	STRUCTURE No.
Yrs	04/004	85	0.0		min mm 10 168		_	L/s		mm/h ha 207 0.05				m m	0.07		6	L/s		_	_	_	_		m %	mm	m/s	1.00	_	- 00	m	m 0.7 0.000	+	m	% m		m/s	m 23.42	m	m	m m	m 6 24.769	m	
10%	G1/B01 G2/B01					8 0.058 8 0.045	0.049			207 0.04				1.202 0.07 1.099 0.063	_	3.49	GULLY MK-S GULLY MK-S		0				_		.919 1.48 5.46 0.69	375 375	0.24	1.08		G2 T10	0.003	9.7 0.029 2.27 0.022		_	0.39 0.20	231 0.09 262 0.148						3 24.821		
10%	G2/B01					8 0.122		_		207 0.04				1.618 0.088			.9 GULLY MK-S		0				0.183		.107 2.1	375		1.36		G2/T3/T6		2.52 0.109										7 23.694		
10%	G4/B01					8 0.035		-	_	207 0.03			16 (_	4.54 2		_	0	-					.594 4.72	450	0.74	1.03				0.37 0.01		_	5.72 0.24			-			21.233 21.8		_	
10%	5/B01	0															MH1500				6.23	197 2	2.725	1475 9.	946 1.01	900	2.32	1.62	0 1	T3/T6	0.274	1.72 0.472	2 2.05	0.562	2.03 0.0	61 0.616	3.18	19.6	19.5	20.317	20.116 20.8	8 22.621	1 1.742	5/B01
10%	OUT/B0	1															HW outlet																								20.1	-		OUT/B01
10%	G1/B02	85	_											2.94 0.092			GULLY MK-S	93	_				0.185		346 1.07			3.09		G2	0.036	3.7 0.134	_	_		0.191					25.12 25.2			
10%	G2/B02		0.9			8 0.245		_		207 0.22				3.031 0.095	_		GULLY MK-S		16						.844 1.44	375	_	3.02		G1/T9	0.152	1.82 0.276	_	0.289	1.18 0.5							3 25.422		
10%	G3/B02		0.9	0.64	10 168	8 0.077	0.066	31	5	207 0.07	72 0.063	36	52 2	2.024 0.067	0.06	1.97	GULLY MK-S	52	0	-	_		_		.145 1.6	450	_	2.22			0.115	0.57 0.065	_		0.7 0.09			-		_		9 24.757	_	
10%	4/B02 5/B02		\vdash			_	-	\vdash		_	-	\vdash	-+		\vdash		MH1050 MH1050	+	-+			_	_		614 2.72	525	_		0 1	T6/T9	0.172	1.83 0.315				0.281 0.298					23.797 24.2	01 24.53 13 24.391		
10%	5/B02 6/B02		+			_	+	+		_		+	-+		+	-	MH1050 MH1350	+	-+			_			.954 2.59 .956 2.41	525 600	1.97		0 1	T3/T6 T1/T3	0.197	1.72 0.339 1.02 0.205	_		0.98 0.3	_		22.8	21.92	23.458		24.391	_	_
10%	7/B02		+ +				+	+		_			-				MH1050	+	-+						.185 2.3	600	2.37	_	0 1	T3	0.202	1.4 0.402		0.456	1.19 0.14							18 23.244		
10%	8/B02											\vdash					MH1200		-+						3.12 1.35	750	2.14		0 1	T9/T10	0.233	2.17 0.506		_		41 0.476			20.52		21.373 22.30	_	_	
10%	9/B02							+									MH1200				6.1		-		1.66 1.62	750	2.32	_	0 1		0.275	0.91 0.25	_		1.35 0.38							2 22.603		
10%	G1/B03	85	0.9	0.64	10 168	8 0.243	0.208	97	5	207 0.22	25 0.197	113	113 3	3.353 0.104	0.07	0.69	GULLY MK-S	102	11	G2/B03	5	207 0	0.197	102 56	.493 0.62	375	0.92	2.74	1	G1	0.044	3.46 0.151	1	0.151	0.34 0.19	92 0.24	1.37	21.1	20.75	21.978	21.787 22.12	9 22.49	0.361	G1/B03
10%	G2/B03	85	0.9	0.64	10 168	8 0.234	0.201	94	5	207 0.21	17 0.19	109	120 3	3.571 0.107	0.08	0.69	GULLY MK-S	107	13	G1/B13	5.75	201 0	0.464	246 16	.413 0.94	525	1.14	2.16	0.42 1	T3/T6	0.066	1.69 0.112	1.99	0.131	0.33 0.0	54 0.29	2.01	20.675	20.52	21.675	21.621 21.80	7 22.1	0.293	G2/B03
10%	3/B03	0															MH1050				5.89	200 0	0.464	245 13	.134 0.91	525	1.13	2.16	0 1		0.065	1.87 0.122		_		0.292			20.38	21.499	21.457 21.63	6 22.034	1 0.398	3/B03
10%	4/B03																MH1200						_		.941 0.67	525	_	2.11			0.099	0.96 0.095	_	_	0.49 0.1	_					21.184 21.46	_	_	
10%	5/B03	0													\vdash		MH1200				6.38	196 0	0.637	347 35	.758 0.84	525	1.6	2.11	0 1	T1/T3	0.131	1.23 0.162	2 1.4	0.183	0.65 0.23	233 0.383	2.05	20.1	19.8	21.023	20.79 21.20	6 22.197	7 0.991	5/B03
10%	F1/B04	85	0.9	0.64	10 168	8 0.106	0.091	42	5	207 0.09	98 0.086	49	19 2	2.197 0.033	0.02	1.52	F1-6x9 on-grade 50% Blockage	8	11	F2/B04	5	207 0	0.086	38 22	.297 1.57	375	0.34	1.28	1	G1	0.006	7 0.042	2	0.042	0.05 0.0	01 0.105	1.49	23.8	23.45	24.239	24.229 24.2	31 25.073	0.792	P F1/B04
10%	F2/B04		0.9	0.64	10 168	8 0.072	0.062	29	5	207 0.06	67 0.058	34	30 2	2.221 0.038	0.02	1.52	F1-6x9 on-grade 50% Blockage	10	20						131 1.35	375	0.56	2.13		T1	0.016	0.92 0.015			0.13 0.0							9 24.733		
10%	3/B04							l									MH1050								414 2.14		_		0 1		0.016	1.5 0.024	_	_		0.126		23.3			24.169 24.20	_		
10%	G1/B05					8 0.232		-	-					2.908 0.091	-				20				_		948 2.11	375	_	2.84	1	G2	0.042	4.15 0.175	_			0.164						6 24.655		
10%	G1/B06 G1/B07				-	8 0.084 8 0.136			_	207 0.07 207 0.12			50 2 63	2.461 0.079 0.046		0.00	GULLY MK-M SAG MK-S		0						.39 2.82	375 450	_	2.68		G2 G2	0.011	4.51 0.048 6.02 0.048			0.08 0.00	002 0.101		21.8			22.753 22.80 22.753 22.80	3 23.196		
10%	G1/B0/					8 0.285		_		207 0.12	_	_		3.345 0.104	_		GULLY MK-S		23		_	_	_		6.5 1.66	375	0.99	1.77		G1	0.006	5.79 0.29		_	0.03 0.00							9 23.714		
10%	G2/B08				10 168	_	0.086	_		207 0.09	_		70 2				GULLY MK-S	70					_		938 4.32	375		1.87		T6/T9		2.17 0.288		_		071 0.185		21.9				3 23.316	_	
10%	G1/B09	85	0.9	0.64	10 168	8 0.204	0.175	82		207 0.18	_	95	95 3	3.223 0.1	0.07	0.6	GULLY MK-S		6	G2/B09		_	0.165		9.63 1.38	375	0.81	1.59	_	G1	0.033	6.61 0.22			1.15 0.25			22.54			22.532 22.9	9 23.784	0.805	G1/B09
10%	G2/B09	85	0.9	0.64	10 168	8 0.016	0.014	6	5	207 0.01	15 0.013	7	13 1	.257 0.046	0.03	1.35	GULLY MK-S	13	0	G1/B07	5.18	206 0	0.178	102 18	.874 3.44	375	0.92	1.14	0.13 1	T1/T3	0.043	1.1 0.048	3 1.24	0.054	1.47 0.33	35 0.144	2.61	22.25	21.6	22.485	22.207 22.53	8 23.588	1.049	G2/B09
10%	G1/B10	85	0.9	0.64	10 168	8 0.09	0.078	36	_	207 0.08	84 0.073	42	42	0.031		0.6 1.	77 SAG MK-S	42	0	0.00.0	5 :				522 1.19	375	_	1.19		G2	0.007	9.7 0.072				0.12		-			21.373 21.4	3 22.554	1.124	
10%	G1/B11				10 168			45		207 0.10	_	_		2.522 0.081	_		GULLY MK-M	52	_			_	_		.74 1.48	375		1.29		G2	0.011	9.7 0.109		_	0.17 0.0							4 22.56		
10%	G1/B12		0.9		10 168			37		207 0.08			43		0.04	0.69			0	G1/B14					595 0.7	375		2.84		G2	0.008	4.16 0.032			0.06 0.00			_			21.787 21.82	_	_	
10%	G1/B13 G1/B14		0.9		10 168			19		207 0.04	_		38	0.029		0.1	SAG MK-S SAG BK-S	38	0				0.044		524 1.53 409 2.05	375 375		2.38		G2 G2	0.006	5.4 0.033 5.34 0.011				003 0.106		20.6	20.5			3 21.942 8 21.943		
10%	G1/B14				10 168			1 .0	-	207 0.04			3/1 /	2.131 0.07	0.04	0.75 2		34							812 1.91	375	0.2	1.21		G2 G2	0.002	9.7 0.046			0.02 0.0	_						3 22.126	_	
10%	G1/B15		0.9			8 0.038		-		207 0.00				1.509 0.076	_	0.75 2			0		_		_		574 2.72		_	1.14		G2	0.003	9.7 0.040		-		0.063				-	21.184 21.19			
10%	G1/B17			_		8 0.119		_		207 0.03	_	_	55 2		_		GULLY MK-S	55			_	_	0.096		2.05 2.36	375	_	2.05		G2	0.013	6.81 0.088	_	_		0.003		22.458				25 23.798		
10%	G1/B18		_	0.64		8 0.212				207 0.19	_	_	_	2.519 0.081	0.09		GULLY MK-S		11				_		496 2.11			2.74		G2	0.032	4.38 0.139		_		0.151		_				1 23.578		
10%	F1/B19					0	_	0			0		780	0.15			RSIP-9x9	174	_				_		151 1.63	450		1.78		G1	0.061	5.76 0.352		_		0.219					18.319 18.84		_	_
10%	OUT/B1	9															HW outlet																									9 18.7	_	OUT/B19
10%		0	\perp			0	0	0		0	0	0	1386	0.15			RSIP-9x9	174	1212	LOST	1 :	286	0	174 6.	151 1.63	450	1.09	1.78	1	G1	0.061	5.76 0.352	2	0.352	2.83 0.0	41 0.219	2.26	18.2	18.1	18.493				F1/B20
10%	OUT/B2		 					1			40				1		HW outlet	1		01/01	_				400		1	1.05			1						1					9 18.7		OUT/B20
10%	G1/B21			0.64		8 0.017				207 0.01				0.056 0.981 0.064				28	_		_	207 0		_	428 11.53 .505 6.33		_	1.67		G2 G1		8.77 0.03 7 0.017				0.056					23.797 23.85 20.96 22.55			
10%	G1/C1 2/C1			0.04	10 168	0.052	0.044	21	9	201 0.04	40 0.042	24	24 (0.064	0.07	4.01 3.	38 GULLY MK-S MH1350	24	U						.143 1.04				0 1		0.002	2.32 0.063									20.96 22.5 19.776 20.0			
10%	OUT/C1		+ +	_			+	+					-				HW outlet	+	-+		U.E.1	200 0	0.171	50 13		513	0.10	1.6	-	13/110	0.021	2.02 0.000	2.10	0.074	1.21 0.10	2 0.170	1.00	10.0	10.0	20.001		6 20.15		OUT/C1
10%	1/C2						1										PC				1 :	286	0	0 7	.39 0.5	375	0				0	2 0		0	0 0	0	0	19.967	19.93	20.102	20.102 20.10			
10%	G2/C2			0.64	10 168	8 0.058	0.05	23	5	207 0.05	54 0.047	27	27 1	1.158 0.065	0.07	4.82 3		27	0		_		-		.062 0.5		_	1.08	1	G2		9.7 0.03		_							20.07 20.10			
10%	G1/C3		_	0.64										1.197 0.066	0.08	5.17 2	97 GULLY BK-S	30	0	G1/F3					.147 1.86		_	1.07		G1	0.004	7 0.026		_		268 0.09					20.29 20.6			
10%	1/G1									207 0.08					$oxed{\Box}$		MH	41	_						24 0.5			1.13		G1	0.007	7 0.05									20.479 20.53			
10%	2/G1									207 0.06						_	MH	35							25 0.5			1.12				1.93 0.046		_							20.399 20.4		_	
10%	3/G1									207 0.06					-		MH	35	_						25 0.5			1.2				1.51 0.074									20.243 20.39			
10%	4/G1 5/G1									207 0.06 207 0.07					-		MH MH	35	_						25 0.5 171 0.53			1.07				0.78 0.031 1.12 0.069				0.277					20.168 20.24 20.077 20.16		_	
10%	5/G1 6/G1			0.04	10 168	0.081	0.069	52	9	201 0.07	10 0.065	38	30		+	_	MH MH1050	38	U					1/5 8. 174 26					0.21 1			1.12 0.069									19.794 20.09			
10%			+ +		_							+					HW outlet	+ +	-+	-	0.00	100 0	0.022	11-4 20	.710 0.0	400	1.1	1.02	J 1	13/10	0.001	1.30 0.12	2.01	0.142	V.U1 U.1	71 0.323	1.45	13.002	13.3	10.000		4 20.15	_	OUT/G1
10%	F1/G2		+ +			0	0	0		0	0	0	174	0.15			RSIP-6x6	116	58	LOST	1 :	286	0	116 8.	365 1.55	450	0.73	1.42	1	G1	0.027	7 0.19		0.19	2.28 0.0	81 0.177	2	18	17.87	18.237	18.047 18.42			_
10%	_																HW outlet																									7 18.516		OUT/G2
·							•																																			•		

STORMWATER DRAINAGE CALCULATIONS - MINOR 10% AEP

REVISION DATE ISSUE DETAILS

DRAWN DESIGN

A 14.12.22 ISSUED FOR APPROVAL

B 01.03.23 AMENDED COUNCIL COMMENTS

IB AA

C 24.05.23 MINOR AMENDMENTS

D 06.10.23 REVISED AS PER COUNCIL RFI

RT AA

DESIGN CHECK

RYAN ASHWORTH RPEQ 19674

FOR & ON BEHALIK OF CALIBRE PROFESSIONAL SERVICES PTY LTD

REPTIONAL COUNCIL

LENNIUM

GROUP



LANDINGS
STAGES 1A & 1B

STORMWATER
CALCULATION TABLES
SHEET 1 OF 2

DRAWING NO.

ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO 22-000082_1A-1B 1430

	CATION	PROP	ERTIES				OFF											ILET DESIGN						D																					
		fi	Ci Cr	tc	Ι	Α	CA	Q	tc	1	A C	A (Q Qa)a					Qg	Qb		tc	1 (CA Q	Qp L	S		Vf	S/Do C	Qg/Qo Du/Do		Vf2/2g	Ku hu Kv	v hv	v Sf	hf	dn '	Vn							
	STRUCTURE No.	FRACTION IMPERVIOUS COEFFICIENT OF RUNOFF	IMPERVIOUS AREA COEFFICIENT OF RUNOFF	PERVIOUS AREA TIME OF CONCENTRATION	RAINFALL INTENSITY	SUB-CATCHMENT AREA	EQUIVALENT IMPERVIOUS AREA	SUB-CATCHMENT DISCHARGE	TIME OF CONCENTRATION	RAINFALL INTENSITY	PARTIAL CATCHMENT AREA	EQUIVALEN I IMPERVIOUS AREA	SUB-CALCHMENT DISCHARGE FLOW IN K&C(INC. BYPASS)	<u> </u>	FLOW DEPTH	FLOW DxV	ROAD GRADE AT INLET	TY PE	FLOW INTO INLET	BYPASS FLOW	BYPASS STRUCTURE No.	CRITICAL TIME OF CONC.	=	TOTAL (C x A)	PIPE FLOW REACH LENGTH	PIPE GRADE	PIPE SIZE	FULL PIPE VELOCITY		GRATE FLOW RATIO DIAMETER RATIO	CHART(S) USED	VELOCITY HEAD	U.S HEAD LOSS COEFFICIENT U.S HEAD LOSS W.S.F. COFFFICIENT	CHANGE IN W.S.F.	PIPE FRICTION SLOPE	PIPE FRICTION HEAD LOSS	NORMAL DEPTH	NORMAL DEPTH VEL.	PIPE U/S I.L		PIPE U/S H.G.L	PIPE D/S H.G.L	W.S.E		FREEBOARD
				min	mm/h	ha	ha	L/s	min	mm/h	ha h	na L	/s L/s	/s m	m		% %		L/s	L/s		min r	nm/hr l	ha L/	/s m	%	mm	m/s				m	m	m	%	m	m n	m/s m	n m		m	m r	m m		m
(G1/B01	85	1 0.7	7 10	294	0.058 0	0.056	45	5	370 (0.053 0.0	052 5	i4 54	4 1.63	7 0.085	0.09	3.49 3	GULLY MK-S	52	2	G1/C1	5	370 0.	.052 5	16.919	1.48	375	0.47	1.29	1	G2	0.011	9.7 0.108	0.10	08 1.71	0.222	0.126 1	1.59 23.	.42 23.1	17 2?	3.584 23	23.296 23.	3.692 24.7	69 1	1.077
	G2/B01	85	1 0.7	7 10	294	0.045 0	0.044	36	5	370 (0.042 0.0	041 4	2 42	2 1.52	21 0.076	0.08	3.91 3	GULLY MK-S	42	0	G3/B01	5.15	367 0.	.094 9	3 55.46	0.69	375	0.85	1.26	0.45 1	T10	0.036	2.28 0.083 2.6	6 0.09	97 0.27	0.154	0.219	1.4 22	2.4 22.0	J2 27	2.729 2	22.58 22.	2.826 24.8	21 1	1.995
	G3/B01	85	1 0.7	7 10	294	0.122 0	0.118	96	5	370 (0.113 0.1	111 1	14 114	14 2.14	6 0.107	0.14	2.42 2.	GULLY MK-S	96	18	G1/B10	5.85	357 0.	.206 18	84 18.107	2.1	375	1.67	1.86	0.51 1	G2/T3/T6	0.142	1.88 0.267 2.2	8 0.32	24 1.91	0.372	0.237 2	2.51 2:	21.6	j2 22	2.314 21	21.967 22.	2.637 23.6	94 1	1.057
(G4/B01	85	1 0.7	7 10	294	0.035 0	0.034	28	5	370 (0.032 0.0	032 3	33	3 1.22	7 0.07	0.08	4.54 2.6	4 GULLY MK-S	33	0	G1/B16	5.98	355 0.	.238 21	15 10.594	4.72	450	1.35	1.1	0.15 0.83	T1/T3	0.093	0.44 0.041 0.4	8 0.04	14 6.08	0.158	0.183	3.54 21	1.6 21.1	.1 21	1.927 21	21.283 21	1.971 23.	17 1	1.199
_	5/B01	0				$\perp \perp \perp$												MH1500	\perp			6.23	351 3.	.057 18	886 9.946	1.01	900	2.96	1.88	0 1	T3/T6	0.419	1.65 0.691 1.8	9 0.79	93 1.12	0.1	0.774 3	3.24 19	9.6 19.5	5 20	0.385 20		1.178 22.6	_	1.443
_	OUT/B01		\perp													$\sqcup \Box$		HW outlet	\perp							\perp											$\bot \bot \bot$		\bot		$\perp \perp$		0.274 20	_	
_	G1/B02	85	1 0.7	_		0.228	_				0.211 0.2			_	0.119		1.21 3	GULLY MK-S		161	G1/B05			.207 5					3.58	1	G2		3.18 0.035	0.03	_	_							5.462 25.4		0.002
_	G2/B02	85	1 0.7	_										_			1.19 3		_	107		_		.429 17					3.79		G1/T9		2.02 0.249 2.0	_	_		0.257 2	_	23.3				5.42 25.4	_	0.002
	G3/B02	85	1 0.7	7 10	294	0.077 0	0.075	61	5	3/0 (0.072 0.0	.0/ 7	2 179	19 3.25	9 0.101	0.12	1.9/ 3	GULLY MK-S	100	79	G1/B17			0.5 26			450		3.16		T1/T3	0.14	0.88 0.124 0.8				0.286 2						4.752 24.7		0.005
-	4/B02 5/B02	0	-		+-	+ +	+	-	-	+		+	_	_	+	+	-+	MH1050	+	-				874 42	_		525		_	0 1	T6/T9	0.112	1.73 0.194 1.8 1.38 0.336 1.5		_	_		_	3 22.8	-		24.284 24	_	-	0
_	6/B02	0	-	+	+	+ +	+	+	\rightarrow	+	_	+	+	_	+	 	-+	MH1050 MH1350	+ +	-				.193 62			525 600		_	0 1 0 1	T3/T6 T1/T3	0.243	1.38 0.336 1.5 0.73 0.18 0.8		_	_	0.0.0		2.8 21.9 1.9 21.4	_		23.539 24. 23.154 23.		_	0.072
_	7/B02	0	+		+		+	-	+	+		+	+	_	+	+	_	MH1050	+	\rightarrow				.389 67	_					0 1	T1/T3	0.247	0.73 0.16 0.8	_					1.9 21.4.				3.19 23.2		0.044
_	8/B02	0	-		1		-+	-+	-+	+		-	+		1		-+	MH1200	+ +	-				.943 98						0 1	T6/T9	0.255		3 0.54	_	_			1.1 20.5			22.045 22.		_	0.386
-	9/B02	0			1		-+			-+		+						MH1200	1 1	_		_			316 24.66					0 1	T1/T3	0.453	1.38 0.625 1.5			_		_	0.5 20.1			21.075 22			0.473
_	G1/B03	85	1 0.7	7 10	294	0.243 0	0.235	192	5	370	0.225 0.2	221 2	27 22	27 5.49	0.134	0.1	0.69 3		116	111	G2/B03			.221 11			375		3.17	1	G1	0.056	3.03 0.17	0.1					1.1 20.7			21.873 22.			0.201
	G2/B03	85	1 0.7	7 10	294	0.234 0	0.226	185	5	370	0.217 0.2	213 2	18 32	29 6.10	0.149	0.13	0.69 3	GULLY MK-S	58	272	G1/B13	5.75	358 0	1.52 17	74 16.413	0.94	525	0.8	2.29	0.31 1	T1/T3	0.033	1.42 0.047 1.6	1 0.05	53 0.16	0.027	0.236 1	1.84 20.6	675 20.5	52 2°	1.826 21	21.799 21.	1.879 22	.1 0	0.221
	3/B03	0																MH1050				5.89	356 0	0.52 17	70 13.134	0.91	525	0.79	2.48	0 1	T6/T9	0.032	1.77 0.056 1.9	3 0.0	61 0.16	0.021	0.236 1	1.81 20	0.5 20.3	38 21	1.743 21	21.723 21.	1.804 22.0	34 0).229
	4/B03	0																MH1200				6.01	354 0.	.613 18	88 35.94	0.67	525	0.87	2.6	0 1	T1/T3	0.038	0.56 0.022 0.6	3 0.02	24 0.19	0.068	0.273 1	1.65 20.	.36 20.1	12 21	1.701 2	21.632 21.	1.725 22	2 0).275
	5/B03	0														\Box		MH1200				6.38	349 0.	.715 38	87 35.758	0.84	525	1.79	2.94	0 1	T6/T9	0.163	1.64 0.268 1.7	7 0.27	77 0.81	0.289	0.422 2	2.07 20	0.1 19.8	8 21	1.365 21	21.075 21.	1.642 22.1	97 0	0.556
F	F1/B04	85	1 0.7	7 10	294	0.106 0	0.102	83	5	370	0.098 0.0	096 9	19 69	9 3.53	88 0.053	0.04	1.52 3	F1-6x9 on-grade 50% Blockage	17	52	F2/B04	5	370 0.	.096 4	17 22.29	1.57	375	0.42	2.31	1	G1	0.009	4.16 0.038	0.03	38 0.07	0.016	0.117 1	1.58 23	3.8 23.4	15 24	4.627 24	24.611 24.	4.665 25.0	73 0	0.408
_	F2/B04	85	1 0.7	7 10	294	0.072	0.07	57	5	370	0.067 0.0	065 6	7 10	3.06	0.064	0.06	1.52 3	F1-6x9 on-grade 50% Blockage	21	83	LOST			.162 8			375	0.74		0.31 1	T1	0.028	0.98 0.027		27 0.22			1.74 23.				24.566 24			0.122
_	3/B04	0			1	0.000	0.000	400	_	070	0044	04 -	40 0-			10.7	4.05	MH1050	1	005	04/501			.162 8	_				3.39	0 1	T3/T6	0.027		_	39 0.21	_	0.145 2		3.3 23.1	_		24.514 24			0.083
_	G1/B05	85	1 0.7	_		0.232 0	-	_	_	_	0.214 0.3	_	-	_			1.65 3.0		91	_	G1/B21		_	0.21 9			375		3.58	1	G2	0.035	3.18 0.111	_	11 0.27				.31 23.1	_		24.514 24.			0.003
_	G1/B06 G1/B07	85 85	1 0.7	_			_	66 107		370 (0.077 0.0	_	78 48i 26 20i	_	0.168	_	0.86 3 0.92 2.6		30 28	458 178	G1/B10 G1/B10		_	.076 3	_				3.64	1	G2 G2	0.004	3.1 0.012 3.77 0.006	_	12 0.03 06 0.01	_	0.078 1		1.8 21.73 1.8 21.63			23.154 23. 23.154 23		_	0.029
_	G1/B07 G1/B08	85	1 0.7			0.136 0		_			0.125 0.1		_	_		_	0.92 2.6			123	G2/B08		370 0.					1.29	_	1	G2 G1		3.12 0.263	_	_		0.073 1		.36 21.9			23.154 23		_	0.03
_	G2/B08	85	1 0.7		294		-	_				-	14 21			-	1.86 3	GULLY MK-S		217	G2/B06 G1/B11			1.35 13			375			0 1	T6/T9	0.064	1.82 0.147 2.0	-	_				1.9 21.6			-	3.087 23.3	-	0.212
_	G1/B09	85	1 0.7	_	_			_	_	_	0.189 0.1		_	90 5.24	_		0.6 3		108	_	G2/B09	_	_	.185 10					_		G1	0.049	3.48 0.169		59 0.38		0.101 3	_	.54 22.2	_		23.318 23.			0.229
_	G2/B09	85	1 0.7	_	_		_		_		_		5 97		9 0.087		1.35 3		87	10				0.2 19			375		2.87		T1/T3	0.043	1.35 0.213 1.4	_						_		22.875 23.			0.26
_	G1/B10	85	1 0.7	_						370	_		4 73	_	0.13		0.6 1.7		177	-	G1/B15			.082 17			375		_		G2		3.32 0.433	_	33 1.01		0.284 1			_		22.045 22			0.05
_	G1/B11	85	1 0.7	_	294			88					_	_	8 0.149	_	0.79 3	GULLY MK-M	177	_	G1/B15		_	.101 17	_		375		3.52	1	G2		3.24 0.425	0.42				2.16 21.				_	2.539 22.		0.021
	G1/B12	85	1 0.7	7 10	294	0.093	0.09	73	_		0.086 0.0	084 8	7 87	_	28 0.095		0.69 3	GULLY MK-S	14	73	G1/B14	5	370 0.	.084 1	_		375			1	G2		3.85 0.003	0.00	0.01	0.001	0.078 0		.76 20.7	.7 21	1.873 21	21.873 21.	1.876 22	.1 0).224
	G1/B13	85	1 0.7	_	294							049 5	0 91		0.15		0.1 3	SAG MK-S	9		G1/B14	_		.049 9	9 6.524				3	1	G2		3.8 0.001	0.0	_	0).6 20.5	_	_	_	1.724 21.9).218
-	G1/B14	85	1 0.7	_	_		_	37					4 102	_	0.15	_	0.1 3	_	13	_	LOST			.043 1	_				3.08	1	G2		3.71 0.003		0.01	_	0.000	1.2 20.		_		21.723 21.		_).218
_	G1/B15	85	1 0.7	_	294		0.01						77	_	_	_	0.75 2.9		177		G1/B13			.066 17	0.012		375		_	1	G2		3.18 0.418	_	18 1.02			2.39 20.					2.12 22.1		0.006
_	G1/B16	85	1 0.7	_	294				5		_		15 35	_	_	_	0.76 3.0		35	0	G1/B14			.035 3						1	G2		5.41 0.029	_	29 0.04	_			.77 20.7				1.662 22.1	_	0.476
-	G1/B17	85	1 0.7	_			0.115	٠.					11 190	_	_		2.34 3	GULLY MK-S	120	70	G1/B07	_		.108 12			375		3.55	1	G2		3.21 0.193		0.47			_	458 22.17	_			3.788 23.7		0.01
-	G1/B18	85	1 0.7	7 10	294	0.212 0		167	5		0.196 0.1			_	0.137	-	2.34 3		44	-	G1/B06		370 0.				375		3.53		G2		3.23 0.026	_	26 0.06				244 22.19	-		-	3.566 23.5	_	0.012
+	F1/B19 OUT/B19	U	+	_	+	0	0	0	\rightarrow	+	0 (0	0 110	UU	0.15	-	-+	RSIP-9x9 HW outlet	174	920	F1/B20	-	506	0 17	74 6.151	1.63	450	1.09	1.78	'	G1	0.061	5.76 0.352	0.3	2.83	U.U41	0.219 2	2.20 18	3.2 18.1	+ 18	8.493 18	_	3.845 20 3.319 18	-	1.155
_	F1/B20	0	+		+	0	0	0	+	+	0 (0	0 202	26	0.15	+	-+	RSIP-9x9	174	1852	LOST	1	506	0 17	74 6.151	1.63	450	1.09	1.78	1	G1	0.061	5.76 0.352	0.34	52 2.83	0.041	0.219 2	2.26 18	2 18	1 15	8.493 1			-	1.155
_	OUT/B20	<u> </u>	-		+	+ " +	-	-+	-+	\rightarrow	<u> </u>		202		0.13	+		HW outlet	1.74	.002	2001	-+	500	- 17	0.101	1.00	700	1.03	1.70	'		0.001	0.70 0.002	0.3	2.00	0.041	0.2.13	10	- 10.1	- 10			3.319 18	-	
_		85	1 0.7	7 10	294	0.017 0	0.017	14	5	370	0.016 0.0	016 1	6 30	02 4.91	9 0.125	0.15	1.85 3.1		45	256	G1/B18	5	370 0.	.016 4	15 2.428	11.53	375	0.41	2.98	1	G2	0.009	3.84 0.033	0.03	33 0.07	0.002	0.07 3	3.18 23	.2 22.9	32 24	4.285 2				0.028
						0.052													49	_					19 24.505		375				G1		7 0.072				0.085 2								
	2/C1																	MH1350				5.27	366 0.	.158 15	54 19.143					0 1	T9/T10		2.2 0.219 2.6	3 0.26	3 1.15	0.196	0.268	1.83 19	.8 19./	.6 2	0.09 1'	9.868 20	0.352 22.7	42 :	2.39
	OUT/C1																	HW outlet																								19.	9.868 20.	15	
-	1/C2	0																PC								0.5		0					2 0				0								
_						0.058 0													52	_					52 18.062		375				G2		9.7 0.109				0.169 1								
-	G1/C3					0.064 0								_	9 0.08	0.11	5.17 2.9		55	_	G1/F3				55 16.147				1.23		G1		7 0.088				0.122 1								
-	1/G1					0.089 0								_	\perp	\vdash	-	MH	83	-					33 24		375				G1		3.35 0				0.224								0
-	2/G1					0.075 0								_		+	-+	MH	70	-							375			$\overline{}$	T1		1.25 0				0.375 1								
_					_	0.075 0		_				_	_	_	_	\vdash	-	MH	70	-					17 25		375				T1		0.97 0.06				0.375 1								
_						0.075 0									+	\vdash		MH	70 75		\rightarrow				81 25 49 8.171					0.24 0.83			0.39 0.044				0.45 1 0.45 2								
_	5/G1 6/G1	85 0	1 0.7	10	294	0.081 0	0.076	04	5	3/0 0	0.075 0.0	J/3 1	υ /5	U I	-			MH MH1050	15	U										0.21 1	T1 T3/T6		0.81 0.143 1.58 0.385 1.7												0
_	OUT/G1	·	_		1		+		-	+		-			+	+	_	HW outlet	+ +	-		0.00	J40 U.	.001 34	20.4/3	0.0	400	2.10	2.41	v 1	10/10	0.244	1.30 0.303 1.7	0.4	1.09	0.081	0.40	2.10 19.0	UE 18.5				9.903 20.	_	v. I J I
_	F1/G2	0	-	_	+	0	0	0	\rightarrow	-+	0 (0	17/	74	0.15	 		RSIP-6x6	116	58	LOST	1	506	0 11	16 8.365	1.55	450	0.73	1.42	1	G1	0.027	7 0.19	0.1	0 220	0.004	0.177	2 1	0 175	87 15	8 237 1		3.427 20		1.573
							٠ ١																													() ()81									

STORMWATER DRAINAGE CALCULATIONS - MAJOR 1% AEP (INCLUDING 20% ABOVE STANDARD 1% AEP INTENTIES FOR CLIMATE CHANGE)

REVISION DATE ISSUE DETAILS DRAWN DESIGN A 14.12.2 ISSUED FOR APPROVAL
B 01.03.23 AMENDED COUNCIL COMMENTS
C 24.05.23 MINOR AMENDMENTS
D 06.10.23 REVISED AS PER COUNCIL RFI ISSUED FOR APPROVAL DESIGN CHECK APPROVED RYAN ASHWORTH RPEQ 19674 aa Kyan Uslworth Or & On BEHALIK OF CALIBRE PROFESSIONAL SERVICES PTY LTD Moreton Bay


FOREVERLEN PTY LTD LENNIUM





LANDINGS STAGES 1A & 1B


STORMWATER CALCULATION TABLES SHEET 2 OF 2


DISCLAIMER ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION, USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE, 22-000082_1A-1B 1431














BIO RETENTION PARTICLE SIZE DISTRIBUTION AND PROPERTIES GUIDE:

(SOURCE: BIOFILTRATION MEDIA GUIDELINES (VERSION 3.01), PREPARED BY THE FACILITY FOR ADVANCING WATER BIOFILTRATION (FAWB), JUNE 2009.)

MATERIAL COMPOSITION RANGE GUIDE:

CLAY AND SILT	<3%	(<0.05mm)
VERY FINE SAND	5-30%	(0.05-0.15mm)
FINE SAND	10-30%	(0.15-0.25mm)
MEDIUM TO COARSE SAND	40-60%	(0.25-1.0mm)
COARSE SAND	7-10%	(1.0-2.0mm)
FINE GRAVEL	<3.0%	(2.0-3.4mm)

IT IS ESSENTIAL THAT THE TOTAL CLAY AND SILT MIX IS LESS THAN 3% (w/w) TO REDUCE THE LIKELIHOOD OF STRUCTURAL COLLAPSE OF SUCH SOILS.

SOIL SPECIFICATIONS

- TOTAL NITROGEN CONTENT <1000mg/kg
- ORTHOPHOSPHATE CONTENT <80mg/kg SOILS WITH TOTAL PHOSPHORUS CONCENTRATIONS > 100mg/kg SHOULD BE TESTED FOR POTENTIAL LEACHING. WHERE PLANTS WITH MODERATE PHOSPHORUS SENSITIVITY ARE TO BE USED, TOTAL PHOSPHORUS CONCENTRATIONS SHOULD BE <20mg/kg)
- ORGANIC MATTER CONTENT AT LEAST 3% (w/w). AN ORGANIC CONTENT LOWER THAN 3% IS LIKELY TO HAVE TOO LOW A WATER HOLDING CAPACITY TO SUPPORT HEALTHY PLANT GROWTH, IN ORDER TO COMPLY WITH BOTH THIS AND THE TOTAL NITROGEN AND ORTHOPHOSPHATE CONTENT REQUIREMENTS, A LOW NUTRIENT ORGANIC MATTER WILL BE REQUIRED.
- pH AS SPECIFIED FOR 'NATURAL SOILS AND SOIL BLENDS' 5.5-7.5 (pH 1:5 IN
- ELECTRICAL CONDUCTIVITY AS SPECIFIED FOR 'NATURAL SOILS AND SOIL BLENDS' <1.2 dS/m

BIO RETENTION INSTALLATION STANDARD NOTES

THE PLACEMENT OF DRAINAGE. TRANSITION AND FILTER MEDIA LAYERS MUST BE UNDERTAKEN CAREFULLY TO ENSURE CORRECT DEPTH, SLOPE AND COMPACTION:

DEPTH: FILTER MEDIA SHOULD BE INSTALLED AND COMPACTED IN TWO LIFTS FOR DEPTHS OVER 500mm.

THE TOP SURFACE OF THE DRAINAGE LAYER, TRANSITION LAYER AND FILTER MEDIA LAYER SHOULD BE FLAT. A SPREADER BAR SHOULD LEVEL THE SURFACE OF EACH LAYER

COMPACTION: THE FILTER MEDIA MUST BE LIGHTLY COMPACTED DURING INSTALLATION TO PREVENT THE MIGRATION OF FINE PARTICLES. THIS CAN BE ACHIEVED WITH A SINGLE PASS OF A LIGHT ROLLER SUCH AS A DRUM LAWN ROLLER, A VIBRATING PLATE CAN ALSO BE USED TO COMPACT SMALL BIO RETENTION SYSTEMS OR 'POZITRACK' BOBCATS CAN BE USED FOR LARGE SYSTEMS, ENSURE ONLY ONE COMPACTING PASS IS MADE OVER THE MEDIA FOR LIGHT COMPACTION.

CONTRACTOR TO ENSURE BIOFILTRATION FILTER MEDIA MEETS THE CRITERIA OUTLINED IN THE MARCH 2008 VERSION OF THE GUIDELINE SPECIFICATION FOR SOIL MEDIA IN BIORETENTION SYSTEMS (VERSION 2.01), FACILITY FOR ADVANCING WATER BIOFILTRATION.

.03.23 AMENDED COUNCIL COMMENTS

24.05.23 MINOR AMENDMENTS D 06.10.23 REVISED AS PER COUNCIL RI

BIO-RETENTION/DETENTION BASINS CONSTRUCTION SEQUENCE AND NOTES:

- 1. ESTABLISH SEDIMENT AND EROSION CONTROL MEASURES IN CATCHMENT, INCLUDING SILT FENCES, SEEDING OF ALLOTMENTS, & FULL WIDTH VERGE TURFING.
- SURVEY BASIN LOCATION
- INSTALL OVERFLOW PIT AND ENSURE PIT CREST IS AT DESIGN LEVEL. THIS PIT CREST WILL THEN BE USED AS A DATUM FROM WHICH OTHER LEVELS WITHIN THE BASIN WILL BE MEASURED. THE PIT REQUIRES HOLES FOR DRAINAGE PIPE CONNECTIONS WHICH CAN BE DRILLED AT THIS STAGE OR AFTER STEP 5 BELOW.
- EXCAVATE SURROUNDING LANDFORM TO DESIGN SUBSOIL LEVEL (ACHIEVING SURROUNDING LEVEL AT THIS STAGE REDUCES THE NEED FOR EARTHWORKS ADJACENT TO THE BASIN AFTER THEY HAVE BEEN
- EXCAVATE BASIN TO DESIGN DEPTH ENSURING BASE OF POD HAS MINIMUM 0.25% GRADE TOWARDS PIT. ENSURE BASE OF BASIN IS FREE FROM DEBRIS.

SUPERINTENDENT INSPECTION AND SIGN OFF REQUIRED BEFORE PROCEEDING.

- LINE SYSTEM WITH GEOFABRIC, AND EXTEND GEOFABRIC A MINIMUM OF 500 MM BEYOND TOP OF EXCAVATION. THESE ARE THE FLAPS REFERRED TO IN ITEM 13 BELOW.
- PLACE DRAINAGE LAYER (USING CLEAN 5-7mm AGGREGATE) TO DESIGN LEVEL.
- NOTE THAT CORRECT FUNCTIONING OF THE DRAINAGE PIPES IS CRITICAL TO THE PERFORMANCE OF THE BIORETENTION SYSTEM, DIG TRENCHES IN DRAINAGE LAYER AND PLACE DRAINAGE PIPES, ENSURE PIPES ARE LAID AT MIN 0.5% SLOPE WITH NO LOCALIZED DEPRESSIONS VERIFIED USING LEVEL OR STRING LINE ALL JOINTS AND JUNCTIONS IN PIPES TO BE SEALED. CONNECT CLEAN OUT POINTS ENSURING TOP OF CLEAN OUT POINTS ARE NOT LESS THAN 50mm BELOW OVERFLOW PIT CREST.

- SUPERINTENDENT INSPECTION AND SIGN OFF REQUIRED BEFORE PROCEEDING.

 10. COVER DRAINAGE PIPES WITH DRAINAGE MEDIA, ENSURING DESIGN COVER.
- PLACE TRANSITION LAYER (USING ONLY PRESCRIBED DRAINAGE MATERIAL: 2.0mm SAND) TO DESIGN LEVEL (REFER DRAWINGS).

SUPERINTENDENT INSPECTION AND SIGN OFF REQUIRED BEFORE PROCEEDING

- PLACE FILTER MEDIA (USING ONLY PRESCRIBED MATERIAL: 0.7mm SAND) TO DESIGN LEVEL (REFER DRAWINGS) SPREAD MATERIAL USING EXCAVATOR BUCKET OR HAND TOOLS TO OBTAIN LIGHT AND EVEN COMPACTION OF FILTER MEDIA. DO NOT DRIVE OVER FILTER MEDIA WITH ANY VEHICLE AS EXCESSIVE COMPACTION CAN IMPEDE DRAINAGE THROUGH THE FILTER MEDIA. FILTER MEDIA SURFACE MUST BE LEVEL (HORIZONTAL) AND FREE FROM LOCAL DEPRESSIONS AND SET AT 100mm BELOW PIT CREST (EXCEPT FOREBAY AREA WHICH IS 200mm). AS SOON AS FILTER MEDIA IS PLACED IT MUST BE IMMEDIATELY COVERED WITH A GEOFABRIC COVER WHICH MUST REMAIN IN PLACE AT ALL TIMES EXCEPT WHEN ACCESS TO FILTER MEDIA IS REQUIRED.THIS PROTECTIVE COVER IS ONLY TO BE REMOVED BY LANDSCAPERS IMMEDIATELY PRIOR TO PLANTING.
- LAY EXCESS GEOFABRIC FLAPS FROM BASIN OUTWARD ACROSS ADJACENT SUBSOIL AND PLACE LANDSCAPING TOPSOIL ON TOP OF THIS GEOFABRIC AND AROUND BASIN AS PER DESIGNS.
- INSTALL PROTECTIVE PLYWOOD BARRIERS ENSURING THE CREST IS AT DESIGN LEVEL (MIN 100mm ABOVE ELEVATION OF PIT CREST) AND EXTENDS LATERALLY TO BASIN BATTERS BY 300mm, AND VERTICALLY INTO THE FILTER MEDIA BY 200mm. THIS PLYWOOD BARRIER NEEDS TO REMAIN IN PLACE FOR 12 MONTHS AND PREVENT SEDIMENT LADEN RUNOFF FROM ENTERING THE MAJORITY FOR THE BASIN AREA. AFTER 12 MONTHS ONCE THE VEGETATION IS ESTABLISHED AND THE ALLOTMENT CONSTRUCTION IS COMPLETE THESE PLYWOOD BARRIERS WILL BE TAKEN OUT AND THE SYSTEM BROUGHT ONLINE.
- COVER INLET ZONE WITH PROTECTIVE GEOFABRIC ENSURING GEOFABRIC EXTENDS OVER CREST OF PROTECTIVE PLYWOOD BARRIER. COVER GEOFABRIC WITH MIN 50mm TOPSOIL SUITABLE FOR TURF GROWTH. SIMILAR TO THE PLYWOOD BARRIERS, THIS GEOFABRIC IS A TEMPORARY PROTECTIVE MEASURE TO PROTECT THE FILTER MEDIA IN THE INLET ZONE FROM BEING CLOGGED WITH CONSTRUCTION SEDIMENT, AND WILL BE
- FLUSH DRAINAGE PIPES TO REMOVE ANY INITIAL INGRESS OF MATERIAL AND TO ENSURE ADEQUATE DRAINAGE.

ISSUED FOR APPROVAL

Ryan ashworth


RYAN ASHWORTH


aa


Moreton Bau

NOTE THAT BETWEEN STEPS 5 - 16 ABOVE THE BASINS WILL BE SUSCEPTIBLE TO STORM DAMAGE. THEREFORE ONCE COMMENCED PODS MUST BE COMPLETED AS SOON AS POSSIBLE TO MINIMISE THE RISK OF STORM

INSPECTION IS REQUIRED IF RAINFALL EVENT OCCURS BETWEEN CONSTRUCTION STEPS 5 - 16 ABOVE.








LANDINGS

STAGES 1A & 1B

LL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO DINSTRUCTION, USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE,



LENNIUM

www.egis-group.com

22-000082_1A-1B

BIO-BASIN NOTES AND

DETAILS

1704

ATTACHMENT 4

Appeal Rights

Chapter 6 Dispute resolution

Part 1 Appeal rights

229 Appeals to tribunal or P&E Court

- Schedule 1 states—
 - (a) matters that may be appealed to—
 - (i) either a tribunal or the P&E Court; or
 - (ii) only a tribunal; or
 - (iii) only the P&E Court; and
 - (b) the person—
 - (i) who may appeal a matter (the appellant); and
 - (ii) who is a respondent in an appeal of the matter; and
 - (iii) who is a co-respondent in an appeal of the matter; and
 - (iv) who may elect to be a co-respondent in an appeal of the matter.
- (2) An appellant may start an appeal within the appeal period.
- (3) The appeal period is—
 - (a) for an appeal by a building advisory agency—10 business days after a decision notice for the decision is given to the agency; or
 - (b) for an appeal against a deemed refusal—at any time after the deemed refusal happens; or
 - (c) for an appeal against a decision of the Minister, under chapter 7, part 4, to register premises or to renew the registration of premises—20 business days after a notice is published under section 269(3)(a) or (4); or

- (d) for an appeal against an infrastructure charges notice—20 business days after the infrastructure charges notice is given to the person; or
- (e) for an appeal about a deemed approval of a development application for which a decision notice has not been given—30 business days after the applicant gives the deemed approval notice to the assessment manager; or
- (f) for an appeal relating to the Plumbing and Drainage Act 2018—
 - (i) for an appeal against an enforcement notice given because of a belief mentioned in the *Plumbing and Drainage Act 2018*, section 143(2)(a)(i), (b) or (c)—5 business days after the day the notice is given; or
 - (ii) for an appeal against a decision of a local government or an inspector to give an action notice under the *Plumbing and Drainage Act 2018*—5 business days after the notice is given; or
 - (iii) for an appeal against a failure to make a decision about an application or other matter under the Plumbing and Drainage Act 2018—at anytime after the period within which the application or matter was required to be decided ends; or
 - (iv) otherwise—20 business days after the day the notice is given; or
- (g) for any other appeal—20 business days after a notice of the decision for the matter, including an enforcement notice, is given to the person.

Note-

See the P&E Court Act for the court's power to extend the appeal period.

(4) Each respondent and co-respondent for an appeal may be heard in the appeal.

- (5) If an appeal is only about a referral agency's response, the assessment manager may apply to the tribunal or P&E Court to withdraw from the appeal.
- (6) To remove any doubt, it is declared that an appeal against an infrastructure charges notice must not be about—
 - (a) the adopted charge itself; or
 - (b) for a decision about an offset or refund—
 - the establishment cost of trunk infrastructure identified in a LGIP; or
 - (ii) the cost of infrastructure decided using the method included in the local government's charges resolution.

230 Notice of appeal

- An appellant starts an appeal by lodging, with the registrar of the tribunal or P&E Court, a notice of appeal that—
 - (a) is in the approved form; and
 - (b) succinctly states the grounds of the appeal.
- (2) The notice of appeal must be accompanied by the required fee.
- (3) The appellant or, for an appeal to a tribunal, the registrar, must, within the service period, give a copy of the notice of appeal to—
 - (a) the respondent for the appeal; and
 - (b) each co-respondent for the appeal; and
 - (c) for an appeal about a development application under schedule 1, section 1, table 1, item 1—each principal submitter for the application whose submission has not been withdrawn; and
 - (d) for an appeal about a change application under schedule 1, section 1, table 1, item 2—each principal submitter for the application whose submission has not been withdrawn; and

- (e) each person who may elect to be a co-respondent for the appeal other than an eligible submitter for a development application or change application the subject of the appeal; and
- (f) for an appeal to the P&E Court—the chief executive;
 and
- (g) for an appeal to a tribunal under another Act—any other person who the registrar considers appropriate.

(4) The service period is-

- if a submitter or advice agency started the appeal in the P&E Court—2 business days after the appeal is started; or
- (b) otherwise—10 business days after the appeal is started.
- (5) A notice of appeal given to a person who may elect to be a co-respondent must state the effect of subsection (6).
- (6) A person elects to be a co-respondent to an appeal by filing a notice of election in the approved form—
 - (a) if a copy of the notice of appeal is given to the person—within 10 business days after the copy is given to the person; or
 - (b) otherwise—within 15 business days after the notice of appeal is lodged with the registrar of the tribunal or the P&E Court.
- (7) Despite any other Act or rules of court to the contrary, a copy of a notice of appeal may be given to the chief executive by emailing the copy to the chief executive at the email address stated on the department's website for this purpose.

231 Non-appealable decisions and matters

(1) Subject to this chapter, section 316(2), schedule 1 and the P&E Court Act, unless the Supreme Court decides a decision or other matter under this Act is affected by jurisdictional error, the decision or matter is non-appealable.

- (2) The Judicial Review Act 1991, part 5 applies to the decision or matter to the extent it is affected by jurisdictional error.
- (3) A person who, but for subsection (1) could have made an application under the *Judicial Review Act 1991* in relation to the decision or matter, may apply under part 4 of that Act for a statement of reasons in relation to the decision or matter.
- (4) In this section—

decision includes—

- (a) conduct engaged in for the purpose of making a decision; and
- (b) other conduct that relates to the making of a decision; and
- (c) the making of a decision or the failure to make a decision; and
- (d) a purported decision; and
- (e) a deemed refusal.

non-appealable, for a decision or matter, means the decision or matter—

- (a) is final and conclusive; and
- (b) may not be challenged, appealed against, reviewed, quashed, set aside or called into question in any other way under the *Judicial Review Act 1991* or otherwise, whether by the Supreme Court, another court, any tribunal or another entity; and
- (c) is not subject to any declaratory, injunctive or other order of the Supreme Court, another court, any tribunal or another entity on any ground.

232 Rules of the P&E Court

- A person who is appealing to the P&E Court must comply with the rules of the court that apply to the appeal.
- (2) However, the P&E Court may hear and decide an appeal even if the person has not complied with rules of the P&E Court.

ATTACHMENT 5

Infrastructure Charges Notice

In accordance with the Infrastructure Charges Resolution (No. 10) dated 5 October 2022 or as amended, there is no Infrastructure Charges applicable to the development.