

Enquiries: Xavier Dubreuil
Direct 07 5433 2739
Our Ref: DA/2023/3497
Your Ref: 22-000082_23
Date: 24 October 2023

Foreverlen Pty Ltd PO Box 5233 BRISBANE QLD 4001

Dear Applicant,

Re: DEVELOPMENT APPROVAL

Planning Act 2016

Development Application No.: DA/2023/3497

Property Location: 409-423 Caboolture River Road LILYWOOD

403 Caboolture River Road UPPER CABOOLTURE

Property Description: Lot 12 RP 866105

Lot 1000 SP 337426

Development Type: Operational Works - Development Permit for

Roadworks and Stormwater and Earthworks

(Lilywood Landings, Stage 23)

Please be advised that on 24 October 2023 the above development application was approved by Council's Delegate as the Assessment Manager in accordance with section 63 of the *Planning Act 2016* subject to conditions.

The following type of approval has been issued:

Development Permit - Operational Works for Roadworks, Stormwater & Earthworks

The development allowed by this approval must be carried out in accordance with the attached Decision package.

Attached is an extract from the *Planning Act 2016* which details your appeal rights and the appeal rights of any submitters, if applicable, regarding this decision.

Should you require any further information about this matter, please contact Xavier Dubreuil as referenced above.

Yours faithfully

Xavier Dubreuil
Senior Engineer

Development Services

Enclosures: Attachment 1 - Decision Notice

Attachment 2 - Assessment Manager Conditions
Attachment 3 - Approved Plans / Documents
Attachment 4 - Appeal Rights
Attachment 5 - Infrastructure Charges

Сс Unitywater

Development.Services@Unitywater.com

ATTACHMENT 1

Decision Notice

Decision Notice

Planning Act 2016, section 63

APPLICATION DETAILS

Application No: DA/2023/3497

Applicant: Foreverlen Pty Ltd

Street Address: 409-423 Caboolture River Road LILYWOOD

403 Caboolture River Road UPPER CABOOLTURE

Real Property Description: Lot 12 RP 866105 Lot 1000 SP 337426

Planning Scheme: Moreton Bay Regional Council Planning Scheme

APPROVAL DETAILS

Date of Decision: 24 October 2023

The development application was approved by Council's Delegate as the Assessment Manager subject to conditions (refer Attachment 2).

Application Type	Development Permit	Preliminary Approval
Operational Works for Roadworks, Stormwater and Earthworks	\square	

OTHER NECESSARY PERMITS

Not applicable.

In addition to this approval, you may also be required to obtain a water approval from the Northern SEQ Distributor Retailer, trading as Unitywater. To engage a Registered Certifier to lodge your connection application, go to Unitywater's website www.unitywater.com/certifier

CURRENCY PERIOD OF APPROVAL

The currency period stated in section 85 of the *Planning Act 2016* applies to this approval as outlined below:

Operational Works - 2 years from the date of this approval starts to have effect.

DEEMED APPROVAL

Not applicable.

VARIATION APPROVAL

Not applicable.

INFRASTRUCTURE

Unless otherwise specified, all assessment manager conditions of this development approval relating to the provision of infrastructure are non-trunk infrastructure conditions under Chapter 4, section 145 of the *Planning Act 2016*.

ASSESSMENT MANAGER CONDITIONS

The Conditions relevant to this development approval are listed in Attachment 2 of the Decision package.

APPROVED PLANS / DOCUMENTS

The approved plans and/or documents as listed below for this development approval are included in Attachment 3 of the Decision package.

The approved plans/documents for this development approval are listed below.

Approved Plans and Docum	Approved Plans and Documents				
Plan / Document Name	Reference Number	Prepared By	Dated		
Title Sheet & Locality Plan	22-000082_23 Dwg. 1000 Rev. B	Egis Consulting Pty Ltd	12/10/2023		
Site Layout Plan	22-000082_23 Dwg. 1100 Rev. B	Egis Consulting Pty Ltd	12/10/2023		
Retaining Wall Setout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 1 of 3	1200 Rev. B	Ltd			
Retaining Wall Setout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 2 of 3	1201 Rev. B	Ltd			
Retaining Wall Setout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 3 of 3	1202 Rev. B	Ltd			
Retaining Wall Notes &	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Details	1203 Rev. B	Ltd			
Retaining Wall Longitudinal Section	22-000082_23 Dwg. 1204 Rev. B	Egis Consulting Pty Ltd	12/10/2023		
Retaining Wal Setout	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sections	1205 Rev. B	Ltd			
Control Line Setout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 1 of 2	1300 Rev. B	Ltd			
Control Line Setout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 2 of 2	1301 Rev. B	Ltd			
Control Line Setout Tables and Details	22-000082_23 Dwg. 1302 Rev. B	Egis Consulting Pty Ltd	12/10/2023		
Roadworks Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 1 of 3	1310 Rev. B	Ltd			
Roadworks Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 2 of 3	1311 Rev. B	Ltd			
Roadworks Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 3 of 3	1312 Rev. B	Ltd			
Intersection Details	22-000082_23 Dwg. 1320 Rev. B	Egis Consulting Pty Ltd	12/10/2023		
Signs and Linemarking Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023		
Sheet 1 of 3	1330 Rev. B	Ltd			

Approved Plans and Docume	ents		
Plan / Document Name	Reference Number	Prepared By	Dated
Signs and Linemarking Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 2 of 3	1331 Rev. B	Ltd	12/10/2023
Signs and Linemarking Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 3 of 3	1332 Rev. B	Ltd	12/10/2023
Road 3 Longitudinal Section	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Toad 3 Longitudinal Section	1340 Rev. B	Ltd	12/10/2023
Road 3 Cross Sections	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
	1341 Rev. B	Ltd	12/10/2020
Road 4 Longitudinal and	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Cross Sections	1342 Rev. B	Ltd	12/10/2023
Road 16 Longitudinal and	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Cross Sections	1343 Rev. B	Ltd	12/10/2020
Road 17 Longitudinal and	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Cross Sections	1344 Rev. B	Ltd	12/10/2020
Road 18 Longitudinal and	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Cross Sections	1345 Rev. B	Ltd	12/10/2020
Stormwater Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 1 of 4	1400 Rev. B	Ltd	12/10/2020
Stormwater Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 2 of 4	1401 Rev. B	Ltd	12/10/2020
Stormwater Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 3 of 4	1402 Rev. B	Ltd	12/10/2020
Stormwater Layout Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 4 of 4	1403 Rev. B	Ltd	12/10/2020
Stormwater Drainage Notes	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
and Details	1404 Rev. B	Ltd	12/10/2020
Stormwater Catchment Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 1 of 2	1410 Rev. B	Ltd	12/10/2020
Stormwater Catchment Plan	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 2 of 2	1411 Rev. B	Ltd	12/10/2020
Stormwater Longitudinal	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sections Sheet 1 of 2	1420 Rev. B	Ltd	12/10/2020
Stormwater Longitudinal	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sections Sheet 2 of 2	1421 Rev. B	Ltd	12/10/2020
Stormwater Calculation Table	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 1 of 2	1430 Rev. B	Ltd	12/10/2020
Stormwater Calculation Table	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Sheet 2 of 2	1431 Rev. B	Ltd	12/10/2020
Stormwater Structures	22-000082_23 Dwg.	Egis Consulting Pty	12/10/2023
Details	1440 Rev. B	Ltd	12/10/2020
Bio-Basin G3 Layout Plan	22-000082_23 Dwg. 1700 Rev. B	Egis Consulting Pty Ltd	12/10/2023
Die Beein C2 Casties Dies	22-000082 23 Dwg.	Egis Consulting Pty	40/40/0000
Bio-Basin G3 Section Plan	1701 Rev. B	Ltd	12/10/2023
Die Beein Notes and Datails	22-000082 23 Dwg.	Egis Consulting Pty	10/10/2022
Bio-Basin Notes and Details	1702 Rev. B	Ltd	12/10/2023

Note: Approved plans as indicated in **BOLD** above are annotated in **red** on the stamped plans by Council dated 24/10/2023.

ASSESSMENT BENCHMARKS

The Assessment Benchmarks that applied to the development from the following Categorising Instruments include;

Categorising Instrument (Planning Regulation 2017)

State Planning Policy

State Planning Policy 2017, Part E.

Regional Plan

South East Queensland Regional Plan 2017 (ShapingSEQ).

Local Categorising Instrument (Moreton Bay Regional Planning Scheme)

• MBRC Planning Scheme - Works Code

Local Categorising Instrument (Variation Approval)

Not applicable.

Local Categorising Instrument (Temporary Local Planning Instrument)

Not applicable.

OTHER RELEVANT ASSESSMENT MATTERS

Not applicable.

REASONS FOR THE DECISION

Not Applicable.

REASONS FOR APPROVAL DESPITE NON-COMPLIANCE WITH ASSESSMENT BENCHMARKS

Not applicable.

REFERRAL AGENCY CONDITIONS

There were no Referral Agencies applicable to this development application.

SUBMISSIONS

Not applicable.

APPEAL RIGHTS

Attachment 4 of the Decision package is an extract from the *Planning Act 2016* which details your appeal rights, and the appeal rights of any submitters, if applicable, regarding this decision.

ATTACHMENT 2 Assessment Manager Conditions of Approval

COND	ITION	TIMING
OPER	ATIONAL WORKS	
DEVEL	OPMENT ENGINEERING	
1	Road Classifications for Pavement Design	
	Design pavement in accordance with the following road classifications:	Prior to subgrade inspections.
	Road 03 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA	
	Road 04 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA	
	Road 16 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA	
	Road 17 - Modified Living Residential (16.5m) - 1.2 x 10 ⁵ ESA	
	Road 18 - Driveway (3.0m) 2.5 x 10 ³ ESA	
2	Non-Conforming Designs	
	Only non-conforming designs listed in this approval have been accepted. All other discrepancies with Council standards shall be redesigned and / or reconstructed as necessary to conform with Council standards at no cost to Council.	At all times during construction and prior to works being accepted Off Maintenance.
3	Errors and Omissions	
	Where errors or omissions occur in the design or works do not conform to or meet Council standards then these works shall be rectified to comply with Council standards at no cost to Council.	At all times during construction and prior to works being accepted Off Maintenance.
	Where drawings contain insufficient detail or do not contain details of works that are either necessary or associated with the development then these works shall be designed and constructed to Council standards.	
	Only the approved plans shall be used for construction.	
	Note: Council reserves the right to amend the approved drawings or request further information should this become necessary.	
4	Works – Applicant's Expense	
	All works, services, facilities and/or public utility alterations required by or as a consequence of this approval or stated condition/s, whether carried out by the Council or otherwise, shall be at the developer's expense unless otherwise specified or agreed in writing.	At all times during construction and prior to works being accepted Off Maintenance.
	Replace existing Council infrastructure (including but not limited to street trees and footpaths) to Council's standards.	

CC	CONDITION		TIMING
5		Works – Connection to existing works	
		Where existing works, including roads and drainage works, will not link up with and join smoothly to proposed works and are not more than twenty (20) metres from the nearest point of the proposed works the developer shall carry out such works as are necessary to ensure that the incomplete works, including roads and drainage, are constructed to link up with and join smoothly to the works proposed in accordance with Council's standards.	Prior to works being accepted On Maintenance.
		These works are to be undertaken at the developer's expense unless otherwise specified or agreed in writing.	
6		Notification of Finalisation of Works	
		Notify Council in writing that the development works on site have been finalised.	At the time of completion of construction.
7		As Constructed Drawings	
	A	Provide, for review and approval, Council with a preliminary set of the surveyor and engineering As Constructed drawings for the approved works and a digital ADAC file.	Prior to requesting an On Maintenance inspection.
		Note: The current design standard and relevant planning scheme policy is MBRC Planning Scheme Policy Operational Works inspection, maintenance and bonding procedures.	
	В	Submit 'As Constructed' drawings and digital ADAC file in accordance with Council's Planning Scheme, relevant Planning Scheme Policies and design standards current at the time of development.	Prior to works being accepted On Maintenance.
8		Works Through Land not owned by the Developer	
		Where any works are proposed to be undertaken on or extend into any property not owned by the developer then the other property owner's written consent must be lodged with Council. The written consent from the land owner must identify the correct drawing title and number (including revision number) for the works within or through their land.	Prior to any works commencing within those properties.
9		Works in Existing Roads	
	A	Works carried out in or affecting existing Roads must be undertaken so that these roads are maintained in a safe and useable condition.	At all times.
	В	Provide to Council's delegated officer and receive acknowledgement of a Traffic Management Plan, with site specific Guidance Scheme, prepared and signed by an appropriately qualified person and in accordance with the Manual of Uniform Traffic Control Devices (MUTCD) for any works that will affect traffic movements or traffic safety in existing roads.	At least five (5) days prior to undertaking the works in or affecting existing roads.

COND	ITION	TIMING
	 A 'Part Road Closure Application' for Development Works form is to accompany the Traffic Management Plan submission. This submission is required to be made in addition to any Traffic Management Plan which has been submitted and/or approved as part of a Construction Management Plan for the site during the development application process for Material Change of Use or Reconfiguring a Lot or subsequent non-IDAS applications. 	
10	Information Sign – Works in Existing Roads	
	A construction advisory road sign must be erected and regularly updated and maintained displaying the developer and contractors details and the expected completion date for works on existing roads. The sign shall be located so as be clearly legible to the public from of minimum 15m distance from the existing road on which the works are to be carried out on.	For the duration of the works from commencement to acceptance of On Maintenance.
11	Notification to Affected Premises	
	Provide Council with a copy of an information kit for 'Notification to Affected Premises' which includes the following: • A layout plan of the proposed development showing adjoining lot boundaries, new and existing roads, park and open space, drainage reserves and community purposes lots as applicable; • Details of any external works with any changes to existing works highlighted for easy identification; • Scheduled start and completion dates; • Contact names and phone numbers for the Developer, Supervising Engineer, Consulting Engineer, the Contractor, Wildlife Spotter and who to contact in an emergency; and • The site working hours authorised for the site works.	Prior to distribution of information kit to residents.
В	Provide all occupiers of premises adjoining the site, directly opposite the frontage of the site, adjacent to and directly opposite external works and residents/occupiers likely to be directly affected by the works with a copy of the 'Notification to Affected Premises' information kit. Provide Council's delegated officer with a list of premises which the information kit has been delivered to.	Not less than 14 days prior to commencing any construction works.
12	Information Sign – Development Works	
	An information sign containing the following details and after hours contact details must be provided at each entrance to the development site: • Developer	For the duration of the development works from commencement to acceptance On

CONDITION		TIMING
	Supervising Consultant/ Engineers / Project Manager Principal Contractor The sign must be at least 0.9m (W) by 0.6m (H). The sign must be erected and maintained for the duration of the development works.	Maintenance by Council.
13	Prestart Meeting	
	Arrange a prestart meeting with Council officers from Development Services section on 3205 0555 or (Email - council@moretonbay.qld.gov.au - Attention - Development Services - Engineering Waraba Construction Team - Referencing DA/2023/3497.	Not less than 7 days prior to commencing any construction works.
	The following people will be required to attend the prestart meeting: • Developer's Supervising Engineer • Contractor's Engineer / Project Manager • Contractor's Site Supervisor • Fauna Manager (where required).	
14	Mandatory Inspections with Council Officers	
	Submit required documentation for each mandatory inspection in accordance with MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to requesting inspection.
	Undertake the following inspections with Council's delegated officer (where applicable to approved works) in accordance with MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures:	As prescribed below.
А	Stormwater drainage.	Prior to backfilling stormwater trenches.
В	Subgrade / box inspection.	Prior to placement of structural pavements.
С	Preseal inspection.	Prior to priming and sealing of structural pavements.
D	For concrete slabs and concrete pavements - foundations / subgrade and pre-pour inspections.	Prior to concrete pouring.
E	On maintenance inspection for Council's acceptance of all works.	Prior to works being accepted On Maintenance.
F	Off maintenance inspection of all works. Note: Reinspections attract a fee in accordance with Council's Fee Schedule. The fee must be paid prior to the reinspection.	After maintenance period has elapsed.

COND	ITION	TIMING
G	Provide Council's delegated officer with a copy of an Engineers' Certificate Soil tester's reports demonstrating that required compaction standards, finished levels and textures of finish have been obtained in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to proceeding to construction of next layer or surfacing.
15	Testing Frequency – General	
A	All testing of the works shall be carried to comply with the minimum testing frequencies given in MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	At all times during construction.
	Note: Council's delegated officer may vary the frequency of testing to suit site conditions but must provide written advice to the supervising engineer prior to commencement of the relevant works.	
В	Provide a plan identifying locations where testing has occurred.	Prior to works being accepted On Maintenance.
16	Construction Hours Restrictions	
	Ensure hours of construction are limited to 0630 to 1830 Monday to Saturday and not at all on Sundays and public holidays.	At all times.
	Note: Council's engineer may approve (in writing) work outside the above hours where it can be demonstrated to the satisfaction of Council that the work will not cause unreasonable interference with the amenity of adjoining premise and any person.	
17	Construction Nuisance and Annoyance	
	Ensure construction works do not cause unreasonable interference with the amenity of adjoining premise and any person by reason of noise, vibration, electrical interference, smell, fumes, vapour, steam, soot, ash, dust, silt, wastewater, waste products, grit, oil or otherwise.	At all times.
18	Construction Site Management	
	Ensure the construction site is kept in a clean and tidy state.	At all times.
19	Temporary Sedimentation, Erosion and Runoff Control	
A	Implement an Erosion and Sediment Control Plan which is prepared by an experienced Certified Professional in Erosion and Sediment Control (CPESC) in accordance with International Erosion Control Association Australasia (IECA) Best Practice and Sediment Control document and MBRC Planning Scheme current at the time of development.	Prior to commencement of works and to be maintained current at all times during construction and until the development is accepted offmaintenance.

COND	TION	TIMING
В	The temporary erosion and sediment control measures shall be maintained and be functional until the end of the Maintenance Period for the works or earlier if Council's delegated officer considers they are no longer required.	At all times during construction.
	Note: Council's delegated officer may order additional measures to control silt on site at no cost to Council.	
20	Haul Routes	
	Submit and have approved by Council's delegated officer all haul routes for the transport of imported or spoil material and gravel pavement material along Council roads below subarterial standard.	Prior to a prestart meeting being held.
	Note: Refer to MBRC Planning Scheme Values and Constraints Mapping - Road Hierarchy for details on subarterial and arterial roads.	
21	Spillage onto Existing Roads	
	Clean those parts of the access route to the site that are affected by any material dropped, deposited or spilled on the roads as a result of construction processes associated with the site.	At all times during construction.
	Note:	
	 All materials must be swept up and removed from the roads and not directed into Council's stormwater drainage system. All care must be taken to prevent sediments being deposited on roads. 	
22	Dust Control – Nuisance and Annoyance	
	Implement suitable dust control measures. If airborne particles are observed leaving the site, any work is to cease immediately and satisfactory dust suppression is to be implemented.	At all times prior to works being accepted Off Maintenance.
	Note: Dust suppression measures must be in place at all times including weekends and public holidays.	
23	Earthworks Batters	
	 Where approved drawings do not include specifications for scour and erosion protection apply the following treatments to batter slopes: Slopes of 1:6 or flatter – topsoil and seed Slopes between 1:6 and 1:4 – topsoil and turf Slopes of 1:4 or greater – provide treatment recommendation from a qualified geotechnical engineer (R.P.E.Q.) for Council approval prior to undertaking batter works Or as directed by Council. 	At all times during construction.
	Note: Batters within Open and Civic Spaces are to be treated	

CONDITION		TIMING
	in accordance with MBRC Planning Scheme Policy Integrated Design - Open and Civil Space Design.	
24	Road Crossings in Existing Roads	
	All services crossings under Existing Council Roads are to be tunnel bored unless approved otherwise by Council's delegated officer.	At all times during construction.
	 Where approval is given for open trenching, the following is to apply: Minor Roads - backfill shall be compacted in layers to 95% standard maximum dry density and topped with 300mm of pavement material and a 50mm AC wearing course. Sub-arterial or Arterial roads - refer to I.P.W.E.A. Standard Drawing RS-170. Verge - Backfill shall be compacted to 90% standard maximum dry density and topped with 75mm of sandy loam. Restoration of any vegetation shall be undertaken to a standard as near as practicable to the pre-construction standard. 	
25	Site works – Stormwater Runoff Quality	
	Carry out earthworks in accordance with the State Planning Policy - Water Quality and IECA Best Practice Erosion and Sediment Control document. Note:	At all time during construction and until the site is suitably stabilised.
	 Soil disturbances of greater than 1.0 hectares will require a site specific Erosion & Sediment Control Plan. Earthworks are to be undertaken to ensure that soil disturbances are staged into manageable areas of not greater than 3.5 hectares. 	
26	Earth Retaining Structures	
A	Earth retaining structures within the subject land around areas of cut that are on or near the boundaries of the site must be designed to allow for the existing live and dead loads associated with the adjoining land/premises current occupancy and use of the adjoining land including allowance for a 2m high boundary fence.	At all times.
	The minimum design life (the period assumed in design for which a structure or structural element is required to perform its intended purpose without replacement or major structural repairs) for the earth retaining structure that is specified in Table 2.1 of Australian Standard AS4678.	
В	Submit for Council records copies of Forms 15 & 16 as detailed under section 254 of the Building Act 2006. The forms are to be signed by an RPEQ for all structural retaining walls.	Prior to works being accepted On Maintenance.

COND	TION	TIMING
	Additionally, submit certification from an R.P.E.Q. that the design and construction of retaining walls comply with the requirements of this condition.	
27	Unsuitable Fill Materials	
	Ensure that all fill material used on the development site is free of unsuitable materials, identified in AS3798 and the following: • actual acid sulfate soils and potential acid sulfate soils; • organic or putrescible matter; • material imported from land which is, or has been, listed on the "Environmental Management Register" under the Environmental Protection Act 1994; and • building demolition material.	At all times.
28	Compaction Requirements	
	All fill material which is intended to be load bearing, or the finished surface level of which is required to remain approximately constant, is selected, placed and compacted to the standard prescribed in Australian Standard AS3798 Guidelines on Earthworks for Commercial and Residential developments.	At all times during construction.
29	Pavement Design	
Α	All road pavements must be designed, constructed and tested in accordance with MBRC Planning Scheme Policy - Integrated Design - Street, Roads and Utilities and standard drawings current at the time of construction. Note: Council requires a primer seal placed under all asphalt surfaces. Increased asphalt surface thicknesses for road thresholds are to be identified in the pavement design.	At all times during construction.
В	Submit, for review and approval by Council's delegated officer, a pavement design for all roads. Pavement designs are to include Soil tester's reports.	Prior to subgrade inspection.
30	Pavement Jointing Detail	
	Undertake pavement jointing in accordance with I.P.W.E.A.Q. Standard Drawings RS-170.	Prior to works being accepted On Maintenance.
31	Concrete Footpaths	
	Construct concrete footpaths and kerb ramps in accordance with I.P.W.E.A. Standard Drawings RS-065 and RS-090.	Prior to works being accepted On Maintenance.
32	Street Signs	
	Street signs must be provided in accordance with Council's Standard Drawings and I.P.W.E.A. Standard Drawings.	Prior to works being accepted On Maintenance.

CONDI	TION	TIMING
	Note: House numbers required for these signs shall be obtained from Council's house numbering officer by contacting Council's Customer Service. The MBRC Logo is not to be put on the sign.	
33	Hazard Management	
A	Undertake the hazard identification and treatment process for any additional, existing or introduced hazards identified onsite by the Consultant or by Council's delegated officer during the construction process.	
	Undertake a review of the identified hazards and provide a copy of the completed Hazard Mitigation Worksheet found in AUSTROADS Guide to Road Design Part 6: Roadside Design, Safety and Barriers Appendix B along with any supporting information.	
В	Provide, for review and approval by Council's delegated officer, adequate design documentation for the recommended hazard management treatment in accordance with AS3845:1999 and AUSTROADS Guide to Road Design Part 6: Roadside Design, Safety and Barriers.	Prior to construction of any hazard management treatment.
С	Construct approved hazard management treatments in accordance with Council's Planning Scheme, Planning Scheme Policies, standard drawings and any other relevant standards current at the time of development.	Prior to works being accepted On Maintenance.
34	Stormwater Runoff Control – Batters and Retaining Walls	
	Provide cut-off drains at the top of the batter with turf or rock lined batter drains for all batters and/or retaining walls generally higher than 600mm in height and with a catchment greater than 1000m2.	Prior to works being accepted On Maintenance.
	Note: Where these are not detailed on the approved drawings then these works shall be in accordance with Council's current standards.	
35	Stormwater Runoff Control – Open Drains	
	Provide lining with appropriate scour protection to all open drains and bunds in accordance with Council's Planning Scheme, Planning Scheme Policies and standard drawings current at the time of development.	Prior to works being accepted On Maintenance.
	Note: Dumped rock is generally not considered as an appropriate solution.	
36	Stormwater Pipe Outlets and Culvert Inlets and Outlets	
	Stabilise all culvert inlets and outlets or stormwater drainage outlets in accordance with industry best practice and the following requirements: • Rock gabion baskets/rock mattresses	At all times.

COND	TION	TIMING
	Grouted rock/stone pitching with a properly designed and prepared base and constructed to the following requirements:	
37	Stormwater Overland Flow – Site Earthworks	
	Earthworks must be undertaken on the site so as not to cause nuisance and annoyance to any person or premises. The development must: • Allow stormwater overland flow which entered the land prior to the commencement of the earthworks to continue to enter the land; and • Ensure stormwater overland flow from the development site is not discharged or diverted onto land (other than a road) adjacent to the site in a manner which: • concentrates the rate of flow at any point along the property boundary; or • increases the peak flow rates of stormwater discharged at any point along the property boundary; beyond that which existed prior to commencement of these earthworks.	At all times during construction.
38	CCTV - Stormwater Pipes	
A	Undertake and provide, to the satisfaction of the Council, a high definition Closed Circuit Television (CCTV) recording of all stormwater pipes, including inter allotment roof water drainage. Recording to be undertaken within one month immediately preceding making a request for On Maintenance inspection and post road pavement construction works. CCTV to clearly display all joints (full surrounds) and any form of damage or defects, including date and time of the recording.	Prior to a request for On Maintenance Inspection
	The recording is to include a report signed by a suitably qualified Registered Professional Engineer Queensland (RPEQ) stating that the recording has been reviewed and all works are satisfactory.	
	Where defects have been identified, consultant is to provide method of rectification to Council for approval, prior to carrying out any rectification works.	

COND	ITION	TIMING
В	Undertake and provide, to the satisfaction of the Council, a high definition Closed Circuit Television (CCTV) recording of all stormwater pipes, including inter allotment roof water drainage. Recording to be undertaken within one month immediately preceding making a request for Off Maintenance inspection. CCTV to clearly display all joints (full surrounds) and any form of damage or defects, including date and time of the recording. The recording is to include a report signed by a suitably qualified Registered Professional Engineer Queensland (RPEQ) stating that the recording has been reviewed and all works are satisfactory. Where defects have been identified, consultant is to provide	Prior to a request for Off Maintenance inspection.
	method of rectification to Council for approval, prior to carrying out any rectification works.	
39	Drainage Behind Retaining Walls	
	Design and install agricultural pipes or strip drains behind retaining walls in accordance with Q.U.D.M. to connect to: • The proposed inter-allotment drainage systems; or • To drainage inlet structures via a stub connection in roadways; or • Directly to kerb and channel if there are no drainage structures within 10m of the frontage of the land; or • As approved in writing by Council's delegated officer.	Prior to works being accepted On Maintenance.
	 Notes: Corrugated pipes are not to be used to connect the stormwater drainage to Council's infrastructure. The drainage system behind retaining walls must not connect to Council's subsurface drainage system in the Council road. 	
40	Provision of Kerb Adapters	
	Provide a minimum of two (2) metal kerb adaptors per lot for lots that drain to the road. Where a lot has side crossfall of up to 1.5%, one (1) kerb adaptor shall be located at each side of the lot. Where a lot has side crossfall of greater than 1.5%, both kerb adaptors shall be located at the low side of the lot. For lots with a concrete footpath at the frontage, the kerb adaptors shall be connected to the front boundary of the lot	Prior to works being accepted On Maintenance.
	with Class SN8 uPVC stormwater pipe.	
41	Certification – Public Stormwater Management Infrastructure	
	Provide documentation to Council from a Registered Professional Engineer (RPEQ) specialising in stormwater design certifying that the stormwater management treatment train as approved in the stormwater management plan and design drawings has been constructed in accordance with engineering best practise and is functioning as designed.	Prior to works being accepted On Maintenance.

COND	ITION	TIMING
	The certification shall include the completed sign-off forms for bioretention systems prepared by Water by Design in Partnership with Healthy Waterways shall be completed. The sign-off forms are accessible from www.waterbydesign.com.au .	
42	Public Bioretention Inspections	
	Provide Council with notice of the subsoil drains being laid and the filter media being installed. Note: Council's delegated officer may attend the inspection.	Not less than 48 hours prior to subsoil drains being laid and the filter media being installed.
43	Maintenance Process for Public Bioretention Basin	
A	The entire bioretention basin shall act as a sediment basin. Note: Council will consider alternative solutions to achieve the desired outcome.	During the build-out phase (80%) or up to a maximum of two (2) years.
В	Submit, for review and approval by Council's delegated officer, a deferred works schedule to cover the cost of basin conversion plus twenty-five percent (25%) and in accordance with the requirements of Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to the bioretention basin area being accepted On Maintenance as a sediment basin.
	 The following works are to be included as a minimum in the deferred works bond schedule: removal of sacrificial turf and geofabric; and In-situ hydraulic conductivity testing of filter material in accordance with the "Guidelines for Soil Filter Media in Bioretention Systems: (produced by the Faculty for Advanced Water Biofiltration) requirements. Planting out of the basin in accordance with the approved landscaping drawings. 	
С	Construct deferred works and any other works necessary to convert to the basin from sediment basin to a functioning bioretention basin in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures. In-situ hydraulic conductivity testing of filter material is to be	Once the contributing catchment achieves eighty percent (80%) build-out or a maximum of 2 years.
	provided to Council's delegated officer to demonstrate that area can be planted out. Where in-situ hydraulic conductivity testing shows that the filter material is not acceptable then replacement of the filter material is required in addition to planting out of basin area. Note: Deferred Works for bioretention basin conversion are subject to a separate on maintenance process to the other civil works for the development. The On Maintenance	
	process is to be in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance	

CONI	DITION	TIMING
	and bonding procedures including on and off maintenance inspections and maintenance period.	
44	Fertilisers for Grassing and Landscape Works	
	Odorous chemicals, fertilisers, soil conditioners or mulches shall not be used on land development projects. Only a non-odorous, commercially bagged and labelled fertiliser shall be used when seeding grass areas or laying turf. Without limiting the above, Council's delegated officer may approve the use of suitably composed and aged organic material, such as soil conditioners, at the following locations: • in isolated locations where existing and proposed houses are considerable distances from the work site; and • where, in the officer's opinion, their use would not adversely affect the occupiers of any nearby properties with strong odours or loose material blown from the work site.	At all times during construction.
	Council's delegated officer will provide the approval in writing with conditions where odorous fertilisers are approved.	
45	Stabilisation of Disturbed Areas	
	Ensure that a grass strike rate of at least 80% cover has been attained on all disturbed areas or other approved means of stabilisation of grassed areas have been provided. Note: For residential and rural residential subdivisions, the road reserve between kerb and property line shall be turfed as a condition of completion.	Prior to works being accepted On Maintenance.

ADVICES Development Permit This approval shall comply with all the conditions of related approval as stipulated in Council's Decision Notice – Development Permit dated 24 August 2023 referenced as DA/2023/4535. The Applicant needs to be aware that the Currency Period of that Decision Notice may determine the validity period of this Decision Notice. 2 **Extent of Checking by Council** This approval shall not be taken to mean that the drawings have been checked in detail and Council accepts no responsibility whatsoever for the survey information, the design, or for the accuracy of any information or detail contained in the approved drawings and specifications. Aboriginal Cultural Heritage Act 3 The Aboriginal Cultural Heritage Act 2003 commenced in Queensland on April 16, 2004. Under the Act, indigenous parties are key in assessing cultural heritage significance. The Aboriginal Cultural Heritage Act 2003 establishes a Duty of Care for indigenous cultural heritage. This applies on all land and water, including freehold land. The Cultural Heritage Duty of Care lies with the person or entity conducting the activity. Penalty provisions apply for failing to fulfil the Cultural Heritage Duty of Care. Those proposing an activity that involves additional surface disturbance beyond that which has already occurred on the proposed site need to be mindful of the Duty of Care requirement. Details of how to fulfil the Duty of Care are outlined in the Duty of Care Guidelines gazetted with the Act. Council strongly advises that you contact the relevant state agency to obtain a copy of the Duty of Care Guidelines and further information on the responsibilities of developer under the terms of the Aboriginal Cultural Heritage Act 2003. **Environmental Protection Act** 4 It remains the duty of care of the site owner not to cause Environmental Harm as defined under the Environmental Protection Act 1994. 5 Road and Stormwater infrastructure In respect to Road and Stormwater infrastructure, the works shall be designed and constructed in accordance with the relevant Planning scheme codes and policies; The current relevant planning scheme codes and policies are: Works code; Reconfiguring a lot codes; PSP- Integrated Design PSP- Operational Works Inspection, Maintenance and Bonding Procedures. All of which may be downloaded free of charge from Council's website at www.moretonbay.qld.gov.au.

ADVICES

The PSP- Operational Works Inspection, Maintenance and Bonding Procedures also contains details of other requirements such as:

- 1. arrangements for works going On or Off Maintenance;
- 2. inspection and testing;
- 3. checklists and certification proforma;
- 4. bonding procedures.

Should further information be required regarding the road and stormwater component of the Operational Works Application, please contact Council's Officer, Xavier Dubreuil on phone (07) 5433 2739.

6 Acceptance Based on Applicant's Certification

Council's acceptance of the above submission is based solely on the applicant's certification that the proposal conforms totally to Council's Planning Scheme, Planning Scheme Policies and standard drawings.

7 Biosecurity Act 2014 - Fire Ant Control

Significant portions of the Moreton Bay are within Fire Ant Biosecurity Zone 2 and must remain vigilant for the presence of fire ants. Under the Biosecurity Act 2014, individuals and businesses are responsible for ensuring that they follow the movement controls for specific organic materials to help prevent the spread of fire ants within South East Queensland's fire ant biosecurity zones. Movement of a fire ant carrier from within the fire ant biosecurity zone may need a biosecurity instrument permit.

More information is available on https://www.fireants.org.au/treat/business-and-industry/movement-controls

ATTACHMENT 3

Approved Plans / Documents


LILYWOOD LANDINGS







STAGE 23 - OPERATIONAL WORKS FOR FOREVERLEN PTY LTD



LOCALITY PLAN

MORETON BAY REGIONAL COUNCIL

AREA OF SITE: 4.454 ha

LOT INFORMATION

LOT 35 ON SP 115959

CONSTRUCTION NOTE THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH:

1345

1400

1401

CRR INTERSECTION & IDC SET - 22-000082_CRR

STORMWATER LAYOUT PLANS

- BULK EARTHWORKS SET 22-000082_EWKS
- STAGE 1A & 1B SET 22-000082_1A-1B
- STAGE 2 SET 22-00082_2
- STAGE 3 SET 22-00082_3
- STAGE 4 SET 22-00082_4
- GEOTECHNICAL REPORT
- BAF TRUNK WATER INFRASTRUCTURE SET 22-000082 TW
- DOBSON LANE TRUNK GRAVITY SEWER SET 20-000027
- SIGNALS PLANS (BY CV SERVICES)
- LANDSCAPE PLANS (BY AECOM) ELECTRICAL/ COMMS PLAN (BY CV SERVICES)

CONSTRUCTION HOLD POINT PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL VERIFY LEVELS OF ALL EXISTING CROSSINGS AND CONNECTION POINTS.

DRAWINGS INDEX

GENERAL TITLE SHEET & LOCALITY PLAN 1000 KEY PLAN 1100 SITE LAYOUT PLAN RETAINING WALL SETOUT PLAN 1200 RETAINING WALL SETOUT PLAN SHEET 1 OF 3 1201 RETAINING WALL SETOUT PLAN SHEET 2 OF 3 1202 RETAINING WALL SETOUT PLAN SHEET 3 OF 3 1203 **RETAINING WALL NOTES & DETAILS** 1204 RETAINING WALL LONGITUDINAL SECTION 1205 RETAINING WALL SETOUT SECTIONS CONTROL LINE SETOUT 1300 CONTROL LINE SETOUT PLAN SHEET 1 OF 2 1301 CONTROL LINE SETOUT PLAN SHEET 2 OF 2 1302 CONTROL LINE SETOUT TABLES AND DETAILS ROADWORKS LAYOUT PLAN 1310 ROADWORKS LAYOUT PLAN SHEET 1 OF 3 1311 ROADWORKS LAYOUT PLAN SHEET 2 OF 3 ROADWORKS LAYOUT PLAN SHEET 3 OF 3 1312 INTERSECTION DETAILS 1320 INTERSECTION DETAILS SIGNS AND LINEMARKING PLAN 1330 SIGNS AND LINEMARKING PLAN SHEET 1 OF 3 1331 SIGNS AND LINEMARKING PLAN SHEET 2 OF 3 SIGNS AND LINEMARKING PLAN SHEET 3 OF 3 1332 SECTIONS **ROAD 3 LONGITUDINAL SECTION** 1340 1341 ROAD 3 CROSS SECTIONS 1342 ROAD 4 LONGITUDINAL AND CROSS SECTIONS 1343 ROAD 16 LONGITUDINAL AND CROSS SECTIONS 1344 ROAD 17 LONGITUDINAL AND CROSS SECTIONS

ROAD 18 LONGITUDINAL AND CROSS SECTIONS

STORMWATER LAYOUT PLAN SHEET 1 OF 4

STORMWATER LAYOUT PLAN SHEET 2 OF 4

1601 WATER RETICULATION LAYOUT PLAN SHEET 1 OF 3

1700 BIO-BASIN G3 LAYOUT PLAN 1701 **BIO-BASIN G3 SECTION PLAN** 1702 **BIO-BASIN NOTES AND DETAILS**

STORMWATER LAYOUT PLAN SHEET 3 OF 4 1403

STORMWATER LAYOUT PLAN SHEET 4 OF 4 STORMWATER DRAINAGE NOTES AND DETAILS 1404

STORMWATER CATCHMENT PLAN

STORMWATER CATCHMENT PLAN SHEET 1 OF 2 1411 STORMWATER CATCHMENT PLAN SHEET 2 OF 2

STORMWATER LONGITUDINAL SECTIONS

STORMWATER LONGITUDINAL SECTIONS SHEET 1 OF 2 1421 STORMWATER LONGITUDINAL SECTIONS SHEET 2 OF 2

STORMWATER CALCULATION TABLES

STORMWATER CALCULATION TABLES SHEET 1 OF 2 1431 STORMWATER CALCULATION TABLES SHEET 2 OF 2

STORMWATER STRUCTURES

1440 STORMWATER STRUCTURES DETAILS

SEWER RETICULATION PLANS

SEWER RETICULATION COVER SHEET

1501 SEWER RETICULATION LAYOUT PLAN SHEET 1 OF 4 1502 SEWER RETICULATION LAYOUT PLAN SHEET 2 OF 4 SEWER RETICULATION LAYOUT PLAN SHEET 3 OF 4 SEWER RETICULATION LAYOUT PLAN SHEET 4 OF 4 1504

SEWER LONGITUDINAL SECTIONS

1510 SEWER LONGITUDINAL SECTIONS SHEET 1 OF 3 1511 SEWER LONGITUDINAL SECTIONS SHEET 2 OF 3 1512 SEWER LONGITUDINAL SECTIONS SHEET 3 OF 3 1513 SEWER RETICULATION CONNECTION SECTIONS

WATER RETICULATION PLANS

WATER RETICULATION COVER SHEET 1600

1602 WATER RETICULATION LAYOUT PLAN SHEET 2 OF 3 1603 WATER RETICULATION LAYOUT PLAN SHEET 3 OF 3 1604


WATER RETICULATION CONNNECTION DETAILS AND SECTIONS.


BIO-BASIN PLANS


LILYWOOD LANDINGS


STAGE 23 DA REF NO. DA/2023/3497 22-000082 23 23 **OPERATIONAL** 13/10/23 1000 WORKS













RETAINING WALL DESIGN AND CONSTRUCT NOTES

- CONCRETE SLEEPER RETAINING WALL IS A DESIGN AND CONSTRUCT ITEM
- CONTRACTOR SHALL ENGAGE A RPEQ STRUCTURAL ENGINEER WITH SUITABLE RETAINING WALL EXPERIENCE.
- FOLLOWING DESIGN PARAMETERS SHALL BE ADOPTED
- a) SURCHARGE LOAD 5kPa FOR INTERALLOTMENT WALLS.
- b) SURCHARGE LOAD 20kPa WHERE WALLS ARE SUPPORTING ROADS OR DRIVEWAYS.
- c) ALLOW FOR WIND AND DEAD LOADS FOR SOLID 1.8m HIGH FENCE, OR HIGHER IF SPECIFIED IN THE ACOUSTIC REPORT
- d) ALLOW FOR MAX 1 IN 4 SLOPE AT TOP AND TOE OF WALLS.
 e) TORSIONALLY RIGID BEAMS SUCH AS UC SECTION SHALL BE SPECIFIED.
- DESIGN SHALL ACHIEVE 60 YEAR DESIGN LIFE. OR DESIGN LIFE SPECIFIED BY THE RELEVANT ALITHORITY
- g) CONTRACTOR SHALL ARRANGE GEOTECHNICAL INVESTIGATION AND STRUCTURAL DESIGN SHALL ALLOW FOR CONDITIONS IDENTIFIED IN INVESTIGATION.
 h) WALL DESIGN SHOULD INCLUDE FOUNDATION LEVELS WITH THEIR LINE OF INFLUENCE



- BE LODGED FOR EARTH RETAINING STRUCTURES >1000mm HIGH.
 ALL WALLS TO BE DESIGNED BASED ON A GEOTECHNICAL ASSESSMENT OF INSITU SOILS BY A SUITABLY QUALIFIED ENGINEER. SHOULD WALLS REQUIRE ADDITIONAL FOOTINGS AND/OR FOUNDATION SUPPORT, THESE ARE TO BE FACTORED INTO THE DESIGN AND THE TENDERED COST OF THE WALLS.
- PRIVATE WALLS INCLUDING FOOTING TO BE CONTAINED WHOLLY WITHIN PRIVATE PROPERTY AND ARE TO BE FULLY CONTAINED WITHIN THE LOWER LOT UNLESS WALL ABUTS ROAD RESERVE/PARK, IN WHICH CASE THE WALL SHALL BE CONTAINED WHOLLY WITHIN THE PRIVATE PROPERTY.
- SUBSOIL DRAINAGE BEHIND ALL WALLS TO INCLUDE DISCHARGE PIPE INTO THE NEAREST STORMWATER STRUCTURE (OR DEDICATED KERB ADAPTOR) AND MUST BE FREE



BOULDER RETAINING WALL NOTE STEPPED BOULDER RETAINING WALLS TO BE CONSTRUCTED WITH 1.5m HORIZONTAL CLEARANCE BETWEEN THE FRONT AND BACK OF SUBSEQUENT WALLS.

2000 1200 500 2500 1500 750 500 3000 1800 900 750

- SURCHARGE LOADING ON BACKFILL : 5KPa FOR LOTS AND 10KPa FOR ROAD RESERVE. POST AND FOOTING DESIGN TO ALLOW FOR 1.8m HIGH FENCE OR HIGHER IF SPECIFIED IN THE ACOUSTIC REPORT.

MAX 1V:4H SLOPE BEHIND WALL

- PROVIDE APPROVED SAFETY FENCE TO ALL WALLS HIGHER THAN 1.0m
- ALL RETAINING WALL FOOTINGS TO BE LOCATED A MINIMUM 1.0m HORIZONTALLY CLEAR OF THE ROOFWATER AND SEWER AND BE TAKEN BELOW THE ZONE OF INFLUENCE.

VISION DATE ISSUE DETAILS DRAWN DESIGN FOR 07.06.23 ISSUED FOR APPROVAL 12.10.23 REVISED AS PER COUNCIL R aa **APPROVAL** RYAN ASHWORTH RPEQ 19674 Ryan Ashworth Moreton Bay

FOREVERLEN PTY LTD

LENNIUM



LANDINGS STAGE 23


LOT


RETAINING WALL NOTES & DETAILS

22-000082_23


AS SHOWN

1203









ROAD 3 CONTROL LINE SETOUT TABLE

	PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
1	IP 1	0.000	90896.379	502042.959	8°55'08.74"			
	TC	52.303	90904.488	502094.629	8°55'08.74"			
SAD	IP 2	65.993	90906.665	502108.503		R = 50.000	27.381	31°23'33.09"
S S	CT	79.683	90915.747	502119.214	40°17'41.82"			
Ě	TC	125.608	90945.447	502154.242	40°17'41.82"			
EXISTING ROAD	IP 3	133.286	90950.897	502160.669		R = 15.000	15.355	58°39'12.57"
	CT	140.964	90959.232	502159.358	98°56'54.40"			
•	TC	302.931	91119.217	502134.165	98°56'54.40"			
	IP 4	314.313	91133.267	502131.953		R = 15.000	23.765	86°57'18.56"
	CT	325.696	91131.805	502117.805	185°54'12.96"			
	TC	461.560	91117.830	501982.661	185°54'12.96"			
	IP 5	475.543	91115.752	501962.562		R = 15.000	27.966	106°49'23.52"
	CC	489.526	91097.115	501970.369	292°43'35.49"			
	IP 6	538.580	91051.650	501989.412		R = -408.000	98.108	13°46'38.45"
1	CT	587.634	91002.959	501997.079	278°56'57.04"			
ဗ္	TC	624.052	90966.983	502002.745	278°56'57.04"			
EXISTING	IP 7	635.833	90952.167	502005.078		R = 15.000	23.561	89°59'48.96"
ŭ "	CT	647.614	90954.499	502019.895	8°56'46.00"			
•	IP8	709.614	90964.141	502081.141	8°56'46.00"			

BASIN G3 ACCESS CONTROL LINE SETOUT TABLE

PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE		
IP 1	0.000	91140.585	502307.584	5°54'12.96"					
TC	7.013	91141.307	502314.559	5°54'12.96"					
IP 2	11.254	91141.771	502319.051		R = 10.000	8.483	48°36'07.23"		
CT	15.495	91145.447	502321.672	54°30'20.18"					
IP 3	21.190	91150.084	502324.979	54°30'20.18"					

ROAD 4 CONTROL LINE SETOUT TABLE

TOTAL TOURITION SINCE OF TOUR TABLE							
PT	CHAINAGE	EASTING	NORTHING	BEARING			
IP 1	0.000	90903.860	502090.633	98°56'54.40"			
IP 2	234.257	91125.388	502055.751	98°56'54.40"			

ROAD 16 CONTROL LINE SETOUT TABLE

	PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
	IP 1	0.000	91125.645	502131.523	35°44'10.97"			
Ī	TC	10.418	91131.730	502139.980	35°44'10.97"			
	IP 2	14_233	91133.908	502143.007		R = -14.000	7.290	29°49'58.14"
ĺ	CT	17.708	91134.291	502146.717	5°54'12.84"			
ĺ	IP 3	78.899	91140.585	502307.584	5°54'12.84"			

ROAD 17 CONTROL LINE SETOUT TABLE


PT	CHAINAGE	EASTING	NORTHING	BEARING
IP 1	0.000	91137.976	502182.353	278°56'54.40"
IP 2	20.938	91117.294	502185.609	278°56'54.40"

ROAD 18 CONTROL LINE SETOUT TABLE

Γ	PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
	IP 1	0.000	91110.572	501971.301	149°18'45.43"			
	TC	8.813	91115.070	501963.723	149°18'45.43"			
	IP 2	14.469	91118.036	501958.725		R = -20.000	11.311	32°24'17.86"
	CC	20.125	91123.218	501956.095	116°54'27.57"			
	IP 3	35.863	91137.260	501948.969		R = 406.100	31.478	4°26'27.94"
	IP 4	51.602	91150.708	501940.777	121°20'55.51"			

RETAINING WALL CONTROL LINE SETOUT TABLE

PT	CHAINAGE	EASTING	NORTHING	BEARING
IP 1	0.000	91147.112	501896.232	5°53'51.46"
IP 2	316.163	91179.598	502310.723	
IP 3	346.146	91149.774	502313.803	
IP 4	351.146	91149.259	502308.829	185°54'12.96"




BARRIER KERB AND CHANNEL

TYPE B1 (300mm) IPWEA


SCALE 1:25

* NOMINAL KERB LINE



BARRIER KERB ONLY TYPE B2 IPWEA SCALE 1:25

★ NOMINAL KERB LINE



MOUNTABLE KERB AND CHANNEL

TYPE M3 IPWEAQ

SCALE 1:25

★ NOMINAL KERB LINE

NOTE: REFER TO DRG 22-000082_23_1300 FOR DRG LEGEND.













1302


22-000082_23


















- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).

PRELIMINARY ROAD 3 PAVEMENT DESIGN

ROAD	SUBGRADE CBR	TRAFFIC ESA'S	ROAD CLASS	AC SURFACING (mm)	BASE (mm)	SUB-BASE (mm)	LOWER SUB-BASE (mm)	TOTAL BOX (mm)
ROAD 3	3 *	1.2 X 10 ⁵	LIVING RESIDENTIAL	25 BCC TYPE 2	100	100	300	525

^{*} ASSUMED SUBGRADE CBR

www.egis-group.com




RPEQ 19674

Ryan Ashworth R & ON BEHALIF OF CALIBRE PROFESSIONA

Moreton Bay

1340


22-000082_23



NOTE:

VISION DATE ISSUE DETAILS

- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).



DRAWN DESIGN

Moreton Bay

aa

FOR

APPROVAL

RPEQ 19674


RYAN ASHWORTH

Ryan Aslworth
ON BEHALF OF CALIBRE PROFESSION

PRELIMINARY ROAD 4 PAVEMENT DESIGN

				• · · · · · · · · · · · · · · · · · · ·		. •		
ROAD	SUBGRADE	TRAFFIC	ROAD CLASS	AC SURFACING (mm)	BASE	SUB-BASE	LOWER SUB-BASE	TOTAL BOX
KUAD	CBR	ESA'S	ROAD CLASS	AC SURI ACING (IIIII)	(mm)	(mm)	(mm)	(mm)
ROAD 4	3 *	1.2 X 10 ⁵	LIVING RESIDENTIAL	25 BCC TYPE 2	100	100	300	525

^{*} ASSUMED SUBGRADE CBR



www.egis-group.com

VERTICAL

FOREVERLEN PTY LTD

LENNIUM

22-000082_23

LANDINGS

STAGE 23

ROAD 4 LONGITUDINAL AND

CROSS SECTIONS

1342

- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).

aa

Moreton Bay

APPROVAL

Kyan Ishworth


RPEQ 19674

RYAN ASHWORTH

PRELIMINARY ROAD 16 PAVEMENT DESIGN

ROAD	SUBGRADE	TRAFFIC	ROAD CLASS	AC SURFACING (mm)	BASE	SUB-BASE	LOWER SUB-BASE	TOTAL BOX
RUAD	CBR	ESA'S	RUAD CLASS	AC SURFACING (IIIII)	(mm)	(mm)	(mm)	(mm)
ROAD 16	3 *	1.2 X 10 ⁵	LIVING RESIDENTIAL	25 BCC TYPE 2	100	100	300	525

^{*} ASSUMED SUBGRADE CBR



VERTICAL

LENNIUM

www.egis-group.com

22-000082_23

AND CROSS SECTIONS

1343

LANDINGS

STAGE 23


NOTE:

- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).

PRELIMINARY ROAD 17 PAVEMENT DESIGN

ROAD	SUBGRADE	TRAFFIC	ROAD CLASS	AC SURFACING (mm)	BASE	SUB-BASE	LOWER SUB-BASE	TOTAL BOX
ROAD	CBR	ESA'S	RUAD CLASS	AC SURFACING (IIIII)	(mm)	(mm)	(mm)	(mm)
ROAD 17	3 *	1.2 X 10 ⁵	LIVING RESIDENTIAL	25 BCC TYPE 2	100	100	300	525

^{*} ASSUMED SUBGRADE CBR



ROAD 17 - LONGITUDINAL SECTION

HORIZ SCALE: 500
VERTICAL SCALE: 50

VISION DATE ISSUE DETAILS

REFER INTERSECTION DETAILS FOR LEVELS

RYAN ASHWORTH

aa


FOR

APPROVAL

RPEQ 19674

DRAWN DESIGN

Moreton Bay



ROAD 17 - CROSS SECTIONS

SCALE 1:100

FOREVERLEN PTY LTD

C 2023 Egis Consulting Pty Ltd

www.egis-group.com

LANDINGS
STAGE 23

ROAD 17 LONGITUDINAL AND CROSS SECTIONS

STAGE 23

SCIAIMER
LL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO ONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.

1344

HORIZONTAL

VERTICAL

1:100


PAVEMENT NOTE:

DRIVEWAY TO BE 175mm THICK N32 CONCRETE WITH SL92 MESH ON 150mm BASE TYPE 2.1. FINISH PER LANDSCAPE SPECIFICATION.

NOTE:

VISION DATE ISSUE DETAILS

- PRELIMINARY PAVEMENT DESIGNS HAVE BEEN BASED ON AN ASSUMED SUBGRADE CBR. ACTUAL PAVEMENT DESIGNS WILL BE BASED ON TEST RESULTS TAKEN AFTER STRIPPING HAS BEEN COMPLETED.
- WHEN THE TOTAL PAVEMENT DEPTH (AS DETERMINED BY SUBGRADE TESTS) EXCEEDS THE NORMAL DEPTH, THE PAVEMENT GRAVEL SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm BEHIND (TYP).





Moreton Bay

DRAWN DESIGN

aa

REFER INTERSECTION DETAILS FOR LEVELS


RYAN ASHWORTH

FOR

APPROVAL

Kyan Uslworth & ON BEHALF OF CALIBRE PROFESSIONAL SERVICES PTY LTD

RPEQ 19674





Concrete Driveway to toe boundary of Lot 684 to 686 - CMB


HORIZONTAL


VERTICAL

1:100









STORMWATER DRAINAGE NOTES

- 1. ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH CURRENT M.B.R.C STANDARD DRAWINGS AND METHODS
- 2. ALL STORMWATER PIPES UNDER ROADWAYS AND FOOTPATHS SHALL BE RCP CLASS 3 U.N.O.
- 3. ALL STORMWATER PIPES UP TO AND INCLUDING 600Ø SHALL BE R.R.J. STORMWATER PIPES GREATER THAN 600Ø SHALL BE INTERNAL FLUSH JOINTED WITH PROPRIETARY EXTERNAL BAND
- STEPIRONS ARE TO BE PROVIDED IN STORMWATER MANHOLES AND GULLIES GREATER THAN 1.20m DEEP, IN ACCORDANCE WITH M.B.R.C STD. DRG. SD.10.
- 5. ALL DIMENSIONS ARE IN METRES UNLESS SHOWN OTHERWISE.
- CONTRACTOR TO LIAISE WITH ALL RELEVANT SERVICE AUTHORITIES TO ASCERTAIN SERVICES
 PRESENT ON-SITE. ANY ALTERATION WORKS TO SERVICES WILL BE CARRIED OUT BY THAT SERVICE
 AUTHORITY ONLY.
- 7. THE CONTRACTOR SHALL NOTIFY THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF DEMOLISHING ANY EXISTING STRUCTURES WITHIN THE SITE AREAS.
- 8. THE STORMWATER PIPE CLASSES HAVE BE DESIGNED FOR SERVICE LOADS ONLY, AND THE CONTRACTOR SHALL ASSESS ANTICIPATED CONSTRUCTION LOADS AND UPGRADE THE PIPE CLASSES IF NECESSARY, IN ACCORDANCE WITH AS3725-2007.
- RETAINING WALL SUBSOIL DRAINS TO CONNECT TO KERB AND CHANNEL SUBSOIL OR STORMWATER DRAINAGE STRUCTURES.
- WORKS SHALL BE PROGRAMMED SO AS NOT TO DISTURB NEARBY HOUSEHOLDERS EITHER BY DUST, NOISE, FLOODING OR DISCONNECTION OF SERVICES.
- 11. ALL CONSTRUCTION ACTIVITIES SHALL COMPLY WITH WORKPLACE HEALTH AND SAFETY REQUIREMENTS.
- 12. ANTI PONDING GULLIES ARE TO BE SIDE ENTRY TYPE. CHAMBER AND GRATE ONLY TYPE NOT TO BE USED.
- 13. GULLY PITS IN EXCESS OF 1.5 METRES DEEP ARE TO BE CONSTRUCTED AS A GULLY PIT/ACCESS CHAMBER STRUCTURE.
- 14. CRACKS IN STORMWATER PIPES WILL NOT BE ACCEPTED.
- 15. LEVELS AND GRADIENTS AT JUNCTIONS WITH EXISTING WORKS MAY BE VARIED AS REQUIRED TO ACHIEVE A SATISFACTORY CONNECTION AND THE CONTRACTOR SHALL INCLUDE THE COST OF THIS WORK IN THE TENDER PRICE. WHERE NEW WORK JOINS EXISTING, THE WORK SHALL TRANSITION NEATLY WITH THE PAVEMENT SO THAT DEVIATION FROM THE LINE OF A 3.0m STRAIGHT EDGE SHALL BE NO GREATER THAN 10mm.
- 16. CONDUITS SHALL BE IN ACCORDANCE WITH I.P.W.E.A STD. DRG. RS-101.
- 17. ALL EXCAVATION AND FILLING SHALL BE COMPACTED TO THE REQUIREMENTS OF AS3798-2007 IN ACCORDANCE WITH THE LOCAL AUTHORITY REQUIREMENTS.
- 18. ALL LEVELS ARE IN METRES ABOVE AUSTRALIAN HEIGHTS DATUM (mAHD) UNLESS OTHERWISE SHOWN

KERB ADAPTORS NOTES

ALL LOTS NOT DRAINING TO A PROPERTY PIT TO HAVE 2 KERB ADAPTORS . KERB ADAPTORS SHOWN ARE INDICATIVE ONLY AND ARE TO BE INSTALLED IN ACCORDANCE WITH IPWEA STD DRG RS-081.

NOTE

NOTWITHSTANDING THAT EXISTING SERVICES MAY OR MAY NOT BE SHOWN ON THE JOB DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE SUPERINTENDENT OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ANY UNDERGROUND SERVICES IN THIS AREA AND SHALL BE RESPONSIBLE FOR MAKING GOOD ANY DAMAGE THERETO.

SCOUR PROTECTION NOTES:


- 1. IF ROCK SIZE IS SPECIFIED ON THE PLAN AS D_{50} THIS CORRESPONDS TO A ROCK SIZE WITH A MEDIAN ROCK DIAMETER OF D_{50} . A VARIANCE OF $\pm 30\%$ IS ACCEPTABLE. Eg. IF D_{50} = 600 IS SPECIFIED THEN THE EQUIVALENT ROCK DIAMETER RANGES FROM 420mm TO 780mm.
- NEITHER BREADTH NOR THICKNESS OF A SINGLE ROCK SHALL BE LESS THAN ONE HALF ITS LENGTH (ie THE ROCK SHALL BE CHUNKY RATHER THAN FLAT).
- 3. ROCK TYPE BASALT OR OTHER APPROVED MATERIAL. TO BE CONFIRMED WITH SUPERINTENDENT BEFORE COMMENCING ROCK WORK.
- 4. ROCKS GREATER THAN D_{50} =450 TO BE PLACED AND INTERLOCKED INTO POSITION AND BUILT UP TO FINAL LEVELS SHOWN, ENSURING COVERAGE OF GEOFABRIC. GAPS BETWEEN THE BOULDERS ARE TO BE FILLED BY DROPPING STONES INTO GAPS AND LOCKING INTO POSITION WITH A CROWBAR.
- 5. ROCKS LESS THAN & EQUAL TO D_{50} =450 TO BE DUMPED & MOVED INTO POSITION. BUILD UP TO FINAL LEVELS & ENSURING COVERAGE OF GEOFABRIC.

REFERENCE POINT LOCATION FOR DRAINAGE


STRUCTURES HORIZONTAL CONTROL STRUCTURE VERTICAL CONTROL (REFERENCE POINT LOCATION) (REFERENCE LEVEL) TYPF FINISHED SURFACE € OF MAIN MANHOLE LEVEL SHAFT GEOMETRIC **GULLY PIT** CENTRE OF PIT KERB LIP LEVEL STRUCTURE INTERSECTION INVERT OF OF HEADWALL **HEADWALL** HFADWAI I FACE AND PIPE 9

ROCK SCOUR PROTECTION

OUTLET	OUTLET PIPE SIZE	VELOCITY	D ₅₀	'L'
OUT/H21	Ø 450	2.06m/s	300 mm	5.0m




TYPICAL GULLY PIT PIPE CONNECTION DETAIL



STORMWATER / SEWER BRIDGING DETAIL - SECTION

SCALE 1:20 (A1) SCALE 1:40 (A3)




STORMWATER / SEWER BRIDGING DETAIL - ELEVATION


SCALE 1:20 (A1) SCALE 1:40 (A3)

		X = WIDTH OF CON	CRETE PIERS (mm)
Γ	PIPE SIZE	FIRM/STIFF CLAY SAFE	STIFF/VERY STIFF CLAY
L	FIFE SIZE	BEARING >150kPa	SAFE BEARING >200kPa
	600Ø - 1050Ø	600	450
	1200Ø - 2100Ø	450	350

NOTE

GROUND CONDITIONS TO BE VERIFIED ON-SITE BY SUPERINTENDENT. IF LESSER GROUND CONDITIONS PREVAIL, SPECIALLY DESIGNED DRILLED PIERS ARE TO BE CONSIDERED.





TYPICAL SCOUR PROTECTION SECTION

REVISION DATE ISSUE DETAILS

A 07.06.23 ISSUED FOR APPROVAL

B 12.10.23 UPDATED TO EGIS

AAA AA AA

DESIGN DEAWN CHECK

STATUS

FOR
APPROVAL

DESIGN CHECK

APPROVED
RYAN ASHWORTH RPEQ 19674

RYAN ASHWORTH RPEQ 19674

FOR & ON BEHALT OF CALIBRE PROFESSIONAL SERV

1:20 0.2 0 0.2 0.4 0.6 0.8 1m A1 1:40 A3 1:50 1 0.5 0 1 2m A1 1:100 A3

LENNIUM





LANDINGS
STAGE 23


L DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO DINSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.


STORMWATER DRAINAGE
NOTES AND DETAILS

PROJECT No. DRAWING No. 1404










, [1	OCATION	C	ROPER	ENT		FULL	AREA F	RUNOFF			PART	T AREA	RUNOF	F						INLE	T DESIGN							D	RAIN DES	IGN							HEADI	LOSSES					F	PART F	ULL				DESIG	GN LEVE	LS		
		fi	Ci	Ср	tc	1	A	CA	Q	tc	1	Α	CA	Q	Q Q	а						Qg	Qb		tc	:	I C	A Q	Qp L	S		Vf	S/Do	o Qg/Q	o Du/Do		Vf2/2g	Ku	hu	Kw h	ıw S	Sf	hf	dn	Vn								
DESIGN ARI	STRUCTURE No.	FRACTION IMPERVIOUS	COEFFICIENT OF RUNOFF	RUNOFF	TIME OF CONCENTRATION	RAINFALL INTENSITY	SUB-CATCHMENT AREA	EQUI	SUB-CATCHMENT DISCHARGE	TIME OF CONCENTRATION	RAINFALL INTENSITY	PARTIAL CATCHMENT AREA	EQUIVALENT IMPERVIOUS AREA	SUB-CATCHMENT DISCHARGE	SOB-CATCHIMENT	HE CINA WO II	FLOW DEPTH	/×0 MO	ROAD GRADE AT INLET	ROAD XFALL AT I	INLET TYPE	FLOW INTO INLET	BYPASS FLOW	BYPASS STRUCTURE No.	CRITICAL TIME OF CONC.		KAINFALL IN LENSI IY TOTAL (C.x. A)	DIPE ELOW	PIPE FLOW REACH LENGTH	PIPE GRADE	PIPE SIZE	FULL PIPE VELOCITY	SUBMERGENCE RATIO	OIT.	DIAMETER RATIO	CHART(S) USED	VELOCITY HEAD	U/S HEAD LOSS COEFFICIENT	U/S HEAD LOSS		CHANGE IN W.S	PIPE FRICTION SLOPE	PIPE FRIC	NORMAL	NORMAL DEPTH VEL.	PIPE U/S I.L	PIPE D/S I.L	PIPE U/S H.G.L	PIPE D/S H.G.L	W.S.E	GRATE LEVEL	FREEBOARD	STRUCTURE No.
Yrs					min	mm/l	h ha	ha	L/s	min	mm/h	h ha	ha	L/s	/s L/	s n	n m		%	%		L/s	L/s		mir	n mm	n/hr h	ia L/	/s m	%	mm	m/s	5				m	m			m '	%	m	m	m/s	m	m	m	m	m	m	m	
10%	F1/H01	85	0.9	0.64	10	168	0.08	0.068	32	5	207	0.074	4 0.06	5 37	7 3	7 2.3	74 0.0	36 0.0	3 3.77	3	F1-6x9 on-grade 50% Blockage	11	26	F2/H0	1 5	20	0.0	065 1	11 18.7	3.96	375	0.1	1.01	1		G1	0.001	7	0.004	0.	004 3	3.81 0	.728 0.	0.047	1.45	25.76	25.02	25.836	25.12	2 25.839	27.099	1.259	F1/H01
10%	F2/H01	85	0.9	0.64	10	168	0.071	1 0.061	28	5	207	0.065	5 0.05	7 33	3 5	9 2.8	14 0.0	12 0.0	4 3.77	3	F1-6x9 on-grade 50% Blockage	15	44	F3/H0	1 5.1	1 20	06 0.1	122 2	26 17.79	5 3.37	375	0.23	1.02	0.56	1	G1/T1/T3	0.003	2.6	0.007	2.76 0.	008 3	.28 0	.596 0	0.072	1.75	25	24.4	25.115	24.53	2 25.123	3 26.394	1.271	F2/H01
10%	F3/H01	85	0.9	0.64	10	168	0.072	2 0.061	29	5	207	0.066	6 0.05	8 33	3 7	7	0.0	3	3.77		FSIP-6x9	13	64	G1/H04	4 5.2			18 3	38 7.50	3 4	375	0.35	1.04	0.33	1	T3	0.006	1.78	0.011	2.31 0.	014 0	.32 (0.07 0.	0.084	2.09	24.38	24.08	24.521	24.49	7 24.535	5 25.713	1.177	F3/H01
10%	4/H01	0																			MH1200				5.24			347 13		_		0.84	_	0	1	T6/T9	0.036	2.27	0.082	2.58 0.	093 0	.03 0				24.06	23.876	24.415	24.41	2 24.508		1.11	4/H01
10%	5/H01	0																			MH1050				5.29	_		_	26 36.06	1 2.37		1.42	1.52	. 0	1	T3/T6	0.103	1.96	0.202	2.29 0.	236 1	.06 ().44 0.	0.229	2.78	23.876	23.02	24.21	23.82	9 24.446	25.487	1.041	5/H01
10%	6/H01	0																			MH1200				5.43				57 33.57		_	1.65		_	1	T3/T6	0.139	1.71	0.237						2.94	23	22.32	23.593					6/H01
10%	7/H01	0																			MH1200				5.62	_		915 50				1.77			1	T1/T3	0.161	1.34	0.215			-		-	2.93	22.3	22.12	23.147			33.967	0.57	7/H01
10%	8/H01	0										+			-			_			MH1200				5.68	_			84 23.51			2.42	_	_	1	T1/T3	0.298	1.48	0.442						3.11	22.1	21.72	22.63	22.26				8/H01
10%	9/H01	0										_	_			_	_				MH1050				5.82	_	_	_	24 34.32	_		1.64		_	0.94		0.137	0.29	0.04						3.05	21.7	21.22	22.228	_	_		_	9/H01
10%	10/H01	0	-	+			_		+	+		_			_			-	_		MH1200				6.0	_		164 81		_		1.83	_	_	1 1	T1/T3	0.171	1.24	0.212					0.361	3.86	21.2	20.62	21.758			22.943	0.93	10/H01
10%	11/H01 12/H01	0	-	-	_	-				+		_			_		_	-	-		MH1350 MH1800				6.16	_			75 43.28			2.21	_	_	1	T1/T3	0.249	1.61 0.9	0.4			.94 1 .81 0		0.357	4.71	20.6	19.02 18.2	21.209 19.645				0.713	11/H01 12/H01
10%	13/H01	0								_		_									MH1500				6.26		90 2.0		13 27.26 171 14.92			1.84			_	T3/T6	0.324		0.291						_	18.18	18.1	18.838					13/H01
10%	OUT/H01	-		+	+	+	_	_	+	+		+	+	_	-	_	+	_	_		HW outlet	+			0.20	.0 13	91 2.1	149	1/1 14.32	3 0.54	900	1.04	1.42	-	+ '-	13/10	0.173	1.02	0.314	2.10 0.	311 0	1.00	.001 0.	0.007	2.33	10.10	10.1	10.030	10.74	18.741		0.532	OUT/H01
10%	G1/H02	85	0.9	0.64	10	168	0.125	5 0.107	50	5	207	0.116	6 0.10	1 58	8 5	8 24	84 0.0	8 00	5 0.82	3	GULLY MK-S	58	0	G1/H04	1 5	20	07 0.1	101 5	58 17.85	1 1.4	375	0.53	1.37	1	+	G2	0.014	9.7	0.137	0	137 0	72 0	176 0	1 136	1.61	24.45	24.2	24 625	24 49	7 24.762		0.999	G1/H02
10%	G1/H03	85	0.9	_	_	168	_		33	_	207		_	_		_		_	_	-	GULLY MK-S	38	0	G1/H0	_	_	07 0.0			_		0.34	_	_	+	G1	0.006	7			_	_		0.105	1.51	24.45	24.2	24.59				_	G1/H03
10%	G1/H04	85	0.9		_	168		_	36	5	207	_		_	1 10	_	06 0.0			3.07	GULLY MK-S	93	13	G1/H0			_	072 9		_		0.84	_	_		G2	0.036	8.16			294 0				2.23	24.06	24	24,418	_				G1/H04
10%	G1/H05	85	0.9		_				34	5				_			29 0.0				GULLY MK-S	40			_	_			10 12.60	_	_	0.36				G2	0.007	9.7			063 0				1.71	23.5	23.22	23.835		_			G1/H05
10%	G1/H06	85	0.9	0.64	10	168		_	85	5	207	0.197	7 0.172	2 99	9 11	_			1 2.59		GULLY MK-S	95	17	G1/H0	7 5	_	07 0.1	172 9				0.86		_		G2	0.038	5.81		0	.22 0	0.29 0	.007 0	0.14	2.53	23.2	23.12	23.836	23.82	9 24.057	7 24.573		G1/H06
10%	G1/H07	85	0.9	0.64	10	168	0.134	4 0.115	54	5	207	0.124	4 0.10	8 62	2 7	9 2.5	26 0.0	31 0.0	7 1.48	3	GULLY MK-S	76	3	G1/H10) 5	20	07 0.1	108 7	76 2.47	3 4.44	375	0.69	2.54	1		G2	0.024	4.82	0.116	0.	116 0	1.19 0	.005 0	0.115	2.63	22.53	22.42	23.366	23.36	2 23.482	2 23.927	0.445	G1/H07
10%	G1/H08	85	0.9	0.64	10	168	0.178	0.153	71	5	207	0.165	5 0.14	4 83	3 8	3 2.5	73 0.0	32 0.0	7 1.48	0.63	GULLY MK-S	74	9	G2/H09	9 5	20	07 0.1	144 7	74 7.37	1.22	375	0.67	2.31	1		G2	0.023	5.7	0.132	0.	132 0	0.18 0	.013 0	0.161	1.64	22.64	22.55	23.375	23.36	2 23.506	23.969	0.462	G1/H08
10%	G1/H09	85	0.9	0.64	10	168	0.215	5 0.184	86	5	207	0.199	9 0.174	4 100	00 10	0 4.1	92 0.0	95 0.0	5 0.6	1.05	GULLY MK-M	94	6	G1/H1	2 5	20	07 0.1	174 9	9.15	0.87	450	0.59	2.13	1		G2	0.018	6.47	0.116	0.	116 0	0.11 (0.01 0.	0.185	1.53	22.35	22.27	23.192	23.18	2 23.307	7 23.654	0.347	G1/H09
10%	G2/H09	85	0.9	0.64	10	168	0.181	1 0.155	72	5	207	0.168	8 0.14	7 84	4 9:	3	0.0		_	2.67	SAG MK-S	93	0	G1/H1:	2 5.09	_		32 18				0.86			0.86	T9/T10	0.038	2.14					_	0.253	1.81	22.25	22.12	23.1	23.07	2 23.196	23.603	0.407	G2/H09
10%	G1/H10	85	0.9	0.64	_	168	0.091	1 0.078	36	5	207	_	4 0.073	3 42	2 4	5 2.0	_	_		3	GULLY MK-S	45	0	G1/H1	_	_		073 4		_	_	0.41				G2	0.009		0.084		_	_	_	_	2.2	22.1	22	22.254	_		_	_	G1/H10
10%	G1/H11	85	0.9		_	168			54	5	207	_				_				3	GULLY MK-S	62	0		_	_	07 0.1			_		0.56				G2	0.016	9.7		_		_			2.4	21.6	21.5	21.973	_	_			G1/H11
10%	G1/H12	85		_				_		_	_		-	_	-	_	51 0.0		_	3	GULLY MK-S	31	0		_	_		044 3	0.01			0.28	_	_		G2	0.004	9.7						0.086	1.62	21.6	21.45	21.972		_			G1/H12
10%	G1/H13	85	0.9	0.64	10	168	0.219	9 0.188	88	5	207	0.203	3 0.178	8 102	02 10	12	0.0	76	0.29	2.98	SAG MK-S	102	0	G1/H16		_	07 0.1	_		_	_	0.92	_	_	+ .	G2	0.044				287 0	_		-	2.62	21.3	21.22	21.8	_	2 22.087		_	G1/H13
10%	2/H13	0		1	1	10-		2 000		+-						- -	70 0			1	MH1050	ļ	-	6	5.0			204 11		_		1.06		_	1	T6/T9	0.057				142 0				2.55	21.2	20.82	21.667					2/H13
10%	G1/H14	85						_	_	5	_		_	_	-		72 0.0				GULLY MK-S	15	0			_		027 1	7.2.		375	0.14			+	G2	0.001	9.7	0.01	_				0.073	1.01	21.3	21.22	21.793			LL.OLO		G1/H14
10% 10%	G1/H15 G1/H16	85 85	0.9	_				_		5	207	_	_	_	_	_	13 0.00 97 0.00		_	3.13	GULLY MK-S GULLY MK-S	57 59			_	_	07 0.1 07 0.1	107 5 12 5		_	_	0.51		_	+	G2 G2	0.013	8.37 9.7			113 (142 -0		_	_	2.12	21.07 19.7	21 19.3	21.612 19.926		_		_	G1/H15 G1/H16
10%	G1/H16 G1/H17	85	0.9			168	0.140		65	5	207				5 8	_	18 0.0		9 3.79		GULLY MK-S GULLY MK-S	68	12	G2/H18			07 0.1	-			375	0.54			+	G2 G2	0.015	8.52	_		164 0			0.107	2.20	19.46	19.3	19.920	19.93			0.995	G1/H16 G1/H17
10%	G1/H17 G1/H18	85	0.9		_	168			1 1	5			-	_	1 1	_	84 0.0		0.5	-	GULLY MK-S GULLY BK-S	1	0		_	_		002 1				0.01			+	G2 G2	0.019	7.91	0.104						0.42	19.40	19.2	19.947				0.707	G1/H17
10%	G2/H18	85	0.9		_	-			9	5	207			_	0 2	_	34 0.0		_		GULLY MK-S	20	_		_	_	_	021 2				0.01		_	1	G1/T10	0.002		- ŭ		009 0	<u> </u>			0.42	19.18	19.02	19.939				0.483	G2/H18
10%	G1/H19	85	0.9	_	_	168	0.025		6	5	207	_	_	_	7 7	0 1.0		_	_		GULLY MK-S	7	0	F1/H2			_	012 7		_		0.13	_		+ '-	G2	0.002		0.000		.001	0	_	0.042	1.05	18.35	18.2	19.152			1 19.693	0.403	G1/H19
10%	G1/H20	85	0.9		_				44					_	1 6	_	14 0.0				GULLY MK-S	58	5		_	_		088 5				0.52	_		1	G2	0.014					0.11 0	-		2.01	18.36	18.3	19.155				0.46	G1/H20
10%	F1/H21	0	1	1	1.0	1.50	0.100		_		1 -5.		0.00) 27	_	0.3			+ -	RSIP-9x9	267			_	_			67 29.21	_		1.68		_	+	G2		4.82			692 0	_				16.5	16.2	16.863					F1/H21
	OUT/H21						† ·					† ·	+		1						HW outlet	1		1	<u> </u>					1		+	1	1		T				- 1								1	1		17.212		OUT/H21


STORMWATER DRAINAGE CALCULATIONS - MINOR 10% AEP


	OCATION	CATC	HMENT ERTIES		FUI	LL ARE	EA RUNO	FF		PA	ART AREA	A RUN	OFF						INLE	ET DESIGN							DRAIN	N DESIGN	N							HEADLO	SSES					PA	RT FULL	L			DE	SIGN LE	VELS		
		fi		p t	tc I		Α (CA C	Q .	tc	I A	A C	CA C	2 (Qa						Qg Qb			tc	I	CA	Qp	L	S		Vf	S/Do Q	Qq/Qo [Du/Do		Vf2/2g	Ku	hu	Kw	hw S	Sf h	f dr	n Vn	,							
		-"	01 0	,			Λ (∢	й Д			,, ,	E A	ш .	, au									10	İ	O/ C	٠,		Ü		**	0/20 4	(g, q, o L	54150		112/29		iiu .	1.00												
DESIGN ARI	STRUCTURE No.	RACTION IMPERVIOUS	IMPERVIOUS AREA	PERVIOUS AREA	IME OF CONCENTRATION	KAINFALL INTENSITY	SUB-CATCHMENT AREA	KVIOUS A	MEN I DISCHARC	IME OF CONCENTRATION		CHMEN I A	COUIVALENT IMPERVIOUS AR	AICHMENI DISC	LOW IN K&C(INC. BY PASS)	:LOW DEPTH	LOW DxV		=	NLET TYPE	FLOW INTO INLET BYPASS FLOW		SYPASS STRUCTURE NO.	CRITICAL TIME OF CONC.	∄	TOTAL (C × A)	IPE FLOW	EACH LENGTH	IPE GRADE	IPE SIZE	ULL PIPE VELOCITY	MERGENC	GRATE FLOW RATIO	DIAMETER RATIO	JHAK I(S) USED	8	J/S HEAD LOSS COEFFICIENT	J/S HEAD LOSS	S.E COEFFIC	CHANGE IN W.S.E	9	INE FRICTION HEAD LOSS	VORMAL DEPTH VEL.	YPE U/S I.L			ć :	IPE D/S H.G.L	V.S.E	3RATE LEVEL	REEBOARD
Yrs	0)			m	nin mn	n/h	ha h	na L	/s n	min mr	ım/h ha	na I	ha L	/s L	/s m	m	+ "	- W	%	=	L/s L/s			min r		_	L/s	m	%	mm	m/s	-0,	$\overline{}$	'	_		m		-		6 n	n m	n m/s	s m	m m	m	n	m	m .	m	m O
	=10101	85	1 0:				_	-	_							_	_			F1-6x9 on-grade 50%			_	_		_							.				_		_		_	-			_	-					
1%	F1/H01	85	. 0.		-				53			-	.072 7	_	74 3.0	0.046	-	_	_	Blockage F1-6x9 on-grade 50%	16 58 21 102	_	/H01	-		0.072	16 37	18.7	3.96	375	0.15	1.02	0.57		31	0.001		0.008			- -	718 0.08	-	+	_						1.24 F1/H0
	F2/H01								56											Blockage							٥.	17.795		375					T1/T3		2.62														
1%	F3/H01		1 0.	77 1	10 29	94 (0.072 0.	069 5	56	5 3	370 0.0	066 0.	.065 6	57 1	69	0.03		3.7	'	FSIP-6x9	13 156	G [*]	-	-		-	49	7.506	4	375	0.45		0.26		Г3		1.75 (_	2.16	-	_	_	95 2.24	_	_	-		1.985 25			0.7 F3/H0
1% 1%	4/H01 5/H01	0	_	_	_		_	_	_		_	_		_	_		+	_		MH1200 MH1050		_	_	_			211	8.203 36.061	2.25	450 450	1.33		0		6/T9 8/T6			_	2.17 (55 0.0 04 0.3			_			_				0.61 4/H01 1.694 5/H01
1%	6/H01	0	_	_	_		_			_	_	_		_	_		+-	+-		MH1200		+		_			291 433	33.577	2.03	525			0		I/T3		1.28				01 0.3	-	_		-).481 6/H01
1%	7/H01	0																		MH1200						1.026	552	11.188	1.61	600		2.13	0		I/T3						81 0.0				_	_					1.448 7/H01
1%	8/H01	0										_					+			MH1200				_		_	606	23.517	1.62	600	2.14		0		/T3					_	97 0.2	_	_	_	_).581 8/H01
1%	9/H01	0															+-			MH1050							728	34.329	1.4	750			-		I/T3		0.88			.145 0.	_	_		_	_						0.62 9/H01
1%	10/H01	0	-									_					+-	+		MH1200		_	-	-		1.641	970	23.943	2.42	750	2.2		0		3/T6		-	0.408		-	76 0.1	-	_	_		-	_	_		_	0.341 10/H0°
1%	11/H01	0																		MH1350			_			_	1270	43.288	3.65	750	_		0		B/T6	0.421					.1 0.9		-			_					1.362 11/H0
1%	12/H01	0																		MH1800			6	5.16	352 2	2.296	1676	27.262	2.93	750			0	1 T	I/T3	0.381	1.16	0.443	1.33	.508 1.	18 0.3	321 0.54	45 4.87				922 19	9.601 2	0.43 20	0.778	1.349 12/H0°
1%	13/H01	0																		MH1500				_					0.54	900			0			0.328	1.75 (_		.664 0.		_	_	6 18.1		_		3.884 19	0.692 19		.054 13/H0°
1%	OUT/H01																			HW outlet																												18	3.884 19	9.55	OUT/H0
1%	G1/H02	85	1 0.	77 1	10 29	94 0	0.125 0.	121 9	98	5 3	370 0.1	116 0.	.113 1	16 1	16 3.24	0.101	0.08	3 0.83	2 3	GULLY MK-S	90 26	G [']	/H04	5	370 (0.113	90	17.851	1.4	375	0.81	2.13	1	(32	0.034	6.44	0.218	(.218 0.:	26 0.0	0.17	73 1.81	1 24.4	5 24.2	2 25.0	032 24	1.985 2	5.25 25	5.761	0.512 G1/H02
1%	G1/H03	85	1 0.	77 1	10 29	94 (0.082 0.	079 6	64	5 3	370 0.0	075 0.	.074 7	76	76 2.76	4 0.088	0.06	8.0	3	GULLY MK-S	74 2	G′	/H05	5	370 (0.074	74	15.375	1.63	375	0.67	1.83	1	-	31	0.023	5.53 (0.126	(.126 0.	18 0.0	0.14	48 1.82	2 24.4	5 24.2	2 25.0	012 24	1.985 25	5.138 25	5.762	0.624 G1/H00
1%	G1/H04	85	1 0.	77 1	10 29	94 C	0.089 0.	086 7	70	5 3	370 0.0	082 0.	.081 8	33 2	66 4.82	6 0.124	0.14	1.48	3.07	GULLY MK-S	81 185	G ²	/H06	5	370 (0.081	81	2.499	2.4	375	0.73	2.32	1	-	G2	0.027	5.67 (0.156	(.156 0.	21 0.0	0.1	14 2.15	5 24.0	6 24	24.7	773 24	1.768 24	1.929 25	5.449	0.52 G1/H04
1%	G1/H05	85	1 0.	77 1	10 29	94 C	0.085 0.	082 6	67	5 3	370 0.0	079 0.	.077 7	79	81 2.29	2 0.074	0.08	3 2.6	3	GULLY MK-S	77 5	G [']	/H08	5	370 (0.077	77	12.601	2.22	375	0.7	2.08	1	(32	0.025	6.65	0.164	(.164 0.	19 0.0	0.13	39 2.06	6 23.	5 23.2	22 24.1	117 24	1.093 24	4.281 24	1.835	0.554 G1/H0
1%	G1/H06	85	1 0.	77 1	10 29	94 0	0.213 0.3	206 16	68	5 3	370 0.1	197 0.	.193 19	99 3	83 5.17	7 0.129	0.19	2.5	3	GULLY MK-S	73 310	G'	/H07	5	370 (0.193	73	2.397	3.34	375	0.66	2.66	1	(32	0.022	4.54 (0.101	().101 0.	17 0.0	0.12	22 2.35	5 23.	2 23.1	24.0	097 24	1.093 24	1.198 24	1.573	.374 G1/H06
1%	G1/H07	85	1 0.	77 1	10 29	94 0	0.134 0.	129 10	05	5 3	370 0.1	124 0.	.121 12	25 4	35 5.92	0.145	0.18	1.48	3	GULLY MK-S	62 373	G [*]	/H10	5	370 (0.121	62	2.478	4.44	375	0.56	2.76	1		G2	0.016	4.33	0.069	(.069 0.	12 0.0	0.10	04 2.48	8 22.5	3 22.4	23.4	495 23	3.492 23	3.565 23	3.927	0.363 G1/H0
1%	G1/H08	85	1 0.	77 1	10 29	94 0	0.178 0.	172 14	40	5 3	370 0.1	165 0.	.162 16	66 1	71 3.46	4 0.105	0.11	1 1.48	0.63	GULLY MK-S	69 101	G	/H09	5	370 (0.162	69	7.375	1.22	375	0.63	2.56	1		G2	0.02	4.77 (0.095	(.095 0.	16 0.0	0.1	55 1.61	1 22.6	4 22.5	55 23.5	504 23	3.492 23	3.599 23	3.969	0.37 G1/H08
1%	G1/H09	85	1 0.	77 1	10 29	94 C	0.215 0.	207 16	69	5 3	370 0.1	199 0.	.195 2	00 2	00 4.89	0.119	0.08	3 0.6	1.05	GULLY MK-M	74 125	G [*]	/H12	5	370 (0.195	74	9.159	0.87	450	0.47	2.9	1	(G2	0.011	4.02	0.045	(.045 0.	0.0	0.10	63 1.44	4 22.3	5 22.2	27 23.	.61 23	3.603 23	3.654 23	3.654	0 G1/H09
1%	G2/H09	85	1 0.	77 1	10 29	94 (0.181 0.	175 14	43	5 3	370 0.1	168 0.	.164 16	69 2	70	0.13		0.8	2.67	SAG MK-S	-10 280	G G	/H12 5	5.09	368 (0.359	63	15.194	0.86	525	0.29	1.83	0	0.86 T9	/T10		2.03 (2.57 (0.011 0.0	02 0.0	0.14	42 1.34	4 22.2	5 22.1	23.2	202 23	3.199 23	3.213 23	3.603	0.39 G2/H0
1%	G1/H10	85	1 0.	77 1	10 29	94 (0.091 0.	088 7	72	5 3	370 0.0	084 0.	.082 8	35 4	57 6.0	0.147	0.18	3 1.48	3	GULLY MK-S	133 324	_	/H11	5	370 (0.082	133	2.477	4.04	375		20	1			0.074				.317 0.	57 0.0	0.1	16 2.97	7 22.	1 22	22.8	824 2	2.81 23	3.141 23	3.412).271 G1/H10
1%	G1/H11	85	1 0.	_	10 29			129 10	06	5 3		_	.122 12	_	49 5.97	9 0.146	0.18	3 1.48	3	GULLY MK-S	129 320	_	/H15	5	370 (0.122	129	2.491	4.02	375		3.21	1		32		3.57	_			54 0.0	0.15	57 2.94	_	_	5 22.5	554 22	2.541 22	2.804 22	2.904	0.1 G1/H1
1%	G1/H12		1 0.								370 0.0	_			56 6.00				3	GULLY MK-S	130 327		/H13	_		0.049	130	6.347	2.36	375		3.26	1		32		3.52 (.247 0.				_	_						0.08 G1/H1
1%	G1/H13	85	1 0.	77 1	10 29	94 0	0.219 0.	212 17	73	5 3	370 0.2	203 0.	.199 2	04 5	531	0.13		0.2	2.98	SAG MK-S	127 404	G'				0.199	_		3.48	375	1.15	_	1		G2		3.6			.242 0.	_		_		_	_	_	2.239 22	_		1.125 G1/H1
1%	2/H13	0	-		. —					_										MH1050	1					0.229	157	12.94	2.94	375	_		0				1.78 (_			.8 0.1										.385 2/H13
1%	G1/H14		1 0.	_				_		_	_	_		-	_	3 0.075	_	_	1.76	GULLY MK-S	31 0	_	/H16	-		0.03	31	7.219	1.11	375	_	2.56	1		G2		4.77	_		.019 0.				_	_	-		_		_	1.365 G1/H14
1%	G1/H15		1 0.	_	_	_	0.133 0.				370 0.1	_		-	_	_	_	_	_	GULLY MK-S	161 283		_	_		0.121			3.05	375	1.45		1			0.108		_		.366 0.	_	_	_	_		_	_	1.951 22		_	.003 G1/H1
1%	G1/H16		1 0.	_	_	_		_		_		137 0.		$\overline{}$	42 5.52		_	_		GULLY MK-S	193 349	_	/H18	_		0.134	193	11.042	3.62	375		3.49	1				3.27	_			21 0.1		_		_	_				_	.054 G1/H10
1%	G1/H17		1 0.				0.161 0.	_						_	33 4.93		_	_	3	GULLY MK-S	177 257	_	/H20				177		4.75	375	1.6	3.6	1		32		3.15	_		1.412 1.0					_	_					0.001 G1/H1
1%	G1/H18		1 0.	_								003 0.			22 8.30				3	GULLY BK-S	8 313	_		_	_	0.000	8		0.66	375	0.08		1		32		3.67 (0.001 (0.00			_	_					0.001 G1/H18
1%	G2/H18		1 0.	_		_	0.023 0.		-				0.02 2	-	70 6.62		_	_		GULLY MK-S	51 319		/H18	_		0.023	59	22.616	0.71	375	0.54		0.86		/T10		2.51 (.039 0.				6 19.1						0.43	0 G2/H18
1%	G1/H19		1 0.	_		_	0.015 0.		-	-	_			-	28 3.55			_	3	GULLY MK-S	78 250	_	/H21	-			78		2.39	375	_	3.58	1		32		3.17	_			.2 0.0	-		_	_	-	_				0 G1/H19
1%	G1/H20	85	1 0.	// 1	10 29	_	0.109 0.	_		5 3			.099 10			_	_	3.79	3	GULLY MK-S	80 278	_		_			80	2.297	2.61	375	0.73		1		32	0.027				.086 0.	_	_	_	_							0 G1/H20
1%	F1/H21	0					0	0 (0		0	0	0 (0 8	00	0.2	+-		-	RSIP-9x9	267 533	L	DST	1	506	0	267	29.214	1.03	450	1.68	2.94	1		32	0.144	3.94 (0.566	(.566 0.	88 0.2	256 0.3	41 2.06	6 16.5	5 16.2	2 17.2	256			_	.678 F1/H2
1%	OUT/H21																			HW outlet																													17 17	7.212	OUT/H2


STORMWATER DRAINAGE CALCULATIONS - MAJOR 1% AEP

(INCLUDING 20% ABOVE STANDARD 1% AEP INTENTIES FOR CLIMATE CHANGE)









BIO RETENTION PARTICLE SIZE DISTRIBUTION AND PROPERTIES GUIDE:

(SOURCE: BIOFILTRATION MEDIA GUIDELINES (VERSION 3.01), PREPARED BY THE FACILITY FOR ADVANCING WATER BIOFILTRATION (FAWB), JUNE 2009.)

MATERIAL COMPOSITION RANGE GUIDE:

CLAY AND SILT	<3%	(<0.05mm)
VERY FINE SAND	5-30%	(0.05-0.15mm)
FINE SAND	10-30%	(0.15-0.25mm)
MEDIUM TO COARSE SAND	40-60%	(0.25-1.0mm)
COARSE SAND	7-10%	(1.0-2.0mm)
FINE GRAVEL	<3.0%	(2.0-3.4mm)

IT IS ESSENTIAL THAT THE TOTAL CLAY AND SILT MIX IS LESS THAN 3% (w/w) TO REDUCE THE LIKELIHOOD OF STRUCTURAL COLLAPSE OF SUCH SOILS.

SOIL SPECIFICATIONS

- TOTAL NITROGEN CONTENT <1000mg/kg
- ORTHOPHOSPHATE CONTENT <80mg/kg SOILS WITH TOTAL PHOSPHORUS CONCENTRATIONS > 100mg/kg SHOULD BE TESTED FOR POTENTIAL LEACHING. WHERE PLANTS WITH MODERATE PHOSPHORUS SENSITIVITY ARE TO BE USED, TOTAL PHOSPHORUS CONCENTRATIONS SHOULD BE <20mg/kg)
- ORGANIC MATTER CONTENT AT LEAST 3% (w/w). AN ORGANIC CONTENT LOWER THAN 3% IS LIKELY TO HAVE TOO LOW A WATER HOLDING CAPACITY TO SUPPORT HEALTHY PLANT GROWTH. IN ORDER TO COMPLY WITH BOTH THIS AND THE TOTAL NITROGEN AND ORTHOPHOSPHATE CONTENT REQUIREMENTS, A LOW NUTRIENT ORGANIC MATTER WILL BE REQUIRED.
- pH AS SPECIFIED FOR 'NATURAL SOILS AND SOIL BLENDS' 5.5-7.5 (pH 1:5 IN
- ELECTRICAL CONDUCTIVITY AS SPECIFIED FOR 'NATURAL SOILS AND SOIL BLENDS' <1.2 dS/m.

BIO RETENTION INSTALLATION STANDARD NOTES:

THE PLACEMENT OF DRAINAGE, TRANSITION AND FILTER MEDIA LAYERS MUST BE UNDERTAKEN CAREFULLY TO ENSURE CORRECT DEPTH, SLOPE AND COMPACTION

DEPTH: FILTER MEDIA SHOULD BE INSTALLED AND COMPACTED IN TWO LIFTS FOR DEPTHS OVER 500mm.

SLOPE: THE TOP SURFACE OF THE DRAINAGE LAYER, TRANSITION LAYER AND FILTER MEDIA LAYER SHOULD BE FLAT. A SPREADER BAR SHOULD LEVEL THE SURFACE OF EACH LAYER.

COMPACTION: THE FILTER MEDIA MUST BE LIGHTLY COMPACTED DURING INSTALLATION TO PREVENT THE MIGRATION OF FINE PARTICLES. THIS CAN BE ACHIEVED WITH A SINGLE PASS OF A LIGHT ROLLER SUCH AS A DRUM LAWN ROLLER, A VIBRATING PLATE CAN ALSO BE USED TO COMPACT SMALL BIO RETENTION SYSTEMS OR 'POZITRACK' BOBCATS CAN BE USED FOR LARGE SYSTEMS. ENSURE ONLY ONE COMPACTING PASS IS MADE OVER THE MEDIA FOR LIGHT COMPACTION.

CONTRACTOR TO ENSURE BIOFILTRATION FILTER MEDIA MEETS THE CRITERIA OUTLINED IN THE MARCH 2008 VERSION OF THE GUIDELINE SPECIFICATION FOR SOIL MEDIA IN BIORETENTION SYSTEMS (VERSION 2.01), FACILITY FOR ADVANCING WATER BIOFILTRATION

REVISED AS PER COUNCIL

BIO-RETENTION/DETENTION BASINS CONSTRUCTION SEQUENCE AND NOTES:

- ESTABLISH SEDIMENT AND EROSION CONTROL MEASURES IN CATCHMENT, INCLUDING SILT FENCES, SEEDING OF ALLOTMENTS, & FULL WIDTH VERGE TURFING.
- SURVEY BASIN LOCATION
- INSTALL OVERFLOW PIT AND ENSURE PIT CREST IS AT DESIGN LEVEL. THIS PIT CREST WILL THEN BE USED AS A DATUM FROM WHICH OTHER LEVELS WITHIN THE BASIN WILL BE MEASURED. THE PIT REQUIRES HOLES FOR DRAINAGE PIPE CONNECTIONS WHICH CAN BE DRILLED AT THIS STAGE OR AFTER STEP 5 BELOW.
- EXCAVATE SURROUNDING LANDFORM TO DESIGN SUBSOIL LEVEL (ACHIEVING SURROUNDING LEVEL AT THIS STAGE REDUCES THE NEED FOR EARTHWORKS ADJACENT TO THE BASIN AFTER THEY HAVE BEEN
- EXCAVATE BASIN TO DESIGN DEPTH ENSURING BASE OF POD HAS MINIMUM 0.25% GRADE TOWARDS PIT. ENSURE BASE OF BASIN IS FREE FROM DEBRIS.

SUPERINTENDENT INSPECTION AND SIGN OFF REQUIRED BEFORE PROCEEDING

- LINE SYSTEM WITH GEOFABRIC, AND EXTEND GEOFABRIC A MINIMUM OF 500 MM BEYOND TOP OF EXCAVATION. THESE ARE THE FLAPS REFERRED TO IN ITEM 13 BELOW.
- PLACE DRAINAGE LAYER (USING CLEAN 5-7mm AGGREGATE) TO DESIGN LEVEL.
- NOTE THAT CORRECT FUNCTIONING OF THE DRAINAGE PIPES IS CRITICAL TO THE PERFORMANCE OF THE BIORETENTION SYSTEM. DIG TRENCHES IN DRAINAGE LAYER AND PLACE DRAINAGE PIPES. ENSURE PIPES ARE LAID AT MIN 0.5% SLOPE WITH NO LOCALIZED DEPRESSIONS VERIFIED USING LEVEL OR STRING LINE. ALL JOINTS AND JUNCTIONS IN PIPES TO BE SEALED. CONNECT CLEAN OUT POINTS ENSURING TOP OF CLEAN OUT POINTS ARE NOT LESS THAN 50mm BELOW OVERFLOW PIT CREST.

- SUPERINTENDENT INSPECTION AND SIGN OFF REQUIRED BEFORE PROCEEDING.


 10. COVER DRAINAGE PIPES WITH DRAINAGE MEDIA, ENSURING DESIGN COVER.
- PLACE TRANSITION LAYER (USING ONLY PRESCRIBED DRAINAGE MATERIAL: 2.0mm SAND) TO DESIGN LEVEL (REFER DRAWINGS)

SUPERINTENDENT INSPECTION AND SIGN OFF REQUIRED BEFORE PROCEEDING


- 12. PLACE FILTER MEDIA (USING ONLY PRESCRIBED MATERIAL: 0.7mm SAND) TO DESIGN LEVEL (REFER DRAWINGS) SPREAD MATERIAL USING EXCAVATOR BUCKET OR HAND TOOLS TO OBTAIN LIGHT AND EVEN COMPACTION OF FILTER MEDIA DO NOT DRIVE OVER FILTER MEDIA WITH ANY VEHICLE AS EXCESSIVE COMPACTION CAN IMPEDE DRAINAGE THROUGH THE FILTER MEDIA. FILTER MEDIA SURFACE MUST BE LEVEL (HORIZONTAL) AND FREE FROM LOCAL DEPRESSIONS AND SET AT 100mm BELOW PIT CREST (EXCEPT FOREBAY AREA WHICH IS 200mm). AS SOON AS FILTER MEDIA IS PLACED IT MUST BE IMMEDIATELY COVERED WITH A GEOFABRIC COVER WHICH MUST REMAIN IN PLACE AT ALL TIMES EXCEPT WHEN ACCESS TO FILTER MEDIA IS REQUIRED. THIS PROTECTIVE COVER IS ONLY TO BE REMOVED BY LANDSCAPERS IMMEDIATELY PRIOR TO PLANTING.
- LAY EXCESS GEOFABRIC FLAPS FROM BASIN OUTWARD ACROSS ADJACENT SUBSOIL AND PLACE LANDSCAPING TOPSOIL ON TOP OF THIS GEOFABRIC AND AROUND BASIN AS PER DESIGNS.
- INSTALL PROTECTIVE PLYWOOD BARRIERS ENSURING THE CREST IS AT DESIGN LEVEL (MIN 100mm ABOVE ELEVATION OF PIT CREST) AND EXTENDS LATERALLY TO BASIN BATTERS BY 300mm, AND VERTICALLY INTO THE FILTER MEDIA BY 200mm. THIS PLYWOOD BARRIER NEEDS TO REMAIN IN PLACE FOR 12 MONTHS AND PREVENT SEDIMENT LADEN RUNOFF FROM ENTERING THE MAJORITY FOR THE BASIN AREA. AFTER 12 MONTHS ONCE THE VEGETATION IS ESTABLISHED AND THE ALLOTMENT CONSTRUCTION IS COMPLETE THESE PLYWOOD BARRIERS WILL BE TAKEN OUT AND THE SYSTEM BROUGHT ONLINE.
- COVER INLET ZONE WITH PROTECTIVE GEOFABRIC ENSURING GEOFABRIC EXTENDS OVER CREST OF PROTECTIVE PLYWOOD BARRIER. COVER GEOFABRIC WITH MIN 50mm TOPSOIL SUITABLE FOR TURF GROWTH. SIMILAR TO THE PLYWOOD BARRIERS, THIS GEOFABRIC IS A TEMPORARY PROTECTIVE MEASURE TO PROTECT THE FILTER MEDIA IN THE INLET ZONE FROM BEING CLOGGED WITH CONSTRUCTION SEDIMENT, AND WILL BE
- FLUSH DRAINAGE PIPES TO REMOVE ANY INITIAL INGRESS OF MATERIAL AND TO ENSURE ADEQUATE DRAINAGE.


NOTE THAT BETWEEN STEPS 5 - 16 ABOVE THE BASINS WILL BE SUSCEPTIBLE TO STORM DAMAGE. THEREFORE ONCE COMMENCED PODS MUST BE COMPLETED AS SOON AS POSSIBLE TO MINIMISE THE RISK OF STORM

INSPECTION IS REQUIRED IF RAINFALL EVENT OCCURS BETWEEN CONSTRUCTION STEPS 5 - 16 ABOVE.



CLEANOUT POINT DETAIL






LANDINGS

STAGE 23

DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO



LENNIUM

www.egis-group.com

RYAN ASHWORTH

APPROVAL

RPFQ 19674

aa

22-000082_23

BIO-BASIN NOTES AND

DETAILS

1702

ATTACHMENT 4

Appeal Rights

Chapter 6 Dispute resolution

Part 1 Appeal rights

229 Appeals to tribunal or P&E Court

- Schedule 1 states—
 - (a) matters that may be appealed to—
 - (i) either a tribunal or the P&E Court; or
 - (ii) only a tribunal; or
 - (iii) only the P&E Court; and
 - (b) the person—
 - (i) who may appeal a matter (the appellant); and
 - (ii) who is a respondent in an appeal of the matter; and
 - (iii) who is a co-respondent in an appeal of the matter; and
 - (iv) who may elect to be a co-respondent in an appeal of the matter.
- (2) An appellant may start an appeal within the appeal period.
- (3) The appeal period is—
 - (a) for an appeal by a building advisory agency—10 business days after a decision notice for the decision is given to the agency; or
 - (b) for an appeal against a deemed refusal—at any time after the deemed refusal happens; or
 - (c) for an appeal against a decision of the Minister, under chapter 7, part 4, to register premises or to renew the registration of premises—20 business days after a notice is published under section 269(3)(a) or (4); or

- (d) for an appeal against an infrastructure charges notice—20 business days after the infrastructure charges notice is given to the person; or
- (e) for an appeal about a deemed approval of a development application for which a decision notice has not been given—30 business days after the applicant gives the deemed approval notice to the assessment manager; or
- (f) for an appeal relating to the Plumbing and Drainage Act 2018—
 - (i) for an appeal against an enforcement notice given because of a belief mentioned in the *Plumbing and Drainage Act 2018*, section 143(2)(a)(i), (b) or (c)—5 business days after the day the notice is given; or
 - (ii) for an appeal against a decision of a local government or an inspector to give an action notice under the *Plumbing and Drainage Act 2018*—5 business days after the notice is given; or
 - (iii) for an appeal against a failure to make a decision about an application or other matter under the Plumbing and Drainage Act 2018—at anytime after the period within which the application or matter was required to be decided ends; or
 - (iv) otherwise—20 business days after the day the notice is given; or
- (g) for any other appeal—20 business days after a notice of the decision for the matter, including an enforcement notice, is given to the person.

Note-

See the P&E Court Act for the court's power to extend the appeal period.

(4) Each respondent and co-respondent for an appeal may be heard in the appeal.

- (5) If an appeal is only about a referral agency's response, the assessment manager may apply to the tribunal or P&E Court to withdraw from the appeal.
- (6) To remove any doubt, it is declared that an appeal against an infrastructure charges notice must not be about—
 - (a) the adopted charge itself; or
 - (b) for a decision about an offset or refund—
 - the establishment cost of trunk infrastructure identified in a LGIP; or
 - (ii) the cost of infrastructure decided using the method included in the local government's charges resolution.

230 Notice of appeal

- An appellant starts an appeal by lodging, with the registrar of the tribunal or P&E Court, a notice of appeal that—
 - (a) is in the approved form; and
 - (b) succinctly states the grounds of the appeal.
- (2) The notice of appeal must be accompanied by the required fee.
- (3) The appellant or, for an appeal to a tribunal, the registrar, must, within the service period, give a copy of the notice of appeal to—
 - (a) the respondent for the appeal; and
 - (b) each co-respondent for the appeal; and
 - (c) for an appeal about a development application under schedule 1, section 1, table 1, item 1—each principal submitter for the application whose submission has not been withdrawn; and
 - (d) for an appeal about a change application under schedule 1, section 1, table 1, item 2—each principal submitter for the application whose submission has not been withdrawn; and

- (e) each person who may elect to be a co-respondent for the appeal other than an eligible submitter for a development application or change application the subject of the appeal; and
- (f) for an appeal to the P&E Court—the chief executive;
 and
- (g) for an appeal to a tribunal under another Act—any other person who the registrar considers appropriate.

(4) The service period is-

- if a submitter or advice agency started the appeal in the P&E Court—2 business days after the appeal is started; or
- (b) otherwise—10 business days after the appeal is started.
- (5) A notice of appeal given to a person who may elect to be a co-respondent must state the effect of subsection (6).
- (6) A person elects to be a co-respondent to an appeal by filing a notice of election in the approved form—
 - (a) if a copy of the notice of appeal is given to the person—within 10 business days after the copy is given to the person; or
 - (b) otherwise—within 15 business days after the notice of appeal is lodged with the registrar of the tribunal or the P&E Court.
- (7) Despite any other Act or rules of court to the contrary, a copy of a notice of appeal may be given to the chief executive by emailing the copy to the chief executive at the email address stated on the department's website for this purpose.

231 Non-appealable decisions and matters

(1) Subject to this chapter, section 316(2), schedule 1 and the P&E Court Act, unless the Supreme Court decides a decision or other matter under this Act is affected by jurisdictional error, the decision or matter is non-appealable.

- (2) The Judicial Review Act 1991, part 5 applies to the decision or matter to the extent it is affected by jurisdictional error.
- (3) A person who, but for subsection (1) could have made an application under the *Judicial Review Act 1991* in relation to the decision or matter, may apply under part 4 of that Act for a statement of reasons in relation to the decision or matter.
- (4) In this section—

decision includes—

- (a) conduct engaged in for the purpose of making a decision; and
- (b) other conduct that relates to the making of a decision; and
- (c) the making of a decision or the failure to make a decision; and
- (d) a purported decision; and
- (e) a deemed refusal.

non-appealable, for a decision or matter, means the decision or matter—

- (a) is final and conclusive; and
- (b) may not be challenged, appealed against, reviewed, quashed, set aside or called into question in any other way under the *Judicial Review Act 1991* or otherwise, whether by the Supreme Court, another court, any tribunal or another entity; and
- (c) is not subject to any declaratory, injunctive or other order of the Supreme Court, another court, any tribunal or another entity on any ground.

232 Rules of the P&E Court

- A person who is appealing to the P&E Court must comply with the rules of the court that apply to the appeal.
- (2) However, the P&E Court may hear and decide an appeal even if the person has not complied with rules of the P&E Court.

ATTACHMENT 5

Infrastructure Charges Notice

In accordance with the Infrastructure Charges Resolution (No. 10) dated 5 October 2022 or as amended, there is no Infrastructure Charges applicable to the development.